



DIVIDER

**STATE OF NORTH DAKOTA
INFORMATION TECHNOLOGY DEPARTMENT
SFN 2053 (4-2002)**

PU-2451-00-630

**Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement**

Application

Filed 11/21/2000

Closed 1/25/2001

00

Scott, Sandi L.

From: Bauske, Shelly A.
Sent: Monday, August 27, 2001 10:40 AM
To: Scott, Sandi L.
Subject: FW: Money Received.....

-----Original Message-----

From: Geiger, Gloria A.
Sent: Monday, August 27, 2001 10:40 AM
To: Bauske, Shelly A.
Subject: RE: Money Received.....

-----Original Message-----

From: Bauske, Shelly A.
Sent: Monday, August 27, 2001 10:24 AM
To: Geiger, Gloria A.
Subject: Money Received.....

Case No. PU-2451-00-630
Pilgrim Telephone Inc
\$43.65

13 PU-2451-00-630

Pages: 0

\$43.65 received

by Pilgrim Telephone, Inc./Qwest Corporation

08/27/2001

CC: Comm Legal Ilona Jerry

Scott, Sandi L.

From: Bauske, Shelly A.
Sent: Friday, March 09, 2001 10:04 AM
To: Scott, Sandi L.
Subject: Money Received

PU-2441-00-618
Qwest
\$43.65

PU-2442-00-619
Qwest
\$43.65

PU-2443-00-620
Qwest
\$43.65

PU-2445-00-624
Qwest
\$43.64

PU-2448-00-627
Qwest
\$43.64

PU-2447-00-628
Qwest
\$43.64

PU-2451-00-630
Qwest
\$43.64

PU-2422-00-563
Qwest
\$62.21

12 **PU-2451-00-630**

Pages: 0

\$43.64 received

by Qwest Corporation

03/12/2001

CC: Comm Legal Ilona Jerry .

PU-2421-00-562
Qwest
\$62.21

PU-2204-00-590
Qwest
\$45.87

PU-2446-00-629
Qwest
\$43.64

PU-2271-00-589
Qwest
\$45.87

PU-2420-00-560
Qwest
\$62.21

PU-2057-00-588
Qwest
\$45.87

PU-1755-00-580
Qwest
\$45.87

APPROVED

DATE: 2-21-01
KMF

MOTION

February 21, 2001

Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application

Case No. PU-2451-00-630

I move the Commission bill Pilgrim Telephone, Inc. and Qwest Corporation for costs incurred to date in Case No. PU-2451-00-630, Pilgrim Telephone, Inc./Qwest Corporation, Interconnection Agreement, Application.

11

PU-2451-00-630

Pages: 3

Utility Valuation Motion/Letter/Billing
Statement
by Public Service Commission

02/21/2001

CC: Comm Legal Illona Jerry .



Public Service Commission
State of North Dakota

600 E Boulevard Ave. Dept. 408
Bismarck, North Dakota 58505-0480
e-mail: sab@oracle.psc.state.nd.us
TDD 800-366-6888
Fax 701-328-2410
Phone 701-328-2400

COMMISSIONERS

Bruce Hagen
President
Susan E. Wefald
Leo M. Reinbold

February 21, 2001

Executive Secretary
Jon H. Mielke

Stan Kugell
Pilgrim Telephone Inc
1 Kendall Square
Cambridge MA 02139

Dan Kuntz
PO Box 1695
Bismarck ND 58502-1695


RE: Case No. PU-2451-00-630
Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application

Enclosed is a copy of the statement approved at the February 21, 2001 Public Service Commission meeting for the expenses incurred to date in Case No. PU-2451-00-630.

Under N.D.C.C. 49-21-01.7, these expenses are billed through the Valuation Fund and must be paid for by the telecommunications company involved.

Please make your check payable to the Public Service Commission.

Sincerely,


Gloria Geiger
Administrative Assistant
701-328-2401

Enc.

c: Scott Macintosh
Qwest Corporation
PO Box 5508

Director - Interconnection Compliance
Qwest Corporation
1801 California St Rm 2410
Denver CO 80202

Post-it® Fax Note	7671	Date	6/22/01	# of pages	2
To	Stan Kugell		From	Jerry Lein	
Co./Dept.	Pilgrim Telephone		Co.	ND PSC	
Phone #	617 225-7000		Phone #	701 328-1035	
Fax #	617 225-0035		Fax #	701 328-2410	

Billing Statement

February 21, 2001

Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application

Case No. PU-2451-00-630

Expenses Incurred to Date:

Advertising Costs	\$87.29
-------------------	---------

Amount Due:

Pilgrim Telephone, Inc.	\$43.65
Qwest Corporation	\$43.64

Send Payment To:

Public Service Commission
600 E Boulevard Ave Dept 408
Bismarck ND 58505-0480

Federal Tax ID 45-0309764

STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION

Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application

Case No. PU-2451-00-630

AFFIDAVIT OF SERVICE BY CERTIFIED MAIL AND ORDINARY MAIL

STATE OF NORTH DAKOTA
COUNTY OF BURLEIGH

Sharon Helbling deposes and says that:

she is over the age of 18 years and not a party to this action and, on the **25th day of January, 2001**, she deposited in the United States Mail, Bismarck, North Dakota, **three** envelopes with certified postage, return receipt requested, fully prepaid, securely sealed and each containing a photocopy of:

Order

The envelopes were addressed as follows:

Dan Kuntz
P O Box 1695
Bismarck ND 58502-1695

Cert. No. 7000 0520 0022 8654 0230

John Munn
Qwest Corporation
1801 California St Rm 5100
Denver CO 80202

Cert. No. 7000 0520 0022 8654 0247

Stan Kugell
Pilgrim Telephone Inc
1 Kendall Square
Cambridge MA 02139
Cert. No. 7000 0520 0022 8654 0322

Sharon Helbling further deposes and says that on the **25th day of January, 2001**, she deposited in the United States Mail, Bismarck, North Dakota, **two** envelopes by regular mail, with postage fully prepaid, securely sealed, each containing a photocopy of the same.

Scott Macintosh
Qwest Corporation
P O Box 5508
Bismarck ND 58502-5508

Dir-Interconnection Compliance
Qwest Corporation
1801 California St Rm 2410
Denver CO 80202

Each address shown is the respective addressee's last reasonably ascertainable post office address.


Subscribed and sworn to before me
this **25th day of January, 2001.**

Sharon Hebling

Sandra L Scott

Notary Public

SEAL



PU-2451-00-630

Copies To:

State Library (8 copies)

Historical Society

Associated Press

APPROVED

MOTION

DATE: 1-24-01
KME

January 24, 2001

**Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application**

Case No. PU-2451-00-630

I move the Commission adopt the Order Approving Interconnection Agreement in the application of Qwest Corporation for approval of an interconnection agreement negotiated with Pilgrim Telephone, Inc., Case No. PU-2451-00-630.

JRL/sdh

**STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION**

**Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application**

Case No. PU-2451-00-630

ORDER APPROVING INTERCONNECTION AGREEMENT

January 24, 2001

On November 21, 2000, Qwest Corporation (Qwest) filed an applications for approval of an interconnection agreement negotiated with Pilgrim Telephone, Inc. Qwest states this agreement is the same as a previously approved interconnection agreement with New Edge Networks, Inc. The agreement includes rates, terms and conditions for interconnection of facilities including access to unbundled network elements and services for resale.

This agreement was filed under Section 252(e) of the Telecommunications Act of 1996 (Act). The Act requires that any agreement adopted by negotiation or arbitration be submitted for approval to the Commission. Under section 252(e)(2)(A), the Commission may only reject an agreement (or portion thereof) adopted by negotiation if it finds that:

1. the agreement (or portion thereof) discriminates against a telecommunications carrier that was not a party to the agreement;
2. the implementation of the agreement (or portion thereof) is not consistent with the public interest, convenience, and necessity.

In addition, the Commission may include in its review state requirements that do not constitute barriers to entry under section 253. Section 252(e)(4) requires that the Commission must act to approve or reject an agreement adopted by negotiation within ninety (90) days after submission by the parties.

On November 22, 2000, the Commission issued a Notice of Opportunity to File Written Comments, which provided that the Commission would receive written comments on the agreement until December 26, 2000. No comments have been received.


The Commission has reviewed the agreement and finds that it has not been shown to discriminate against a telecommunications carrier that was not a party to the agreement. The Commission further finds that implementation of the agreement has not been shown to be inconsistent with the public interest, convenience and necessity.


Order

The Commission orders:

1. The interconnection agreement negotiated between Qwest Corporation and Pilgrim Telephone, Inc., filed with the Commission on November 21, 2000, is APPROVED.
2. The Commission retains continuing jurisdiction over the agreement at all times.
3. Notice of any changes to the agreement must be filed promptly with the Commission.
4. The agreement must not be assigned, assumed or otherwise transferred without the approval of the Commission.
5. Each party to the agreement shall respond reasonably and in good faith to the other party's requests to implement the agreement.

PUBLIC SERVICE COMMISSION



Anthony T. Clark
Commissioner


Susan E. Wefald
President


Leo M. Reinbold
Commissioner

Affidavit of Publication

State of North Dakota)
County of Burleigh)



Laurie Thiel, being duly sworn, state as follows:

1. I am the designated agent, under the provisions and for the purposes of, Section 31-04-06, NDCC, for the newspapers listed on the attached exhibits.
2. The newspapers listed on the exhibits published the advertisement of:
AT & T - Pilgrim, 1 time(s)
as required by law or ordinance.
3. All of the listed newspapers are legal newspapers in the State of North Dakota and, under the provisions of Section 46-05-01, NDCC, are qualified to publish any public notice or any matter required by law or ordinance to be printed or published in a newspaper in North Dakota.

Signed: [Signature]

Subscribed and sworn to before me this 19th day of December A.D. 2000

[Signature]

- 6 **PU-2441-00-618** Pages: 11
Affidavit of Publication
- 6 **PU-2442-00-619** Pages: 11
Affidavit of Publication
- 6 **PU-2443-00-620** Pages: 11
Affidavit of Publication
- 6 **PU-2445-00-624** Pages: 11
Affidavit of Publication
by North Dakota Advertising Service, Inc.

- 6 **PU-2448-00-627** Pages: 11
Affidavit of Publication
- 6 **PU-2447-00-628** Pages: 11
Affidavit of Publication
- 6 **PU-2446-00-629** Pages: 11
Affidavit of Publication
by North Dakota Advertising Service, Inc.
- 7 **PU-2451-00-630** Pages: 11
Affidavit of Publication
by North Dakota Advertising Service, Inc.

Notice of Opportunity To File Written
Comments

December 6, 2000

Case No. PU - 2451-00-630

Gamestown -	12-13
Minot	12-13
Valley City	12-15
Wahpeton	12-15
Williston	12-15
Bismarck	12-13
Devils Lake	12-15
Dickinson	12-15
Fargo	12-18
Grand Forks	12-13

Scott Macintosh
Qwest Corporation
P O Box 5508
Bismarck ND 58502-5508


Dir-Interconnection Compliance
Qwest Corporation
1801 California St Rm 2410
Denver CO 80202


Walter E Steimel Jr Esq
Greenberg Traurig LLP
800 Connecticut Ave NW Ste 500
Washington D C 20006

Doris Franklin
Maxcess Inc
315 S Calhoun Ste 314
Tallahassee FL 32301

Each address shown is the respective addressee's last reasonably ascertainable post office address.

Subscribed and sworn to before me
this **7th day of December, 2000.**





Notary Public

SEAL

SANDRA L. SCOTT
Notary Public, STATE OF NORTH DAKOTA
My Commission Expires JUNE 11, 2004

STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION

**AT&T Communications of the Midwest, Inc./Qwest
Interconnection Agreement Amendment
Application** **Case No. PU-2441-00-618**

**New Edge Network, Inc./Qwest Corporation
Interconnection Agreement Amendments
Application** **Case No. PU-2442-00-619**

**NewPath Holdings, Inc./Qwest Corporation
Interconnection Agreement Amendment
Application** **Case No. PU-2443-00-620**

**New Acess Communications, LLC/Qwest
Interconnection Agreement
Application** **Case No. PU-2445-00-624**

**DSLnet Communications, LLC/Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2448-00-627**

**Maxcess, Inc./Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2447-00-628**

**Choctaw Communications, Inc./Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2446-00-629**

**Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2451-00-630**

AFFIDAVIT OF SERVICE BY ORDINARY MAIL OR E-MAIL

STATE OF NORTH DAKOTA
COUNTY OF BURLEIGH

Sharon Helbling deposes and says that:

she is over the age of 18 years and not a party to this action and, on the **7th day of December, 2000**, she deposited in the United States Mail, Bismarck, North Dakota, envelopes by first class mail, fully prepaid, securely sealed, each containing a photocopy of:


Notice of Opportunity to File Written Comments


The envelopes were addressed as follows:

See Attached List

Each address shown is the respective addressee's last reasonably ascertainable post office address.

Subscribed and sworn to before me
this **7th day of December, 2000**.





Notary Public

SEAL



envelopes with certified postage, return receipt requested, fully prepaid, securely sealed and each containing a photocopy of:

Notice of Opportunity to File Written Comments

The envelopes were addressed as follows:

Dan Kuntz
P O Box 1695
Bismarck ND 58502-1695

Cert. No. 7099 3400 0014 4513 6323

Steven C Clay President
New Access Communications Inc
310 4th Ave Ste 900
Minneapolis MN 55415
Cert. No. 7099 3400 0014 4513 6309

Dan Webb
Maxcess Inc
100 W Lucerne Circle Ste 500
Orlando FL 32801
Cert. No. 7099 3400 0014 4513 6286

Stan Kugell
Pilgrim Telephone Inc
1 Kendall Square
Cambridge MA 02139
Cert. No. 7099 3400 0014 4513 6262

Rob McMillin
New Edge Network Inc
3000 Columbia House Blvd
Vancouver WA 50322
Cert. No. 7000 0520 0022 8653 2853

John Munn
Qwest Corporation
1801 California St Rm 5100
Denver CO 80202
Cert. No. 7099 3400 0014 4513 6316

John J Withington
DSLnet
545 Long Wharf Dr 5th Fl
New Haven CT 06511
Cert. No. 7099 3400 0014 4513 6293

Seth Block
Choctaw Communications Inc
8700 S Gessner Rd
Houston TX 77074
Cert. No. 7099 3400 0014 4513 6279

Christine Schwartz
AT&T
1875 Lawrence St Rm 10-74
Denver CO 80202
Cert. No. 7000 0520 0022 8653 2846

Mick Herke
NewPath Holdings Inc
4364 Northwest 114th St
Des Moines IA 50322
Cert. No. 7000 0520 0022 8653 2860

Sharon Helbling further deposes and says that on the **7th day of December, 2000**, she deposited in the United States Mail, Bismarck, North Dakota, **four** envelopes by regular mail, with postage fully prepaid, securely sealed, each containing a photocopy of the same.

wahlgren@rus.usda.gov
Wayne Ahlgren

bberkenpas@mc usa.com
Barb Berkenpas

wbrudvik@ohnstadlaw.com
William Brudvik

donlee@martin-associates.com
Don Lee

jxpet23.uswest.com
Janis Peterson

lisestrom@dwt.com
Lise Strom

harumiyamamoto@dwt.com
Harumi Yamamoto

ruth.holder@teligent.com
Ruth Holder

nlarsen@nvc.net
Clint Hanson
Accent Communications Inc
235 E 1st Ave
Groton SD 57445

jlchapman@acomminc.com
Jerry Chapman
Acomm Inc
510 1st Ave N Ste 203
Minneapolis MN 55403-0343

smassey@bepc.com
Sheryl Massey
Basin Electric Power Coop
1717 E Interstate Ave
Bismarck ND 58501-0564

jtmgr@bektel.com
Jerome Tishmack
BEK Communications Cooperative
PO Box 230
Steele ND 58482-0230

jtmgr@bektel.com
Jerome Tishmack
BEK Communications I Inc
PO Box 230
Steele ND 58482-0230

ken@staff.ctctel.com
L Dan Wilhelmson
Consolidated Comm Networks Inc
PO Box 1077
Dickinson ND 58601-1077

ken@staff.ctctel.com
L Dan Wilhelmson
Consolidated Telcom Inc
PO Box 1077
Dickinson ND 58601-1077

ken@staff.ctctel.com
L Dan Wilhelmson
Consolidated Telephone Cooperative
PO Box 1077
Dickinson ND 58601-1077

drtc@drtel.net
Darren Moser
Dickey Rural Telephone Cooperative
PO Box 69
Ellendale ND 58436-0069

glenn.richards@shawpittman.com
Glenn Richards
Glenn Richards
ShawPittman
2300 N St NW

rlaqua@rrv.net
Ronald Laqua
Halstad Telephone Company
PO Box 55
Halstad MN 56548-0055

dclark@hq.idt.net
Diane Clark
IDT America, Corp.
520 Broad St 7th Fl
Newark NJ 07102

kander@ictc.com
Keith Anderson
Inter-Community Telephone Co. II
PO Box 8
Nome ND 58062-0008

nschmid@acginc.net
Neil Schmid
Ionex Communications North Inc
5710 LBJ Frwy Ste 215
Dallas TX 75240

Michel.Murray@MCI.com
Michel Murray
MCI WorldCom Inc
707 17th St Ste 3600
Denver CO 80202

john_sullivan@cable.comcast.com
John Sullivan
McLeodUSA

meredith.giff@gecapital.com
Meredith Gifford
GE Capital Comm Services Corp
6540 Powers Ferry Rd
Atlanta GA 30339

cooperstown@mlgc.com
Ray Brown
Griggs County Telephone Company
Cooperstown ND 58425

hold@texas.net
Dana Wilson
Home Owners Long Distance Inc
8647 Wurzbach Rd #M-1
San Antonio TX 78240-1245

kander@ictc.com
Keith Anderson
Inter-Community Telephone Co
PO Box 8
Nome ND 58062-0008

itci@means.net
Bruce Reuber
Interstate Telcom Consulting Inc
130 Birch Ave W
Hector MN 55342-0668

skat@means.net
Steven Katka
Loretel Systems Inc
13 E 4th Ave
Ada MN 56510

skillebrew@deltacom.com
Sharon Killebrew
McLeodUSA

wheaston@mcleodusa.com
William Heaston
McLeodUSA
P O Box 3177
Cedar Rapids IA 52406-3547

STATE OF NORTH DAKOTA

PUBLIC SERVICE COMMISSION

AT&T Communications of the Midwest, Inc./Qwest Interconnection Agreement Amendment Application	Case No. PU-2441-00-618
New Edge Network, Inc./Qwest Corporation Interconnection Agreement Amendments Application	Case No. PU-2442-00-619
NewPath Holdings, Inc./Qwest Corporation Interconnection Agreement Amendment Application	Case No. PU-2443-00-620
New Acess Communications, LLC/Qwest Interconnection Agreement Application	Case No. PU-2445-00-624
DSLnet Communications, LLC/Qwest Corporation Interconnection Agreement Application	Case No. PU-2448-00-627
Maxcess, Inc./Qwest Corporation Interconnection Agreement Application	Case No. PU-2447-00-628
Choctaw Communications, Inc./Qwest Corporation Interconnection Agreement Application	Case No. PU-2446-00-629
Pilgrim Telephone, Inc./Qwest Corporation Interconnection Agreement Application	Case No. PU-2451-00-630

AFFIDAVIT OF SERVICE BY CERTIFIED MAIL AND ORDINARY MAIL

STATE OF NORTH DAKOTA
COUNTY OF BURLEIGH

Sharon Helbling deposes and says that:

she is over the age of 18 years and not a party to this action and, on the **7th day of December, 2000**, she deposited in the United States Mail, Bismarck, North Dakota, **ten**

6 **PU-2451-00-630** Pages: 17

Affidavits of Service

by Public Service Commission

12/07/2000

CC: Comm Legal Ilona Jerry

amy.ibis@dtg.com
Amy Ibis
McLeodUSA
140 North Phillips Ave Ste 404
Sioux Falls SD 57104-6711

sbunn@mlgc.com
Shelie Bunn
Moore & Liberty Telephone Co
Enderlin ND 58027

dhill@ndarec.com
Dennis Hill
ND Assn Rural Electric Coops
PO Box 727
Mandan ND 58554-0727

lclemens@nft.net
Larry Clemens
Noonan Farmers Tele Co
Noonan ND 58765

cajuul@norstan.com
Cathy Juul
Norstan Network Services Inc
P O Box 5715
Minnetonka MN 5534333-57

klund@nccray.com
Kenneth Lund
Northwest Communications Corp
PO Box 38
Ray ND 58849-0038

jram@erols.com
John Ramsey
Parcel Consultants Inc
150 Commerce Rd
Cedar Grove NJ 07009

ddunning@polarcomm.com
David Dunning
Polar Telcom Inc
PO Box 270
Park River ND 58270-0270

gerrya@midriv .com
Gerry Anderson
Mid-Rivers Telephone Coop Inc
PO Box 280
Circle MT 59215-0280

hfuglest@ndarec.com
Harlan Fugelsten
ND Assn Rural Electric Coops
PO Box 727
Mandan ND 58554-0727

pschaner@ndarec.com
Patti Schaner
ND Assn Rural Electric Coops
PO Box 727
Mandan ND 58554-0727

rer@norlight.com
Robert E Rogers
NorLight Inc
275 N Corporate Dr
Brookfield WI 53045

pagnnda@btigate.com
Patricia Gisinger
North Dakota Telephone Assoc
PO Box 2614
Bismarck ND 58502-2614

royce@restel.net
Royce Aslakson
Parcel Consultants Inc
150 Commerce Rd
Cedar Grove NJ 07009

ddunning@polarcomm.com
David Dunning
Polar Commun Mut Aid Corp
PO Box 270
Park River ND 58270-0270

ddunning@polarcomm.com
David Dunning
Polar Telecommunications Inc
PO Box T
Park River ND 58270

jvonduyke@phoneforall.com
Jeff Walker
Preferred Carrier Services Inc
14681 Midway Rd Ste 105
Dallas TX 75244

pam@tnics.com
Pamela Harrington
RC Communications Inc
PO Box 197
New Effington SD 57255-0197

ardondoran@rrt.net
Ardon Doran
Red River Telecom Inc
PO Box 136
Abercrombie ND 58001-0136

mbrestel@ndak.net
Marcia Burckhard
Reservation Telephone Cooperative
Parshall ND 58770

warrenlh@srttel.com
Warren Hight
Souris River Tele Coop
PO Box 2027
Minot ND 58702-2027

stevedl@srttel.com
Steve Lysne
SRT Communications Inc
P O Box 789
Minot ND 58702-0789

janehp@srttel.com
Jane Petersen
SRT Communications Inc
P O Box 789
Minot ND 58702-0789

kimrw@srttel.com
Kim Weydahl
SRT Communications Inc
P O Box 789
Minot ND 58702-0789

protel@citil: com
Scott Lee
Protel Advantage Inc
1144 Larpenteur Ave W
St Paul MN 55113-6317

ardondoran@rrt.net
Ardon Doran
Red River Rural Tele Assoc
PO Box 136
Abercrombie ND 58001

jdbtbb@ndak.net
Jan Boschee
Reservation Telephone Cooperative
Parshall ND 58770

pam@tnics.com
Pamela Harrington
Roberts Cty Tele Coop Assoc
New Effington SD 57255

suelh@srttel.com
Sue Hamilton
SRT Communications Inc
P O Box 789
Minot ND 58702-0789

christm@srttel.com
Chris Morsefield
SRT Communications Inc
P O Box 789
Minot ND 58702-0789

johnar@srttel.com
John Reiser
SRT Communications Inc
P O Box 789
Minot ND 58702-0789

mdickers@state.nd.us
Marcy Dickerson
State Tax Department
State Capitol
Bismarck ND 58505

grndelec@iw.net
Darrell Henderson
Stateline Telecomm Inc
PO Box 39
Bison SD 57620-0039

clarson@teleg p.com
Caroline Larson
Telegroup Inc
2098 Nutmeg Ave
Fairfield IA 52556

bgreene@magicnet.net
Barbara Greene
Telephone Co of Central Florida Inc
3599 W Lake Mary Blvd Ste E
Lake Mary FL 32746-3417

thomasc@totaltel.com
Tom Carroll
TotalTel Inc
150 Clove Rd 8th Fl
Little Falls NJ 07424

bpipkin@touch1.com
Leigh Ann Wooten
Touch 1 Long Distance Inc
100 Brookwood Rd
Atmore AL 36502

maryg@uslink.net
Mary Goodman
U S Link Inc
200 2nd St
Pequot Lakes MN 56472

lahall@usgs.gov
Lenora Hall
U S Geological Survey

kjvannin@usgs.gov
K Vannin
U S Geological Survey

afranklin@us-south.net
Anne Franklin
U S South Communications Inc
250 Williams St Ste 2360
Atlanta GA 30303

ralyana@uswest.com
Richard Alyanak
U S WEST

kblicke@uswest.com
Kent Blickensderfer
U S WEST Communications Inc
PO Box 5508
Bismarck ND 58502-5508

smacint@uswest.com
Scott Macintosh
U S WEST Communications Inc
PO Box 5508
Bismarck ND 58502-5508

jmunnn@uswest.com
John Munn
U S WEST Communications Inc
1801 California Rm 5100
Denver CO 80202

saberry@uswest.com
Sharon Berry
U S WEST Communications Inc
409 1st Ave N
Fargo ND 58102-4802

sschwan@uswest.com
Suzy Schwandt
U S WEST Communications Inc.
P O Box 5508
Bismarck ND 58502-5508

johng@unidial.com
John Greive
UniDial Communications Inc
1901 Eastpoint Pkwy
Louisville KY 40223

kander@ictc.com
Keith Anderson
Valley Communications Inc
P O Box 8
Nome ND 58062

tsusak@vocal n
Tony Susak
VoCall Communications Corp
284 Sheffield St
Mountainside NJ 07092

bonniek@westriv.com
Bonnie Krause
West River Telecomm Coop
PO Box 467
Hazen ND 58545-0467

pihland@means.net
Paul Ihland
Wolverton Telephone Company
Wolverton MN 56594

Myer Shark
2277 Gene Autry Trail Unit C
Palm Springs CA 92264

Ann Faught
Absaraka Co-op Tele Co
Absaraka ND 58002

Mark Waind
Altru Health System
1200 South Columbia Rd
Grand Forks ND 58201

Arch Paging
11437 Valley View Rd
Eden Prairie MN 55344

Jack Medaris
Atlas Communications LTD
484 Norristown Rd Ste 123
Blue Bell PA 19422

Jennifer Whitley
Business Discount Plan Inc
3780 Kilroy Arpt Wy
Long Beach CA 90806

Scott Geston
Cable One of Fargo
P O Box 10624
Fargo ND 58106-0624

Robert Fallan
Coast International
14303 W 95th St
Lenexa KS 66215-5210

Molli Harper
Commnet Cellular Inc
8350 E Crescent Pkwy Ste 400
Englewood CO 80111

Elaine McHale
Concert Communications Sales LLC
295 N Maple Ave Rm 5463A2
Basking Ridge NJ 07920

Myer Shark
Knollwood Place Apts #221
3630 Phillips Pkwy
St Louis Park MN 55426

ACN Communications Services Inc
32991 Hamilton Ct
Farmington Hills MI 48334

John Summers
AmeriTel Pay Phones Inc
8201 Tristar Dr
Irving TX 75063-2816

Leeann Brunnette
AT&T
321 E Walnut St
Des Moines IA 50309

Dorothy Jones
Bell Atlantic Communications Inc
1320 N Courthouse Rd 9th Fl
Arlington VA 22201

John Session
Cable & Wireless Comm Inc
8219 Leesburg Pike
Vienna VA 22182

Choctaw Communications Inc
1600 Viceroy
Dallas TX 75235

Comcast Telecommunications
1500 Market St
Philadelphia PA 19102

Murray Barr
Competitive Strategies Group Inc
70 East Lake St 7th Fl
Chicago IL 80112

D D D Calling Inc
5120 Woodway Ste 8020
Houston TX 77056

Robert Hill
Dakota Central Tele Coop
PO Box 299
Carrington ND 58421-0299

Robert Hill
Dakota Central Telecom I
PO Box 299
Carrington ND 58421-0299

Dickey Rural Communications Inc
PO Box 69
Ellendale ND 58436-0069

DSLnet Communications LLC
545 Long Wharf Dr
New Haven CT 06511

Easton Telecom Services Inc
4646 W Streetsboro
Richfield OH 44286

Excel Communications Inc
8750 N Central Expswy Ste 2000
Dallas TX 75231

Lawrence Freedman
Fleischman & Walsh
1400 16th ST NW
Washington DC 20036

Framco Inc
P O Box 2711
Fargo ND 58108

Ronald Rodemerk
Frontier Comm International
180 S Clinton Ave
Rochester NY 14646-0500

Craig Brewerton
Geo Economics
PO Box 4272
Missoula MT 59806-4272

Lucille Nilson
Griggs County Telephone Company
Cooperstown ND 58425

Group Long Distance Inc
6600 N Andrews Ave Ste 140
Ft Lauderdale FL 33309

HJN Telecom Inc
3235 Satellite Blvd Bldg 400 Ste 300
Duluth GA 30096

IdeaOne Telecom Group LLC
3239 39th St SW
Fargo ND 58104

Lance Sentman
International Telcom Ltd
417 2nd Ave W
Seattle WA 98119

Sue Weiske
Ionex Communications North Inc
5710 LBJ Frwy Ste 215
Dallas TX 75240

Nanette Edwards
ITC DELTACOM INC
4092 Memorial Pkwy SW
Huntsville AL 35802-1382

Larry Barnes
IXC/SSC-Regulatory Affairs
1122 S Capital of TX Hwy
Austin TX 78746-6426

Katherine E Ford
U S WEST
1801 California St Ste 5100
Denver CO 80202

Thomas K Crowe
Law Offices of Thomas K Crowe PC
2300 M St NW Ste 800
Washington DC 20037

LCI International Telecom Corp
4650 Lakehurst Ct
Dublin OH 43017

Level 3 Communications LLC
3555 Farnam St
Omaha NE 68131

Marilyn Foss
MCI WorldCom Inc
707 17th St Ste 3600
Denver CO 80202

McLeodUSA
P O Box 3177
Cedar Rapids IA 52406-3177

Midcontinent Communications
410 South Phillips Ave
Sioux Falls SD 57104

Gordon Wilhelmi
Midstate Communications Inc
PO Box 400
Stanley ND 58784-0400

Minnesota Independent Equal Access
Corp
10300 6th Avenue N
Plymouth MN 55441

MVX Communications LLC
100 Rowland Way Ste 145
Novato CA 94945

Richard Thronson
Nemont Telephone Cooperative Inc
Scobey MT 59263

Net-tel Corporation
1023 31st St NW
Washington DC 20007

LDM Systems Inc
430 Park Ave 5th Fl
New York NY 10022

Jan Lowe
Long Dist Consolidated Billing Co
145 S Livernois Rd #199
Rochester MI 48307-1837

MCImetro Access Transmission Services
1801 Pennsylvania Ave NW
Washington DC 20006

Carolyn Fodor
MIDCOM Communications Inc
26913 Northwestern Hwy #165
Southfield MI 48034

Mid-Rivers Telephone Coop Inc
P O Box 280
Circle MT 59215

Mark Wilhelmi
Midstate Telephone Co
PO Box 400
Stanley ND 58784-0400

Mike Strand
MITS
PO Box 5237
Helena MT 59604-5237

Dave Crothers
NDATC
Box 1144
Mandan ND 58554-1144

Sharon Meinhart
NetLogix Telecom Inc
501 Bath St
Santa Barbara CA 93101

Sandra Adams
NewPath Holdings Inc
4364 114th St
Des Moines IA 50322

Nextel West Corp
2001 Edmund Halley Dr
Reston VA 20191-3436

Holly Sasscer
Operator Communications Inc
3530 Forest Ln Ste 200
Dallas TX 75234-7910

Pamcomm
P O Box 5200
Sioux Falls SD 57117-5200

Primus Telecommunications Inc
1700 Old Meadow Rd 3rd Fl
McLean VA 22102

Quintelco Inc
1 Blue Hill Plaza
Pearl River NY 10965

Dean Polkow
RCC Network Inc
PO Box 2000
Alexandria MN 56308-2000

Gene Sloan
Reservation Telephone Cooperative
Parshall ND 58770

Skyland Technologies Inc
P O Box 5237
Helena MT 59604-5237

Andrew Jones
Sprint
8140 Ward Pkwy Flr 5E
Kansas City MO 64114

Randy Burckhard
SRT Communications Inc
P O Box 789
Minot ND 58702-0789

Dave Dirck
North Dakota Telephone Company
PO Box 180
Devils Lake ND 58301-0180

Patrick Delaney
Overlook Communications International
1325 North Meadow Pkwy #S110
Roswell GA 30076

Bryan Engle
Parcel Consultants Inc
150 Commerce Rd
Cedar Grove NJ 07009

Jan Sebby
Pringle and Herigstad P C
PO Box 1000
Minot ND 58702-1000

Heather Troxell
Qwest Communications Corporation
4250 Fairfax Dr
Arlington VA 22203

RCN Long Distance Company
105 Carnegie Ctr
Princeton NJ 08540

Sandra Adams
NewPath Holdings Inc
4364 114th St
Des Moines IA 50322

Lisa Dabkowski
SNET America Inc
6 Devine St 1st Fl
North Haven CT 06743

SRT Communications Inc
P O Box 789
Minot ND 58702-0789

Harris Saele
T P C Inc
PO Box 180
Devils Lake ND 58301-0180

Target Telecom Inc
1515 S Federal Hwy Ste 400
Boca Raton FL 33432-7451

Jack Medaris
Telco Partners Inc
484 Norristown Rd Ste 123
Blue Bell PA 19422

Tele-Tech Inc
2900 W 11th St
Sioux Falls SD 57104-3660

T-Netix Inc
67 Inverness Drive E
Englewood CO 80112

Charles Steese
U S WEST
1801 California St Ste 5100
Denver CO 80202

Dick Boyer
U S West Interprise America Inc
1999 Bdwy Rm 700
Denver CO 80202

Sam Billingsley
United States Advanced Network Inc
3000 Nrothwoods Pkwy Ste 140
Norcross GA 30071

Dennis Houston
Universal Network Services of ND
1572 North Batavia St Ste 1A
Orange CA 92867

USBG Inc
5601 W 120th St
Alsip IL 60658

Randy Houdek
Venture Communications Inc
PO Box 157
Highmore SD 57345-0157

Regulatory alyst
Technologies Management Inc
PO Drawer 200
Winter Park FL 32790-0200

Al Bosch
Tele-Beep Company
PO Box 7072
Bismarck ND 58502-7072

Liz Petroni
Teltrust Comm Services Inc
401 N 5600 W
Salt Lake City UT 84116-3753

Kenneth Carlson
Turtle Mountain Communications
PO Box 729
Langdon ND 58249-0729

Richard Alyanak
U S WEST Communications Inc
1801 California St Rm 4700
Denver CO 80202

Giuseppe Vitale
UKI Communications Inc
500 N Rainbow Blvd Ste 300
Las Vegas NV 89107

Kenneth Carlson
United Telephone Mut Aid Corp
Langdon ND 58249

Telecomm Dept
University of North Dakota
Box 8193
Grand Forks ND 58202-7141

Val-Ed Joint Venture LLP
150 2nd St SW
Perham MN 56573

Mick Grosz
West River Communications Inc
PO Box 467
Hazen ND 58545-0467

Doris Cooper
West River Long Distance Co
PO Box 467
Hazen ND 58545-0467

Mick Grosz
West River Telecomm Coop
PO Box 467
Hazen ND 58545-0467

Western CLEC Corporation
3650 131st Ave SE #400
Bellevue WA 98006

Z-Tel Communications Inc
601 S Harbour Island Blvd Ste 220
Tampa FL 33602-5925

PU-2451-00-630

Copies To:

State Library (8 copies)

Historical Society

Associated Press

Helbling, Sharon D.

From: Helbling, Sharon D.
Sent: Thursday, December 07, 2000 11:04 AM
To: ndna (E-mail)
Subject: Notice of Opportunity to File Written Comments

Please have the attached Notice of Opportunity to File Written Comments published as a legal publication in the next issue of the ten North Dakota daily newspapers, and run it as a "News Item Only" article as well.

Send the bill directly to the Public Service Commission along with a tear sheet for billing purposes.

If you have any questions, please call me at 328-4076.

Thank you.

Sharon Helbling
Public Utilities Division

5 **PU-2451-00-630** Pages: 1

Notice e-mailed to NDNA requesting
publication
by Public Service Commission

12/07/2000

CC: Comm Legal Ilona Jerry .

12/7/2000

APPROVED:

DATE:

12-6-00

KMF

MOTION

December 6, 2000

AT&T Communications of the Midwest, Inc./Qwest Interconnection Agreement Amendment Application	Case No. PU-2441-00-618
New Edge Network, Inc./Qwest Corporation Interconnection Agreement Amendments Application	Case No. PU-2442-00-619
NewPath Holdings, Inc./Qwest Corporation Interconnection Agreement Amendment Application	Case No. PU-2443-00-620
New Acess Communications, LLC/Qwest Interconnection Agreement Application	Case No. PU-2445-00-624
DSLnet Communications, LLC/Qwest Corporation Interconnection Agreement Application	Case No. PU-2448-00-627
Maxcess, Inc./Qwest Corporation Interconnection Agreement Application	Case No. PU-2447-00-628
Choctaw Communications, Inc./Qwest Corporation Interconnection Agreement Application	Case No. PU-2446-00-629
Pilgrim Telephone, Inc./Qwest Corporation Interconnection Agreement Application	Case No. PU-2451-00-630

I move the Commission issue a Notice of Opportunity to File Written Comments in the applications by Qwest Corporation for approval of interconnection agreements and amendments in the above captioned cases.

JRL/sdh

**STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION**

**AT&T Communications of the Midwest, Inc./Qwest
Interconnection Agreement Amendment
Application** **Case No. PU-2441-00-618**

**New Edge Network, Inc./Qwest Corporation
Interconnection Agreement Amendments
Application** **Case No. PU-2442-00-619**

**NewPath Holdings, Inc./Qwest Corporation
Interconnection Agreement Amendment
Application** **Case No. PU-2443-00-620**

**New Acess Communications, LLC/Qwest
Interconnection Agreement
Application** **Case No. PU-2445-00-624**

**DSLnet Communications, LLC/Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2448-00-627**

**Maxcess, Inc./Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2447-00-628**

**Choctaw Communications, Inc./Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2446-00-629**

**Pilgrim Telephone, Inc./Qwest Corporation
Interconnection Agreement
Application** **Case No. PU-2451-00-630**

NOTICE OF OPPORTUNITY TO FILE WRITTEN COMMENTS

December 6, 2000

On November 16, 2000 Qwest Corporation Communications, Inc. (Qwest) filed applications for approval of a second amendment negotiated to its interconnection agreement with AT&T Communications of the Midwest, Inc. of Minneapolis, MN (Case No. PU-2441-00-618), a third amendment negotiated to its interconnection agreement with New Edge Netowrks of VanCouver, WA (Case No. PU-2442-00-619), and a first amendment negotiated to its interconnection agreement with NewPath Holdings, Inc. of Des Moines IA (Case No. PU-2443-00-620). These amendments set forth rates, terms

3 PU-2451-00-630

Pages: 2

Notice of Opportunity to File Written
Comments
by Public Service Commission

12/06/2000

CC: Comm Legal Ilona Jerry

or conditions for interconnection of facilities, including unbundled network elements, collocation augments, operational support systems, or local number portability.

On November 21, 2000, Qwest filed applications for approval of service resale agreements negotiated with New Access Communications, LLC of Minneapolis, MN (Case No. PU-2445-00-624) and Choctaw Communications Inc. d/b/a Smoke Signal Communications of Houston TX (Case No. PU-2446-00-629). These agreements set rates, terms and conditions under which Qwest agrees to provide services for resale.

Also on November 21, 2000, Qwest filed applications for approval of DSLnet Communications, LLC to "opt in" to a previously approved interconnection agreement with New Edge Networks, Inc. (Case No. PU-2448-00-627) and for approval of MAXCESS, Inc. of Orlando, FL to "opt in" to a previously approved interconnection agreement with Pathnet, Inc. (Case No. PU-2447-00-628), and for approval of an interconnection agreement negotiated with Pilgrim Telephone, Inc. of Cambridge MA (Case No. PU-2451-00-630), which Qwest states is the same as a previously approved interconnection agreement with New Edge Networks, Inc.


These agreements were filed under Section 252(e) of the Telecommunications Act of 1996 (Act). The Act requires that any agreement adopted by negotiation or arbitration be submitted for approval to the Commission. Under section 252(e)(2)(A), the Commission may only reject an agreement (or portion thereof) adopted by negotiation if it finds that:


1. the agreement (or portion thereof) discriminates against a telecommunications carrier that was not a party to the agreement;
2. the implementation of the agreement (or portion thereof) is not consistent with the public interest, convenience, and necessity.


In addition, the Commission may include in its review state requirements that do not constitute barriers to entry under section 253. Section 252(e)(4) requires that the Commission must act to approve or reject an agreement adopted by negotiation within ninety (90) days after submission by the parties.

The Commission will receive written comments on these agreements until January 8, 2001. For more information contact the Public Service Commission, State Capitol, Bismarck, North Dakota 58505, 701-328-2400; or Relay North Dakota 1-800-366-6888 TTY. If you require any auxiliary aids or services, such as readers, signers, or Braille materials please notify Jon Mielke, Executive Secretary.

PUBLIC SERVICE COMMISSION


Susan E. Wefald
Commissioner


Bruce Hagen
President


Leo M. Reinbold
Commissioner



Public Service Commission

State of North Dakota

COMMISSIONERS

Bruce Hagen
President
Susan E. Wefald
Leo M. Reinbold

November 22, 2000

600 E Boulevard Ave. Dept. 408
Bismarck, North Dakota 58505-0480
e-mail: sab@oracle.psc.state.nd.us
TDD 800-366-6888
Fax 701-328-2410
Phone 701-328-2400

Executive Secretary
Jon H. Mielke

Stan Kugell
Pilgrim Telephone Inc
1 Kendall Sq
Cambridge MA 02139

Dear Mr. Kugell:

We have received an interconnection agreement between Qwest Corporation and Pilgrim Telephone Inc. In the agreement you state you are a competitive local exchange carrier. In North Dakota you are registered only as a reseller of long distance telecommunications services.


We will begin to process your interconnection agreement, but before you can provide competitive local exchange services in North Dakota, you must apply for a Certificate of Registration for switchless local resale, or a Certificate of Public Convenience and Necessity for facilities-based local services.

I have enclosed an application form for registration as a reseller, an example of a facilities-based application, and all other rules and laws that apply. We also require that you provide us with a current original Certificate of Good Standing. You can obtain that document by calling the North Dakota Secretary of State at 701-328-2900.

Tariffs are required for CLECs (see N.D.C.C 49-21-04 attached). If a local exchange reseller requires prepayments, the bond amount is \$25,000. A copy of the PSC policy relating to bonds for local exchange resellers is enclosed.

If you have any questions, please call me at 701-328-4076. Thank you.

Sincerely,



Sharon Helbling
Public Utilities Division

sdh

Enclosures

c: Dan Kuntz

2

PU-2451-00-630

Pages: 1

Letter re application

by Public Service Commission

11/22/2000

CC: Comm Legal Illona Jerry .

ZUGER KIRMIS & SMITH

COUNSELORS AND ATTORNEYS AT LAW

Lyle W. Kirmis
Thomas O. Smith, P.C.
Lance D. Schreiner, P.C.
James S. Hill, P.C.*^
Patrick J. Ward**
Rebecca S. Thiem, P.C.*
Daniel S. Kuntz, P.C.
Brenda L. Blazer, P.C.
Jerry W. Evenson, P.C.^
Christine A. Hogan
Lawrence A. Dopson

316 North Fifth Street
Provident Building
P.O. Box 1695
Bismarck, ND 58502-1695
(701) 223-2711
fax (701) 223-7387
zkslaw@zkslaw.com
www.zkslaw.com


Lawrence E. King*
Tracy Vigness Kolb
Shawnda R. Reid

Of Counsel
John A. Zuger

Also licensed in
Minnesota *
Montana/Illinois **

^Certified Civil Trial Specialist
National Board of Trial Advocacy

November 21, 2000



Mr. Jon Mielke
Executive Secretary
ND Public Service Commission
State Capitol -- 12th Floor
Bismarck, ND 58505-0480

Re: Interconnection Agreement Between Qwest Corporation and Pilgrim Telephone, Inc.

Dear Mr. Mielke:

Enclosed for filing are the original and seven copies of an Interconnection Agreement between Pilgrim Telephone, Inc. and Qwest Corporation f/k/a U S WEST Communications, Inc. Also enclosed is an extra copy of this letter. Please date stamp the extra copy and return it to me in the enclosed postage-paid envelope.

Please contact me if you have any questions regarding this filing.

Sincerely,

A handwritten signature in black ink, appearing to read "Daniel S. Kuntz".

Daniel S. Kuntz


Enclosures

c: Scott Macintosh w/enc.
Debra Hartl wo/enc.
Stan Kugell wo/enc.

kac:\dkuntz\10070\1-mielke.pilgrim

1 PU-2451-00-630 Pages: 130

Interconnection agreement application
by Pilgrim Telephone, Inc./Qwest Corporation
11/21/2000 CC: Comm Legal Ilona Jerry



**INTERCONNECTION
AGREEMENT**

BETWEEN

U S WEST COMMUNICATIONS, INC.

AND

PILGRIM TELEPHONE, INC.

FOR

NORTH DAKOTA

TABLE OF CONTENTS

1. RECITALS.....	8
2. SCOPE OF AGREEMENT	9
3. DEFINITIONS.....	10
4. RATES AND CHARGES GENERALLY.....	16
5. RECIPROCAL TRAFFIC EXCHANGE	17
5.1 Scope.....	17
5.2 Traffic Types	17
5.3 Types of Exchanged Traffic.....	18
5.4 Rate Structure	20
5.5 LIS Interface Code Availability And Optional Features	22
5.6 Measuring Local Interconnection Minutes	23
5.7 Testing.....	23
5.8 Ordering	24
5.9 Billing Arrangements	25
5.10 Mileage Measurement	26
5.11 Construction Charges	26
6. INTERCONNECTION.....	26
6.1 Exchange of Local Traffic	26
6.2 Mid-Span Meet POI	26
6.3 Collocation	27
6.4 Entrance Facility (EF2)	27
6.5 Quality of Interconnection	27
6.6 Points of Interface (POI).....	27

TABLE OF CONTENTS

6.7	Trunking Requirements	27
6.8	Interconnection Forecasting	29
6.9	Service Interruptions	30
7.	COLLOCATION	31
7.1	General Description.....	31
7.2	Virtual Collocation	34
7.3	Physical Collocation.....	36
7.4	Common Collocation.....	40
7.5	CLEC Combination of Unbundled Network Elements	40
7.6	Collocation Rate Elements	44
7.7	Collocation Installation Intervals:	49
7.8	Adjacent Space Collocation:	50
8.	UNBUNDLED ACCESS/ELEMENTS.....	50
8.1	General Terms	50
8.2	Description of Unbundled Elements	51
9.	ANCILLARY SERVICES AND ARRANGEMENTS.....	62
9.1	Signaling Access to Call-Related Databases	62
9.2	Interim Number Portability.....	63
9.3	911/E-911 Service	68
9.4	Directory Assistance	71
9.5	White Pages Directory Listings.....	72
9.6	Busy Line Verify and Busy Line Interrupt Services.....	75
9.7	Toll and Assistance Operator Services	76
9.8	Interconnection to Line Information Data Base (LIDB)	77

TABLE OF CONTENTS

9.9	Access to Poles, Ducts, Conduits, and Rights of Way	78
9.10	Miscellaneous Ancillary Services.....	78
10.	ACCESS TO OPERATIONAL SUPPORT SYSTEMS (OSS)	78
10.1	Operational Systems Interfaces - Interface Implementation Timetable.....	79
10.2	OSS Interface Design	79
10.3	Accessible OSS Functions	80
10.4	Billing Interfaces.....	85
10.5	Compensation.....	86
11.	RESALE	87
11.1	Description.....	87
11.2	Scope.....	87
11.3	Ordering and Maintenance	87
11.4	Pilgrim Responsibilities	90
11.5	Rates and Charges	91
11.6	Collateral and Training.....	93
11.7	Directory Listings	94
11.8	Billing.....	94
11.9	Deposit	94
11.10	Payment.....	95
12.	ACCESS TO TELEPHONE NUMBERS.....	96
12.1	Number Resources Arrangements.	96
13.	DIALING PARITY.....	97
14.	U S WEST DEX ISSUES.....	97

TABLE OF CONTENTS

15. ACCESS TO DATABASES	97
16. NOTICE OF CHANGES	97
17. REFERRAL ANNOUNCEMENT	98
18. COORDINATED REPAIR CALLS.....	98
19. BONA FIDE REQUEST PROCESS	98
20. AUDIT PROCESS	100
21. AUDIOTEXT AND MASS ANNOUNCEMENT SERVICES	102
22. LOCAL INTERCONNECTION DATA EXCHANGE FOR BILLING.....	102
23. CONSTRUCTION CHARGES.....	103
24. SERVICE PERFORMANCE RESULTS	105
25. IMPLEMENTATION SCHEDULE.....	108
26. MISCELLANEOUS TERMS	108
26.1 General Provisions	108
26.2 Term of Agreement.....	110
26.3 Letter of Authorization	110
26.4 Payment.....	111
26.5 Taxes	112
26.6 Force Majeure	112
26.7 Limitation of Liability.....	112
26.8 Indemnity.....	113
26.9 Intellectual Property	114
26.10 Warranties	117

TABLE OF CONTENTS

26.11	Assignment.....	117
26.12	Default	117
26.13	Disclaimer of Agency	117
26.14	Severability	118
26.15	Nondisclosure.....	118
26.16	Survival.....	120
26.17	Dispute Resolution	120
26.18	Controlling Law.....	120
26.19	Joint Work Product.....	121
26.20	Responsibility for Environmental Contamination	121
26.21	Notices.....	121
26.22	Responsibility of Each Party	122
26.23	No Third Party Beneficiaries.....	122
26.24	Referenced Documents.....	122
26.25	Publicity and Advertising.....	123
26.26	Amendment.....	123
26.27	Executed in Counterparts	123
26.28	Headings of No Force or Effect.....	123
26.29	Cancellation Charges	123
26.30	Regulatory Approval	123
26.31	Compliance	124
26.32	Compliance with the Communications Law Enforcement Act of 1994 ("CALEA").....	124

TABLE OF CONTENTS

26.33 Cooperation..... 124

26.34 Entire Agreement..... 124

NORTH DAKOTA APPENDIX A 127

INTERCONNECTION AGREEMENT

This Interconnection Agreement is between Pilgrim Telephone, Inc. ("Pilgrim") and U S WEST Communications, Inc. ("USWC"), a Colorado corporation.

1. RECITALS

- 1.1 Pursuant to this Interconnection Agreement ("Agreement"), Pilgrim, a Competitive Local Exchange Carrier and USWC, an Incumbent Local Exchange Carrier (collectively, the "Parties" and individually, a "Party") will enter into certain arrangements in the state of North Dakota. This Agreement includes terms, conditions, and prices for network interconnection, and Pilgrim's access to USWC's unbundled network elements, ancillary network services, and retail services available for resale. Pursuant to this Interconnection Agreement Pilgrim and USWC, collectively "the Parties", will extend certain arrangements to one another within each LATA in which they both operate within the state of North Dakota. This Agreement is a combination of agreed terms and terms imposed by arbitration under Section 252 of the Communications Act of 1934, as modified by the Telecommunications Act of 1996 ("the Act"), and as such does not necessarily represent the position of either Party on any given issue. The Parties enter into this Agreement without prejudice to any position they may have taken previously, or may take in the future in any legislative, regulatory, or other public forum addressing any matters, including matters related to the types of arrangements prescribed by this Agreement. Nevertheless, the Parties shall fully honor the terms of the Agreement, regardless of their respective advocacy positions subject to modification of this Agreement pursuant to a change in the law.
- 1.2 This Agreement is entered into as a result of both private negotiations between the Parties and the incorporation of some of the results of arbitrated decisions by the Commission, acting pursuant to Section 252 (b) of the Act, and involving interconnection agreements of other parties. The Parties have included for convenience certain rates, terms or conditions in this Agreement which reflect rates, terms or conditions established in some or all of those other arbitrations. Pilgrim acknowledges: (1) that those rates, terms or conditions are extended only because of the arbitrated results in other dockets, (2) that USWC intends to appeal certain of those decisions, and (3) that any negotiations, appeal, stay, injunction or similar proceeding impacting the applicability of those rates, terms or conditions to the local service providers who were parties to those arbitrations may impact the applicability of those rates, terms or conditions to Pilgrim. The Parties further recognize that certain provisions of this Agreement are subject to the generic proceedings by the Commission addressing the services in this Agreement. Nevertheless, the Parties shall fully honor the terms of the Agreement, regardless of their respective advocacy positions subject to modification of this Agreement pursuant to a change in the law.

- 1.3. The Parties have agreed to certain provisions in this Agreement, based, in large part, on the existing state of the law, rules, regulations and interpretations thereof, as of the date hereof (the "Existing Rules"). To the extent that certain of the Existing Rules are changed and modified, including changes pursuant to Section 1.2, and it reasonably appears that the Parties would have negotiated and agreed to different term(s), conditions(s), or covenant(s) than as contained herein had such change or modification been in existence before execution hereof, then the Parties will meet as required and confer in good faith to renegotiate the terms of this Agreement which may be amended to reflect such different term(s), condition(s), or covenant(s). Where the Parties fail to agree upon such an amendment, it shall be resolved in accordance with the Dispute Resolution provision of this Agreement. Nevertheless, the Parties shall fully honor the terms of the Agreement, regardless of their respective advocacy positions subject to modification of this Agreement pursuant to a change in the law. Nothing in this paragraph shall be construed as a waiver by either Party of any of its property rights in this Agreement.

2. SCOPE OF AGREEMENT

- 2.1 This Agreement sets forth the terms, conditions and prices under which USWC agrees to provide (a) services for resale (hereinafter referred to as "Local Services") (b) certain unbundled network elements, ancillary functions and additional features to Pilgrim (hereinafter collectively referred to as "Network Elements") for the purposes of Pilgrim's offering and provisioning of telecommunications services. The Agreement also sets forth the terms, conditions and prices under which the Parties agree to interconnect and pay reciprocal compensation for the exchange of local traffic between USWC and Pilgrim. Nothing in this Agreement shall prohibit either Party from using the other Party's services and facilities to provide telecommunications originating or terminating services for information services provided by either Party or a third party. Unless otherwise provided in this Agreement, the Parties will perform all of their obligations hereunder throughout, to the extent provided in the Appendices attached hereto. The Agreement includes all accompanying Appendices.
- 2.2 In the performance of their obligations under this Agreement, the Parties shall act in good faith and consistently with the intent of the Act. Where notice, approval or similar action by a Party is permitted or required by any provision of this Agreement, (including, without limitation, the obligation of the Parties to further negotiate the resolution of new or open issues under this Agreement) such action shall not be unreasonably delayed, withheld or conditioned.

3. DEFINITIONS

- 3.1 "Access Service Request" or "ASR" means the industry standard forms and supporting documentation used for ordering Access Services. The ASR will be used to order trunking and facilities between Pilgrim and USWC for Local Interconnection Service.
- 3.2 "Access Services" refers to the tariffed interstate and intrastate switched access and private line transport services (including special access services) offered for the origination and/or termination of interexchange traffic (see each Party's appropriate state and interstate access tariffs).
- 3.3. "ADSL" or "Asymmetrical Digital Subscriber Line" means a transmission technology which transmits an asymmetrical digital signal using one of several transmission methods (for example, carrier - less AM/PM discrete multi-tone, or discrete wavelet multi-tone).
- 3.3 "Act" means the Communications Act of 1934 (47 U.S.C. 151 et.seq.), as amended by the Telecommunications Act of 1996, and as from time to time interpreted in the duly authorized rules and regulations of the FCC or a Commission within its state of jurisdiction.
- 3.4 "Automatic Number Identification" or "ANI" means a Feature Group D signaling parameter which refers to the number transmitted through a network identifying the billing number of the calling party.
- 3.5 "Basic Exchange Switched Features" are optional end user switched services that include, but are not necessarily limited to: Automatic Call Back; Call Trace; Caller ID and Related Blocking Features; Distinctive Ringing/Call Waiting; Selective Call Forward; Selective Call Rejection.
- 3.6 "Basic Exchange Telecommunications Service" means a service offered to end users which provides the end user with a telephonic connection to, and a unique local telephone number address on, the public switched telecommunications network, and which enables such end user to generally place calls to, or receive calls from, other stations on the public switched telecommunications network. Basic residence and business line services are Basic Exchange Telecommunications Services. As used solely in the context of this statement and unless otherwise agreed, Basic Exchange Telecommunications Service includes access to ancillary services such as 911, directory assistance and operator services.
- 3.7 "BLV/BLVI Traffic" means an operator service call in which the caller inquires as to the busy status of or requests an interruption of a call on another end user's Basic Exchange Telecommunications Service line.

- 3.8 "Calling Party Number" or "CPN" is a Common Channel Signaling ("CCS") parameter which refers to the number transmitted through a network identifying the calling party. Reference Technical Pub. 77342.
- 3.9 "Central Office Switch" means a switch used to provide telecommunications services, including, but not limited to:
- 3.9.1 "End Office Switches" which are used to terminate end user station loops for the purpose of interconnecting to each other and to trunks; and
 - 3.9.2 "Tandem Office Switches" which are used to connect and switch trunk circuits between and among other Central Office Switches. Access tandems provide connections for exchange access and toll traffic while local tandems provide connections for local/EAS traffic.
- 3.10 "Collocation" means an arrangement whereby Pilgrim's facilities are terminated in its equipment necessary for Interconnection or for access to Network Elements on an unbundled basis which has been installed and maintained at the premises of a USWC. Collocation may be "physical", "virtual", or "common". In "Physical Collocation," Pilgrim installs and maintains its own equipment in USWC's premises. In "Virtual Collocation," USWC installs and maintains Pilgrim's equipment in USWC's premises. In "Common Collocation", Pilgrim installs and maintains its own equipment in USWC's premises without the use of a cage.
- 3.11 "Commission" means the relevant state regulatory commission with jurisdiction over USWC's telecommunications services in that state.
- 3.12 "Common Channel Signaling" or "CCS" means a method of digitally transmitting call set-up and network control data over a special signaling network fully separate from the public voice switched network elements that carry the actual call. The CCS used by the Parties shall be Signaling System 7.
- 3.13 "Competitive Local Exchange Carrier" (CLEC) means an entity authorized to provide Local Exchange Service that does not otherwise qualify as an Incumbent Local Exchange Carrier ("ILEC").
- 3.14 "Digital Signal Level" means one of several transmission rates in the time division multiplexing hierarchy.
- 3.15 "Digital Signal Level 0" or "DS0" means the 64 Kbps zero-level signal in the time-division multiplex hierarchy.
- 3.16 "Digital Signal Level 1" or "DS1" means the 1.544 Mbps first-level signal in the time-division multiplex hierarchy. In the time-division multiplexing hierarchy of the telephone network, DS1 is the initial level of multiplexing.

- 3.17 "Digital Signal Level 3" or "DS3" means the 44.736 Mbps third-level in the time-division multiplex hierarchy. In the time-division multiplexing hierarchy of the telephone network, DS3 is defined as the third level of multiplexing.
- 3.18 "Exchange Message Record" or "EMR" is the standard used for exchange of telecommunications message information between telecommunications providers for billable, non-billable, sample, settlement and study data. EMR format is contained in BR-010-200-010 CRIS Exchange Message Record, a Bellcore document that defines industry standards for exchange message records.
- 3.19 "Extended Area Service (EAS)/Local Traffic" means traffic that is originated by an end user of one Party and terminates to an end user of the other Party as defined in accordance with USWC's then current EAS/local serving areas, as determined by the Commission.
- 3.20. "HDSL" or "High-Bit Rate Digital Subscriber Line" means a two-wire or four-wire transmission technology which typically transmits a DS1-level signal (or, higher level signals with certain technologies), using 2 Binary/1 Quaternary ("2B1Q").
- 3.21 "Integrated Digital Loop Carrier" means a subscriber loop carrier system, which integrates within the switch at a DS1 level (twenty-four (24) local Loop transmission paths combined into a 1.544 Mbps digital signal).
- 3.22 "Interexchange Carrier" or "IXC" means a carrier that provides, directly or indirectly, interLATA or IntraLATA Toll services.
- 3.23 "IntraLATA Toll" is defined in accordance with USWC's current intraLATA toll serving areas, as determined by the Commission.
- 3.24 "Integrated Services Digital Network" or "ISDN" means a switched network service that provides end-to-end digital connectivity for the simultaneous transmission of voice and data. Basic Rate Interface-ISDN (BRI-ISDN) provides for a digital transmission of two 64 Kbps bearer channels and one 16 Kbps data channel (2B+D). Primary Rate Interface - ISDN (PRI-ISDN) provides a digital transmission of 23 bearer channels and one data channel (23+D). "IDSL" means a Pilgrim service using Pilgrim's digital subscriber line equipment collocated in USWC's premises over loops provided by USWC and providing the same or similar functionality as ISDN.
- 3.25 "Local Loop Transmission" or "Loop" means the entire transmission path which extends from the network interface or demarcation point at an end user's premises to the Main Distribution Frame or other designated frame or panel in USWC's Wire Center which serves the end user.

- 3.26 "Main Distribution Frame" or "MDF" means the distribution frame of USWC providing the Loop used to interconnect cable pairs and line and trunk equipment terminals on a switching system.
- 3.27 "MECAB" refers to the Multiple Exchange Carrier Access Billing (MECAB) document prepared by the Billing Committee of the Ordering and Billing Forum (OBF), that functions under the auspices of the Carrier Liaison Committee of the Alliance for Telecommunications Industry Solutions. The MECAB document, published by Bellcore as Special Report SR-BDS-000983, contains the recommended guidelines for the billing of an Access Service provided by two or more LECs (including a LEC and a CLEC) or by one LEC in two or more states within a single LATA.
- 3.28 "MECOD" refers to the Multiple Exchange Carriers Ordering and Design (MECOD) Guidelines for Access Services - Industry Support Interface, a document developed by the Ordering/Provisioning Committee under the auspices of the Ordering and Billing Forum (OBF), that functions under the auspices of the Carrier Liaison Committee of the Alliance for Telecommunications Industry Solutions. The MECOD document, published by Bellcore as Special Report SR STS-002643, establishes recommended guidelines for processing orders for Access Service that is to be provided by two or more LECs (including a LEC and a CLEC). It is published by Bellcore as SRBDS 00983.
- 3.29 "Meet-Point Billing" or "MPB" refers to an arrangement whereby two LECs (including a LEC and CLEC) jointly provide Switched Access Service to an Interexchange Carrier, with each LEC (or CLEC) receiving an appropriate share of the transport element revenues as defined by their effective access tariffs.
- 3.30 "Mid-Span Meet" is a Point of Interconnection between two networks, designated by two Telecommunications Carriers, at which one carrier's responsibility for service begins and the other carrier's responsibility ends.
- 3.31 "Network Element" means a facility or equipment used in the provision of a telecommunications service. Network Element includes features, functions, and capabilities that are provided by means of such facility or equipment, including subscriber numbers, databases, signaling systems, and information sufficient for billing and collection or used in the transmission, routing, service monitoring, maintenance or other provision of a telecommunications service.
- 3.32 "North American Numbering Plan" or "NANP" means the numbering plan used in the United States that also serves Canada, Bermuda, Puerto Rico and certain Caribbean Islands. The NANP format is a 10-digit number that consists of a 3-digit NPA code (commonly referred to as the area code), followed by a 3-digit NXX code and 4-digit line number.
- 3.33 "NXX" means the fourth, fifth and sixth digits of a ten-digit telephone number.

- 3.34 "Party" means either USWC or Pilgrim and "Parties" means USWC and Pilgrim.
- 3.35 "Point of Interface", "Point of Interconnection", or "POI" is a mutually agreed upon point of demarcation where the exchange of traffic between two LECs (including a LEC and a CLEC) takes place.
- 3.36 "Port" means a termination on a Central Office Switch that permits end users to send or receive telecommunications services over the public switched network, but does not include switch features or switching functionality.
- 3.37 "Rate Center" means the specific geographic point and corresponding geographic area which are associated with one or more particular NPA-NXX codes which have been assigned to a LEC (or CLEC) for its provision of basic exchange telecommunications services. The "rate center point" is the finite geographic point identified by a specific V & H coordinate, which is used to measure distance-sensitive end user traffic to/from, the particular NPA-NXX designations associated with the specific Rate Center. The "rate center area" is the exclusive geographic area identified as the area within which the LEC (or CLEC) will provide Basic Exchange Telecommunications Service bearing the particular NPA-NXX designations associated with the specific Rate Center. The Rate Center point must be located within the Rate Center area.
- 3.38 "Reseller" is a category of local exchange service provider that obtains dial tone and associated telecommunications services from another provider through the purchase of bundled finished services for resale to its end users.
- 3.39 "Routing Point" means a location that a LEC or CLEC has designated on its own network as the homing (routing) point for traffic, bearing a certain NPA-NXX designation, that is inbound to Basic Exchange Telecommunications Services provided by the LEC or CLEC. The Routing Point is employed to calculate mileage measurements for the distance-sensitive transport element charges of Switched Access Services. Pursuant to Bellcore Practice BR 795-100-100, the Routing Point may be an "End Office" location, or a "LEC Consortium Point of Interconnection". Pursuant to that same Bellcore Practice, examples of the latter shall be designated by a common language location identifier (CLLI) code with (x)KD in positions 9, 10, 11, where (x) may be any alphanumeric A-Z or 0-9. The above referenced Bellcore document refers to the Routing Point as the Rating Point. The Rating Point/Routing Point must be located within the rate center area.
- 3.40 "Service Control Point" or "SCP" means a signaling end point that acts as a database to provide information to another signaling end point (i.e., Service Switching Point or another SCP) for processing or routing certain types of network calls. A query/response mechanism is typically used in communicating with an SCP.
- 3.41 "Signaling Transfer Point" or "STP" means a signaling point that performs message routing functions and provides information for the routing of messages

between signaling end points. An STP transmits, receives and processes Common Channel Signaling ("CCS") messages.

- 3.42 Single Point of Termination frame ("SPOT frame") is an intermediate distribution frame or appropriate cross connect device which is the standard demarcation point between Pilgrim and USWC owned network facilities and equipment, as well as, the demarcation point between USWC's unbundled network elements and Pilgrim's collocated equipment.
- 3.43 "Switched Access Service" means the offering of transmission or switching services to Telecommunications Carriers for the purpose of the origination or termination of telephone toll service. Switched Access Services include: Feature Group A, Feature Group B, Feature Group D, 800/888 access, and 900 access and their successors or similar Switched Access services.
- 3.44 "Tariff" as used throughout this Agreement refers to USWC interstate tariffs and state tariffs, price lists, price schedules and catalogs.
- 3.45 "Telecommunications Carrier" means any provider of telecommunications services, except that such term does not include aggregators of telecommunications services (as defined in Section 226 of the Act). A Telecommunications Carrier shall be treated as a common carrier under the Act only to the extent that it is engaged in providing telecommunications services, except that the Commission shall determine whether the provision of fixed and mobile satellite service shall be treated as common carriage.
- 3.46 "Traffic Type" is the characterization of intraLATA traffic as "local" (local includes EAS), or "toll" which shall be the same as the characterization established by the appropriate state commission for the incumbent LEC.
- 3.47 "Wire Center" denotes a building, or space within a building, that serves as an aggregation point on a given carrier's network, where transmission facilities are connected or switched. Wire Center can also denote a building where one or more Central Offices, used for the provision of Basic Exchange Telecommunications Services and Access Services, are located. However, for purposes of Collocation Service, Wire Center shall mean those points eligible for such connections as specified in the FCC Docket No. 91-141, and rules adopted pursuant thereto.
- 3.48 "xDSL" refers to a set of service enhancing copper technologies, including but not limited to Asymmetric Digital Subscriber Loop (ADSL), High Bit Rate, or Hybrid, Digital Subscriber Loop (HDSL) and Integrated Digital Subscriber Loop (IDSL), that are designed to provided digital communications services over copper Loops, either in addition to or instead of normal analog voice service. xDSL Loops means Loops that have been conditioned, if necessary and at the appropriate charge if any, by USWC to carry the appropriate xDSL signals.

- 3.49 Terms not otherwise defined here, but defined in the Act or in regulations implementing the Act, shall have the meaning defined there.

4. RATES AND CHARGES GENERALLY

- 4.1. For Interconnection, Resold Services and Unbundled Network Elements, Pilgrim and USWC agree to use state-specified permanent rates where established, or where no state-specified permanent rate exists, Pilgrim agrees to use the state-specified interim rates where established. Where no state-specified permanent or interim rates exist, Pilgrim agrees to use the ordered and approved AT&T rates as interim rates until such time as the state Commission issues an order in a generic proceeding or arbitration, implementing approved rates, whether those approved rates are interim or final. Upon issuance of the order, USWC will move Pilgrim to such approved rates for those states and true up the amounts charged to that point not to exceed 12 months. If either interim, permanent or approved AT&T rates are later modified on appeal, on a retroactive basis, an additional true up will occur to that point not to exceed 12 months. For purposes of this agreement, "Rates" include rate structure.
- 4.2. Sections of this Agreement referring to TELRIC are agreements in principle on their use of TELRIC. References to TELRIC in this agreement include the condition that the Parties do not necessarily agree to a specific TELRIC methodology. The Parties agree to utilize the specific methodology that is ultimately ordered by the arbitrators/regulators.
- 4.3. USWC will not charge Pilgrim any non-recurring charges incurred as a result of USWC implementing network redesigns/reconfigurations or electronic system redesign/reconfigurations solely initiated by USWC to its own network or systems. However, any redesign or reconfiguration expenses required by a regulatory body where the regulatory body orders a cost-sharing arrangement may be billed as appropriate on a non-discriminatory basis to Pilgrim.
- 4.4. Prices for termination and transport of traffic, interconnection, access to unbundled network elements, and ancillary services are set forth in Appendix A. The Parties agree that Pilgrim shall only pay the specific charges set forth in Appendix A; provided however, USWC will only be required to provide those services or elements as set forth in Appendix A. The Parties agree that all charges for Loops, Dedicated Transport and Collocation are expressly set forth in Appendix A. In the event the Parties have inadvertently made errors in Appendix A, the Parties agree to mutually correct such errors expeditiously.
- 4.5. USWC's wholesale discounts for resale services are set forth in Appendix A.
- 4.6. The underlying provider of a resold service shall be entitled to receive, from the purchaser of switched access, the appropriate access charges pursuant to its then effective switched access tariff. For the purposes of this paragraph,

Unbundled Elements as defined in this agreement and the Act are not considered as resold services.

- 4.7. All Individual Case Basis (ICB), or Time and Material based charges will be accompanied by sufficient documentation to verify charges when billed.

5. RECIPROCAL TRAFFIC EXCHANGE

5.1 Scope

Reciprocal traffic exchange addresses the exchange of traffic between Pilgrim end users and USWC end users. If such traffic is local, the provisions of this Agreement shall apply. Where either Party acts as an IntraLATA Toll provider or interLATA Interexchange Carrier (IXC) or where either Party interconnects and delivers traffic to the other from third parties, each Party shall bill such third parties the appropriate charges pursuant to its respective tariffs or contractual offerings for such third party terminations. Absent a separately negotiated agreement to the contrary, the Parties will directly exchange traffic between their respective networks, without the use of third party transit providers.

5.2 Traffic Types

The Traffic Types to be exchanged under this Agreement include:

- 5.2.1 EAS/Local Traffic as defined above.
- 5.2.2 IntraLATA Toll traffic as defined above.
- 5.2.3 Switched Access traffic, or interLATA toll traffic, as specifically defined in USWC's state and interstate Switched Access Tariffs, and generally identified as that traffic that originates at one of the Party's end users and terminates at an IXC point of presence, or originates at an IXC point of presence and terminates at one of the Party's end users, whether or not the traffic transits the other Party's network.
- 5.2.4 Transit traffic is any traffic other than Switched Access, that originates from one Telecommunications Carrier's network, transits another Telecommunications Carrier's network, and terminates to yet another Telecommunications Carrier's network.

Transit service provides the ability for a Telecommunications Carrier to use its connection to a local or access tandem for delivery of calls that originate with a Telecommunications Carrier and terminate to a company other than the tandem company, such as another CLEC, an existing LEC, or a wireless carrier. In these cases, neither the originating nor terminating end user is a customer of the tandem Telecommunications

Carrier. The tandem Telecommunications Carrier will accept traffic originated by a Party and will terminate it at a Point of Interconnection with another local, intraLATA or interLATA network Telecommunications Carrier. This service is provided through local and access tandem switches.

5.2.5 Ancillary traffic includes all traffic destined for ancillary services, or that may have special billing requirements, including, but not limited to the following:

- 5.2.5.1 Directory Assistance
- 5.2.5.2 911/E911
- 5.2.5.3 Operator call termination (busy line interrupt and verify)
- 5.2.5.4 800/888 database dip
- 5.2.5.5 LIDB
- 5.2.5.6 Information services requiring special billing.

5.2.6 Unless otherwise stated in this Agreement, ancillary traffic will be exchanged in accordance with whether the traffic is EAS/Local, IntraLATA Toll, or Switched Access.

5.3 Types of Exchanged Traffic

5.3.1 Termination of Local Traffic.

Local traffic will be terminated as Local Interconnection Service (LIS).

5.3.2 Transport of Local Traffic

As negotiated between the Parties, the exchange of local traffic between the Parties may occur in several ways:

5.3.2.1 While the Parties anticipate the use of two way trunks for the delivery of local traffic, either Party may elect to provision its own one-way trunks for delivery of local traffic to be terminated on the other Party's network.

5.3.2.2 The Parties may elect to purchase transport services from each other or from a third party. Such transport delivers the originating Party's local traffic to the terminating Party's end office or tandem for call termination. Transport may be purchased as either tandem switched transport or direct trunk transport.

5.3.2.3 Based on forecasted traffic at Pilgrim's busy hour in CCS, where there is a DS1's worth of traffic (512 CCS) between the Pilgrim switch and a USWC end office, the traffic will be moved to a dedicated (i.e., direct) trunk group from the

Pilgrim switch directly to the USWC end office. To the extent that Pilgrim has established a Collocation arrangement at a USWC end office location, and has available capacity, the Parties agree that Pilgrim shall provide two-way direct trunk facilities, when required, from that end office to the Pilgrim switch. In all other cases, the direct facility may be provisioned by USWC or Pilgrim or a third party. If both Pilgrim and USWC desire to provision the facility and cannot otherwise agree, the Parties may agree to resolve the dispute through the submission of competitive bids.

5.3.3 Transit Traffic.

5.3.3.1 USWC will accept traffic originated by Pilgrim and will terminate it at a Point of Interconnection with another CLEC, LEC, IXC, or wireless carrier. USWC will provide this transit service through local and access tandem switches. Pilgrim may also provide USWC with transit service.

5.3.3.2 The Parties expect that all networks involved in transporting transit traffic will deliver calls to each involved network with CCS/SS7 protocol and the appropriate ISUP/TCAP message to facilitate full interoperability and billing functions. In all cases, the originating company is responsible to follow the EMR standard and to exchange records with both the transiting company and the terminating company, to facilitate the billing process to the originating network.

5.3.3.3 The Parties will use industry standards developed to handle the provision and billing of Switched Access by multiple providers (MECAB, MECOD and the Parties' FCC tariffs), including the one-time provision of notification to Pilgrim of the billing name, billing address and carrier identification codes of all Interexchange Carriers originating or terminating at each USWC access tandem.

5.3.4 Toll Traffic.

Toll traffic routed to an access tandem, or directly routed to an end office, will be terminated as Switched Access Service. Traffic terminated at the access tandem will be routed to the end offices within the LATA that subtend the USWC access tandem switch. Switched Access Service also allows for termination at an end office or tandem via direct trunked circuits provisioned either by USWC or Pilgrim.

5.4 Rate Structure

5.4.1 Local Traffic

5.4.1.1 Call Termination

- 5.4.1.1.1 The Parties agree that call termination rates as described in Appendix A will apply reciprocally for the termination of EAS/Local traffic per minute of use. If the exchange of EAS/Local traffic between the Parties is within +/- 5% of balance (as measured monthly), the Parties agree that their respective call termination charges will offset one another, and no compensation will be paid. The Parties agree to perform monthly joint traffic audits, based upon mutually agreeable measurement criteria and auditing standards. In the event that the exchange of traffic is not in balance as described above, the call termination charges in Appendix A will apply.
- 5.4.1.1.2 For traffic terminated at a USWC or Pilgrim end office, the end office call termination rate in Appendix A shall apply.
- 5.4.1.1.3 For traffic terminated at a USWC or Pilgrim tandem switch, the tandem switched rate and the tandem transmission rate in Appendix A shall apply in addition to the end office call termination rate described above.
- 5.4.1.1.4 The Parties acknowledge that Pilgrim will initially serve all of its end users within a given LATA through a single Pilgrim switch. The Parties also acknowledge that Pilgrim may, in the future, deploy additional switches in each LATA. For purposes of call termination, the initial Pilgrim switch shall be treated as an end office switch.
- 5.4.1.1.5 For purposes of call termination, this Agreement recognizes the unique status of traffic originated by and terminated to enhanced service providers. These parties have historically been subject to an access charge exemption by the FCC which permits the use of Basic Exchange Telecommunications Service as a substitute for Switched Access Service. Until any reform affecting enhanced service providers is

accomplished, the Parties agree to exempt traffic originated to and terminated by enhanced service providers from the reciprocal compensation arrangements of this Agreement.

- 5.4.1.1.6 Neither Party shall be responsible to the other for call termination charges associated with third party traffic that transits such Party's network.

5.4.2 Transport

- 5.4.2.1 If the Parties elect to each provision their own one-way trunks to the other Party's end office for the termination of local traffic, each Party will be responsible for its own expenses associated with the trunks and no transport charges will apply. Call termination charges shall apply as described above.
- 5.4.2.2 If one Party desires to purchase direct trunk transport from the other Party, the following rate elements will apply. Transport rate elements include the direct trunk transport facilities between the POI and the terminating Party's tandem or end office switches. The applicable rates are described in Appendix A.
- 5.4.2.3 Direct trunk transport facilities are provided as dedicated DS3 or DS1 facilities without the tandem switching functions, for the use of either Party between the Point of Interconnection and the terminating end office or tandem switch.
- 5.4.2.4 If the Parties elect to establish two-way direct trunks, the compensation for such jointly used 'shared' facilities shall be adjusted as follows. The nominal compensation shall be pursuant to the rates for direct trunk transport in Appendix A. The actual rate paid to the provider of the direct trunk facility shall be reduced to reflect the provider's use of that facility. The adjustment in the direct trunk transport rate shall be a percentage that reflects the provider's relative use (i.e., originating minutes of use) of the facility in the busy hour.
- 5.4.2.5 Multiplexing options are available at rates described in Appendix A.

5.4.3 Toll Traffic.

Applicable Switched Access Tariff rates, terms, and conditions apply to toll traffic routed to an access tandem, or directly to an end office. Relevant rate elements include Direct Trunk Transport or Tandem Switched Transport, Interconnection Charge, Local Switching, and Carrier Common Line, as appropriate.

5.4.4 Transit Traffic.

Applicable Switched Access, Type 2 or LIS transport rates apply for the use of USWC's network to transport transit traffic. For transiting local traffic, the applicable local transit rate applies to the originating Party per Appendix A. For transiting toll traffic, the Parties will charge the applicable Switched Access rates to the responsible carrier. For terminating transiting wireless traffic, the Parties will charge their applicable rates to the wireless provider. For transiting wireless traffic, the Parties will charge each other the applicable local transit rate.

5.5 LIS Interface Code Availability And Optional Features

5.5.1 Interface Code Availability.

Supervisory signaling specifications, and the applicable network channel interface codes for LIS trunks, are the same as those used for Feature Group D Switched Access Service, as described in the Parties' applicable Switched Access Tariffs.

5.5.2 Switching Options.

5.5.2.1 Inband MF or SS7 Out of Band Signaling.

Inband MF signaling and SS7 Out of Band Signaling are available for LIS trunks. MF signaling or SS7 Out-of-Band Signaling must be requested on the order for the new LIS trunks. Provisioning of the LIS trunks equipped with MF signaling or SS7 Out of Band Signaling is the same as that used for Feature Group D Switched Access. Common Channel Signaling Access Capability Service, as set forth in this Agreement, must be ordered by Pilgrim when SS7 Out-of-Band Signaling is requested on LIS trunks.

5.5.2.2 Clear Channel Capability.

Clear Channel Capability permits 24 DS0-64 Kbit/s services or 1.536 Mbit/s of information on the 1.544 Mbit/s line rate. Clear Channel Capability is available for LIS trunks equipped with SS7 Out-of-Band Signaling. Clear

Channel Capability is only available on trunks to USWC's access tandem switch or USWC's end office switches (where available); (Clear Channel Capability is not available on trunks to USWC's local tandem switches or end offices where it is currently not deployed. Pilgrim agrees to use the Bona Fide Request process to request clear channel capability for such additional switches. Prices for such additional Clear Channel Capability, if any, will be established through the BFR Process). Clear Channel Capability must be requested on the order for the new LIS trunks. The provisioning of the LIS trunks equipped with Clear Channel Capability is the same as that used for Feature Group D Switched Access Service. USWC will provide Pilgrim with a listing of USWC end offices, local tandems and access tandems equipped with Clear Channel Capability.

5.6 Measuring Local Interconnection Minutes

- 5.6.1 Measurement of terminating local interconnection minutes begins when the terminating LIS entry switch receives answer supervision from the called end user's end office indicating the called end user has answered. The measurement of terminating call usage over LIS trunks ends when the terminating LIS entry switch receives disconnect supervision from either the called end user's end office, indicating the called end user has disconnected, or Pilgrim's Point of Interconnection, whichever is recognized first by the entry switch.
- 5.6.2 USWC and Pilgrim are required to provide each other the proper call information (e.g., originating call party number and destination call party number, etc.) to enable each Party to issue bills in a complete and timely fashion.

5.7 Testing

5.7.1 Acceptance Testing

At the time of installation of an LIS trunk group, and at no additional charge, the Parties will cooperatively test the same parameters tested for terminating Feature Group D Switched Access Service. See USWC's applicable Switched Access Tariff for the specifications.

5.7.2 Testing Capabilities

- 5.7.2.1 Terminating LIS testing is provided where equipment is available, with the following test lines: seven-digit access to balance (100 type), milliwatt (102 type), nonsynchronous or synchronous, automatic transmission

measuring (105 type), data transmission (107 type), loop-around, short circuit, open circuit, and non-inverting digital loopback (108 type).

5.7.2.2 In addition to LIS acceptance testing, other tests are available (e.g., additional cooperative acceptance testing, automatic scheduled testing, cooperative scheduled testing, manual scheduled testing, and non-scheduled testing) at the applicable tariff rates.

5.8 Ordering

- 5.8.1 When ordering LIS, the ordering Party shall specify on the service order: 1) the type and number of Interconnection facilities to terminate at the Point of Interconnection in the serving wire center; 2) the type of interoffice transport, (i.e., Direct Trunk Transport or Tandem Switched Transport); 3) the peak busy hour CCS from the Pilgrim end office; 4) the number of trunks to be provisioned at a local exchange office or tandem; 5) and any optional features. When the ordering Party requests facilities, routing, or optional features different than those determined to be available, the Parties will work cooperatively in determining an acceptable configuration, based on available facilities, equipment and routing plans.
- 5.8.2 When the ordering Party initially orders a DS3 Interconnection facility, in conjunction with Tandem Switched Transport to a tandem, or DS3 Direct Trunk Transport facilities to a tandem or local exchange office, the provider will forward the appropriate DS1 facility record information necessary to identify the circuit facility assignment. On subsequent orders utilizing existing DS3 Interconnection facilities, or DS3 Direct Trunk Transport facilities, the provider will assign the DS1 facility to the DS3 Interconnection facility or DS3 Direct Trunk Transport facility, as directed by the ordering Party.
- 5.8.3 A joint planning meeting will precede Pilgrim and USWC trunking orders. These meetings will result in the transmittal of Access Service Requests (ASRs) to initiate order activity. A Party requesting tandem Interconnection will provide its best estimate of the traffic distribution to each end office subtending the tandem.
- 5.8.4 Service intervals and due dates for the initial establishment of trunking arrangements at each location of Interconnection between the Parties will be determined on an individual case basis.
- 5.8.5 Service intervals and due dates for the establishment of subsequent trunking arrangements for Interconnection between the Parties, will be in accordance with the guidelines for LIS.

5.9 Billing Arrangements

- 5.9.1 USWC and Pilgrim desire to submit separate bills, pursuant to their separate tariffs, to Interexchange Carriers for their respective portions of jointly provided Switched Access Service.

Based on the negotiated POI, the Parties will agree on a meet point percentage to enable the joint provisioning and billing of Switched Access Services to third parties in conformance with the Meet-Point Billing guidelines adopted by and contained in the Ordering and Billing Forum's MECAB and MECOD documents and referenced in USWC's Switched Access Tariffs. The Parties understand and agree that MPB arrangements are available and functional only to/from Interexchange Carriers who directly connect with the tandem(s) that Pilgrim sub-tends in each LATA.

- 5.9.2 The Parties will use reasonable efforts, individually and collectively, to maintain provisions in their respective federal and state access tariffs (if any), and/or provisions within the National Exchange Carrier Association ("NECA") Tariff No. 4, or any successor tariff (if any), sufficient to reflect this MPB arrangement, including MPB percentages.
- 5.9.3 As detailed in the MECAB document, Pilgrim and USWC will exchange all information necessary to bill third parties for Switched Access Services traffic jointly handled by Pilgrim and USWC via the meet point arrangement in a timely fashion. Information shall be exchanged in Exchange Message Record ("EMR") format (Bellcore Standard BR 010-200-010, as amended) on magnetic tape or via a mutually acceptable electronic file transfer protocol. The Parties will exchange records pursuant to this paragraph without additional compensation.
- 5.9.4 The Parties will agree upon reasonable audit standards and other procedures as required to ensure billing accuracy.
- 5.9.5 Each Party will bill the IXCs the appropriate rate elements in accordance with their respective interstate and intrastate tariffs, as follows:

<u>Rate Element</u>	<u>Billing Company</u>
Carrier Common Line	Dial Tone Provider
Local Switching	Dial Tone Provider
Interconnection Charge	Dial Tone Provider
Local Transport Termination	Based on negotiated BIP
Local Transport Facility (also called Tandem Transmission per mile)	Based on negotiated BIP
Tandem Switching	Access Tandem Provider
Entrance Facility	Access Tandem Provider

5.9.6 For originating 800/888 traffic routed to an access tandem, the tandem provider will perform 800/888 database inquiry and translation functions and bill the inquiry charge and translation charge (if any) to the Interexchange Carrier pursuant to tariff. For all originating 800/888 database inquiry and translation functions, the charges will be billed to the Interexchange Carrier transporting the call.

5.10 Mileage Measurement

Where required, the mileage measurement for LIS facilities and trunks is determined in the same manner as the mileage measurement for Feature Group D Switched Access Service.

5.11 Construction Charges

If applicable, construction charges will apply as detailed in the Construction Charges section of this Agreement.

6. INTERCONNECTION

6.1 Exchange of Local Traffic

6.1.1 Interconnection is the linking of the USWC and Pilgrim networks for the mutual exchange of traffic and for Pilgrim access to unbundled Network Elements. Interconnection does not include the transport and termination of traffic. Interconnection is provided by Virtual or Physical Collocation, entrance facilities or Mid-Span Meet arrangements.

6.1.2 USWC will provide Interconnection at the line side of the local switch, the trunk side of the local switch, trunk interconnection points of the tandem switch, central office cross-connect points, including cross-connection of USWC Loops to Pilgrim equipment and USWC dedicated transport to Pilgrim equipment as described in Sections 7.4 and 7.5 below, and the location of the signaling transfer points necessary to exchange traffic and access call related databases.

6.2 Mid-Span Meet POI

6.2.1 A Mid-Span Meet POI is a negotiated point of interface, limited to the interconnection of facilities between one Party's switch and the other Party's switch. The actual physical Point of Interface and facilities used will be subject to negotiations between the Parties. Each Party will be responsible for its portion of the build to the Mid-Span Meet POI, if the meet point arrangement is used exclusively for the exchange of local traffic.

6.2.2 If the Mid-Span Meet arrangement is to be used for access to unbundled Network Elements, Pilgrim must pay the portion of the economic costs of the Mid-Span Meet arrangement used by Pilgrim for access to unbundled Network Elements.

6.3 Collocation

Interconnection may be accomplished through either Virtual, Physical, or Common Collocation. The terms and conditions under which Collocation will be available are described in the Collocation section of this Agreement.

6.4 Entrance Facility (EF2)

Interconnection may be accomplished through the provision of an entrance facility. An entrance facility extends from the serving Wire Center of the provider to the other Party's switch location. Entrance facilities may not extend beyond the area described by the provider's serving Wire Center. The rates for entrance facilities (EF2) are provided in Appendix A. Entrance facilities may not be connected to USWC's unbundled Network Elements; provided however, USWC shall connect USWC unbundled Network Elements, including dedicated transport, to Pilgrim's collocated equipment as provided for in Entrance Facility (EF1).

6.5 Quality of Interconnection

USWC will not, for the purpose of Interconnection, provide to Pilgrim less favorable terms and conditions than USWC provides itself or in a manner less efficient than it would impose on itself. The quality of Interconnection will be at least equal to that of USWC.

Both Parties agree to manage their network switches in accordance with the Bellcore LSSGR.

6.6 Points of Interface (POI)

Upon the request for specific point to point routing, USWC will make available to Pilgrim information indicating the location and technical characteristics of USWC's network facilities. The following alternatives are negotiable: (1) a DS1 or DS3 entrance facility; (2) Virtual Collocation; (3) Physical Collocation; (4) Common Collocation, and (5) negotiated Mid-Span Meet facilities. Each Party is responsible for providing its own facilities up to the Mid-Span Meet POI. The Parties will negotiate the facilities arrangement between their networks.

6.7 Trunking Requirements

6.7.1 The Parties agree to provide designed Interconnection facilities that meet the same technical criteria and service standards, such as probability of

blocking in peak hours and transmission standards, in accordance with industry standards.

6.7.2 Two-way trunk groups will be established wherever possible. Exceptions to this provision will be based on billing, signaling, and network requirements. For example, (1) billing requirements - switched access vs. local traffic, (2) signaling requirements - MF vs. SS7, and (3) network requirements - directory assistance traffic to TOPS tandems. The following is the current list of traffic types that require separate trunk groups, unless specifically otherwise stated in this Agreement.

- 6.7.2.1 IntraLATA Toll and Switched Access trunks
- 6.7.2.2 EAS/Local trunks
- 6.7.2.3 Directory Assistance trunks
- 6.7.2.4 911/E911 trunks
- 6.7.2.5 Operator services trunks
- 6.7.2.6 Commercial Mobile Radio Service/Wireless traffic for which Pilgrim serves as the transit provider between the CMRS provider and USWC.
- 6.7.2.7 Transit IntraLATA Toll
- 6.7.2.8 Transit local
- 6.7.2.9 Meet-Point Billing Trunks (for the joint provision of Switched Access)
- 6.7.2.10 Mass calling trunks, if applicable

6.7.3 Trunk group connections will be made at a DS1 or multiple DS1 level for exchange of EAS/Local, IntraLATA Toll, wireless/Commercial Mobile Radio Service, and Switched Access traffic. Ancillary service trunk groups will be made below a DS1 level, as negotiated.

6.7.4 The Parties will provide Common Channel Signaling (CCS) to one another, where available, in conjunction with all EAS/Local trunk circuits. All CCS signaling parameters will be provided including Calling Party Number (CPN), originating line information (OLI), calling party category, charge number, etc. All privacy indicators will be honored.

6.7.5 Where CCS is not available, in-band multi-frequency (MF) wink start signaling will be provided. When the Parties interconnect via CCS for jointly provided Switched Access Service, the tandem provider will provide MF/CCS interworking as required for Interconnection with Interexchange Carriers who use MF signaling.

6.7.6 The Parties will follow all Ordering and Billing Forum adopted standards pertaining to CIC/OZZ codes.

6.7.7 USWC will cooperate in the provision of TNS (Transit Network Selection) for the joint provision of Switched Access Service.

6.7.8 The Parties shall terminate EAS/Local traffic exclusively on EAS/Local trunk groups. No EAS/Local trunk groups shall be terminated on USWC's access tandems.

6.7.9 The Parties agree to terminate local traffic in the same EAS/Local area as such traffic originated.

6.8 Interconnection Forecasting

6.8.1 The Parties agree that during the first year of Interconnection, joint forecasting and planning meetings will take place no less frequently than once per quarter.

6.8.2 The Parties shall establish joint forecasting responsibilities for traffic utilization over trunk groups. Intercompany forecast information must be provided by the Parties to each other four times a year. The quarterly forecasts shall include forecasted requirements for each trunk group identified in Paragraph 6.7.2 of this Section. In addition, the forecast shall include, for tandem-switched traffic, the quantity of tandem-switched traffic forecasted for each subtending end office. The Parties recognize that, to the extent historical traffic data can be shared between the Parties, the accuracy of the forecasts will improve. Forecasts shall be for a minimum of three (current and plus-1 and plus-2) years and shall include:

6.8.2.1 The use of Common Language Location Identifier (CLLI-MSG), which are described in Bellcore documents BR 795-100-100 and BR 795-400-100;

6.8.2.2 A description of major network projects anticipated for the following six months that could affect the other Party. Major network projects include trunking or network rearrangements, shifts in anticipated traffic patterns, or other activities that are reflected by a significant increase or decrease in trunking demand for the following forecasting period. This planning will include the issues of network capacity, forecasting and compensation calculation, where appropriate.

6.8.3 If differences in quarterly forecasts of the Parties vary by more than 24 additional DS0 two-way trunks for each local interconnection trunk group, the Parties shall meet to reconcile the forecast to within 24 DS0 trunks.

6.8.4 If a trunk group is under 75 percent of centum call seconds (ccs) capacity on a monthly average basis for each month of any three month period, either Party may request to resize the trunk group, which resizing will not

be unreasonably withheld. If a resizing occurs, the trunk group shall not be left with less than 25 percent excess capacity.

- 6.8.5 Each Party shall provide a specified point of contact for planning, forecasting and trunk servicing purposes.

6.9 Service Interruptions

- 6.9.1 Standards and procedures for notification of trunk disconnects will be jointly developed by the Parties. Neither Party shall be expected to maintain active status for a trunk disconnected by the other Party for an extended or indefinite period of time. Collectively, the Parties will use their best good faith efforts to complete and agree on such plan.
- 6.9.2 With respect to traffic exchanged by the Parties, the characteristics and methods of operation of any circuits, facilities or equipment of either Party connected with the services, facilities or equipment of the other Party pursuant to this Agreement shall not: 1) interfere with or impair service over any facilities of the other Party; its affiliated companies, or its connecting and concurring carriers involved in its services; 2) cause damage to their plant; 3) violate any applicable law or regulation regarding the invasion of privacy of any communications carried over the Party's facilities; or 4) create hazards to the employees of either Party or to the public. Each of these requirements is hereinafter referred to as an "Impairment of Service".
- 6.9.3 With respect to local traffic exchanged by the Parties, if either Party causes an Impairment of Service, as set forth in this Section, the Party whose network or service is being impaired (the "Impaired Party") shall promptly notify the Party causing the Impairment of Service (the "Impairing Party") of the nature and location of the problem. The Impaired Party shall advise the Impairing Party that, unless promptly rectified, a temporary discontinuance of the use of any circuit, facility or equipment may be required. The Impairing Party and the Impaired Party agree to work together to attempt to promptly resolve the Impairment of Service. If the Impairing Party is unable to promptly remedy the Impairment of Service, the Impaired Party may temporarily discontinue use of the affected circuit, facility or equipment.
- 6.9.4 To facilitate trouble reporting and to coordinate the repair of the service provided by each Party to the other under this Agreement, each Party shall designate a Trouble Reporting Control Office (TRCO) for such service.
- 6.9.5 Where new facilities, services and arrangements are installed, the TRCO shall ensure that continuity exists and take appropriate transmission measurements before advising the other Party that the new circuit is ready for service.

- 6.9.6 Each Party shall furnish a trouble reporting telephone number for the designated TRCO. This number shall give access to the location where facility records are normally located and where current status reports on any trouble reports are readily available. Alternative out-of-hours procedures shall be established to ensure access to a location that is staffed and has the authority to initiate corrective action.
- 6.9.7 Before either Party reports a trouble condition, each shall use its best efforts to isolate the trouble to the other's facilities.
 - 6.9.7.1 In cases where a trouble condition affects a significant portion of the other's service, the Parties shall assign the same priority provided to other interconnecting carriers.
 - 6.9.7.2 The Parties shall cooperate in isolating trouble conditions.

7. COLLOCATION

7.1 General Description

- 7.1.1 Collocation allows Pilgrim to obtain dedicated space in a USWC Wire Center and to place equipment in such spaces to interconnect with the USWC network. Pilgrim may request Collocation at other USWC locations not otherwise specified in this Agreement pursuant to the BFR Process or through additional Interconnection negotiations under the Act. USWC will provide the resources necessary for the operation and economical use of collocated equipment. USWC designated POIs for network interconnection can be established for Virtual, Common, or Physical Collocation arrangements.
- 7.1.2 Except when Pilgrim purchases USWC's unbundled network transmission elements, or the services or facilities of another carrier, Pilgrim will construct its own fiber optic cable to the USWC-designated Point of Interconnection. USWC will extend Pilgrim's fiber optic cable from the POI to the cable vault within the Wire Center. For the purposes of Collocation, the POI shall be that point outside the USWC central office where the Pilgrim and USWC fibers meet. If necessary, USWC may bring the cable into compliance with USWC internal fire code standards and extend the cable to the collocated space.
- 7.1.3 Pilgrim will be provided two points of entry into the USWC Wire Center only when there are at least two existing entry points for USWC cable and when there are vacant entrance ducts in both. USWC will promptly remove any unused cabling to free up entrance ducts when no other ducts are available. Cable entry will be limited to fiber facilities.

- 7.1.4 Pilgrim may collocate transmission equipment to terminate basic transmission facilities. In addition, Pilgrim may collocate any transmission equipment used or useful to it in accessing or managing unbundled network elements, including, but not limited to, digital subscriber line access multiplexers (“DSLAMs”). Pilgrim may request Collocation of other equipment pursuant to the BFR Process or through additional Interconnection negotiations under the Act. When Pilgrim installs equipment, Pilgrim must identify what equipment will be installed, to the extent reasonably necessary for USWC to determine the required power, floor loading, heat release, environmental particulant level, and HVAC requirements.
- 7.1.5 Pilgrim will only collocate equipment that is used or useful for interconnection or access to unbundled network elements, in accordance with FCC Rule 51.323(b). Nothing herein requires USWC to permit collocation of equipment used solely for switching or solely to provide enhanced services; provided however, that USWC may not place any limitations on the ability of Pilgrim to use all the features, functions, and capabilities of equipment collocated hereunder, including, but not limited to switching and routing features and functions and enhanced services functionalities. USWC will permit collocation of any equipment required by law, unless USWC proves to the Commission that the equipment will not be actually used by Pilgrim for the purpose of obtaining interconnection or access to unbundled network elements. Collocation will be provided in accordance with FCC Rule 51.321(c).
- 7.1.6 Nothing in this part shall be construed to limit Pilgrim’s ability to obtain Virtual, Common, and Physical Collocation in a single location.
- 7.1.7 Denial of Space
- 7.1.7.1 If USWC denies a request for Collocation in a USWC Wire Center due to space limitations, USWC shall allow Pilgrim representatives to tour the entire Wire Center premises escorted by USWC personnel within ten (10) days of the denial of space. Such tour shall be without charge to Pilgrim. If, after the tour of the premises, USWC and Pilgrim disagree about whether space limitations at the Wire Center make Collocation impractical, USWC and Pilgrim may present their argument to the Commission.
- 7.1.7.2 USWC shall submit to the Commission, subject to any protective order as the Commission may deem necessary, detailed floor plans or diagrams of any premises where physical collocation is not practical because of space limitations.

- 7.1.7.3 Upon request, USWC will submit to Pilgrim a report indicating USWC's available collocation space in a particular USWC premise, in accordance with FCC Rule 51.321(h).
- 7.1.7.4 USWC will maintain a publicly available document, posted for viewing on the Internet, indicating all premises that are full, and will update this document within ten (10) calendar days of the date at which a premises runs out of physical space.
- 7.1.7.5 If a request for Collocation is denied due to a lack of space in a USWC Central Office, USWC will remove obsolete equipment in accordance with FCC Rule 51.321(i) at no charge. Pilgrim may request USWC to provide a cost quote for the rearrangement of space and/or equipment. Quotes will be developed within sixty (60) business days including the estimated time frames for the work that is required in order to satisfy the Collocation request. Pilgrim has thirty (30) business days to accept the quote. If Pilgrim accepts the quote, work will begin on receipt of 50% of the quoted charges and proof of insurance, with the balance due on completion.
- 7.1.7.6 Rearrangement may include grooming and space reclamation specifically required to accommodate Pilgrim's collocation request. Pilgrim shall be responsible to pay only for space reclamation associated with that collocation space requested by Pilgrim. Grooming is the moving of circuits from working equipment to other equipment with similar functionality for the purpose of providing space for interconnection. Space reclamation is the recovery of administrative space that can be reconditioned for the placement of equipment for the purposes of Collocation.

7.1.8 Cross Connects

USWC shall permit Pilgrim to connect to another collocated Telecommunications Carrier under the provisions of FCC Rule 51.323(h).

7.1.9 Shared Space Caged Physical Collocation

Shared Space Caged Physical Collocation allows two or more Telecommunications Carriers to share a single collocation enclosure. Under Shared Physical Collocation, one Telecommunications Carrier obtains a Caged Physical Collocation arrangement, and another Telecommunications Carrier, pursuant to the terms of its approved

interconnection agreement, may share use of that space, in accordance with terms and conditions agreed to between the two (2) Telecommunications Carriers. USWC will not increase the overall cost of site preparation or nonrecurring charges for shared collocation cages above the cost for providing a cage of similar dimensions and material to a single collocating Telecommunications Carrier. Furthermore, USWC will prorate the charge for site conditioning and preparation undertaken by USWC to construct the shared collocation cage or condition the space for collocation use, regardless of how many carriers actually collocate in that cage, by determining the total charge for site preparation and allocating that charge to a collocating Telecommunications Carrier based on the percentage of the total space utilized by that Telecommunications Carrier. USWC shall not place unreasonable restrictions on Pilgrim's use of a collocation cage, such as limiting Pilgrim's ability to contract with other Telecommunications Carriers to share Pilgrim's collocation cage in a sublease-type arrangement. In addition, if two or more Telecommunications Carriers who have interconnection agreements with USWC utilize a shared collocation arrangement, USWC shall permit each Telecommunications Carrier to order UNEs to and provision service from that shared collocation space, regardless of which Telecommunications Carrier was the original collocator. NEBS1 safety standards are required.

7.1.10 Rates Elements - Shared Space Cage Physical Collocation

All rates for Caged Physical Collocation shall apply and shall be distributed among the Telecommunications Carriers sharing the caged space.

7.1.11 Ordering – Shared Space Caged Physical Collocation

All ordering provisions for Caged Physical Collocation shall also apply to Shared Space Caged Physical Collocation. When desiring space in another Telecommunications Carrier's Caged Physical Collocation, Pilgrim must obtain a Letter of Authorization from the original Telecommunications Carrier. Such Letter of Authorization must accompany Pilgrim's Collocation Order Form.

7.2 Virtual Collocation

7.2.1 USWC shall provide Virtual Collocation for the purpose of Interconnection or access to unbundled Network Elements subject to the rates, terms and conditions of this Agreement.

7.2.2 Pilgrim will not have physical access to the USWC wire center building pursuant to a Virtual Collocation arrangement.

- 7.2.3 Pilgrim will be responsible for obtaining and providing to USWC administrative codes, e.g., common language codes, for all equipment specified by Pilgrim and installed in Wire Center buildings.
- 7.2.4 Pilgrim will be responsible for payment of training of USWC employees for the maintenance, operation and installation of Pilgrim's virtually collocated equipment when that equipment is different than the equipment used by USWC.
- 7.2.5 Pilgrim will be responsible for payment of charges incurred in the maintenance and/or repair of Pilgrim's virtually collocated equipment.
- 7.2.6 USWC does not guarantee the reliability of Pilgrim's virtually collocated equipment.
- 7.2.7 Pilgrim is responsible for ensuring the functionality of virtually collocated SONET equipment provided by different manufacturers.
- 7.2.8 Maintenance Labor, Inspector Labor, Engineering Labor and Equipment Labor business hours are considered to be Monday through Friday, 8:00am to 5:00pm (local time) and after business hours are after 5:00pm and before 8:00am (local time), Monday through Friday, all day Saturday, Sunday and holidays.
- 7.2.9 Pilgrim will transfer possession of Pilgrim's virtually collocated equipment to USWC via a no cost lease. The sole purpose of the lease is to provide USWC with exclusive possessory rights to Pilgrim's virtually collocated equipment. Title to the Pilgrim virtually collocated equipment shall not pass to USWC.
- 7.2.10 Installation and maintenance of Pilgrim's virtually collocated equipment will be performed by USWC or a USWC authorized vendor.
- 7.2.11 Pilgrim shall ensure that upon receipt of the Pilgrim virtually collocated equipment by USWC, all warranties and access to ongoing technical support are passed through to USWC, all at Pilgrim's expense. Pilgrim shall advise the manufacturer and seller of the virtually collocated equipment that Pilgrim's equipment will be possessed, installed and maintained by USWC.
- 7.2.12 Pilgrim's virtually collocated equipment must comply with the Bellcore Network Equipment Building System (NEBS) Generic Equipment Requirements TR-NWT-000063, USWC Wire Center environmental and transmission standards and any statutory (local, state or federal) and/or regulatory requirements in effect at the time of equipment installation or that subsequently become effective. Pilgrim shall provide USWC interface specifications (e.g., electrical, functional, physical and software) of Pilgrim's virtually collocated equipment.

- 7.2.13 USWC may restrict the type of virtually collocated equipment. USWC will only permit basic transmission terminating equipment to be virtually collocated by Pilgrim. Pilgrim may request Collocation of other equipment pursuant to the BFR Process or through additional Interconnection negotiations under the Act.
- 7.2.14 Pilgrim must specify all software options and associated plug-ins for its virtually collocated equipment.
- 7.2.15 Pilgrim is responsible for purchasing and maintaining a supply of spares. Upon failure of Pilgrim's virtually collocated equipment, Pilgrim is responsible for transportation and delivery of maintenance spares to USWC at the Wire Center housing the failed equipment.

7.3 Physical Collocation

- 7.3.1 USWC shall provide to Pilgrim Physical Collocation of equipment necessary for Interconnection or for access to unbundled Network Elements, except that USWC may provide for Virtual Collocation if USWC demonstrates to the Commission that Physical Collocation is not practical for technical reasons or because of space limitations, as provided in Section 251(c)(6) of the Act. USWC shall provide such Collocation for the purpose of Interconnection or access to unbundled Network Elements, except as otherwise mutually agreed to in writing by the Parties or as required by the FCC or the appropriate Commission subject to the rates, terms and conditions of this Agreement.
- 7.3.2 Where Pilgrim is virtually collocated in a premises which was initially prepared for Virtual Collocation, Pilgrim may elect to (i) retain its Virtual Collocation in that premises and expand that Virtual Collocation according to the rates, terms and conditions of this Agreement, or (ii) unless it is not practical for technical reasons or because of space limitations, convert its Virtual Collocation at such premises to Physical Collocation, in which case Pilgrim shall coordinate the construction and rearrangement with USWC of its equipment (IDLC and transmission) and circuits for which Pilgrim shall pay USWC at applicable rates, and pursuant to the other terms and conditions in this Agreement. In addition, all applicable Physical Collocation recurring charges shall apply.
- 7.3.3 Pilgrim will be allowed access to the POI on non-discriminatory terms. Pilgrim owns and is responsible for the installation, maintenance and repair of its transmission equipment located within the space rented from USWC.
- 7.3.4 Pilgrim must use leased space promptly and may not warehouse space for later use or sublease to another provider. Physical Collocation is

offered in Wire Centers on a space-available, first come, first-served basis.

- 7.3.5 The minimum standard leasable amount of floor space is 100 square feet. Pilgrim must efficiently use the leased space; no more than 50% of the floor space may be used for storage cabinets and work surfaces. The Commission will be the final arbitrator in points of dispute between the Parties. USWC shall accommodate Pilgrim's request for physical Collocation ahead of any other entity to the extent that Pilgrim's request for physical Collocation preceded the request of such other entity. The Commission will be the final arbitrator in points of dispute between the Parties with respect to the availability of Collocation space.
- 7.3.6 Pilgrim's leased floor space will be separated from other competitive providers and USWC space through a cage enclosure except in the case of common Collocation. Pilgrim may elect to have USWC construct the enclosure, or choose from USWC approved contractors to construct the cage, meeting USWC's installation Technical Publication 77350. Pilgrim must determine at the time of application whether USWC or an approved contractor will construct the cage enclosure.
- 7.3.7 The following standard features will be provided by USWC:
 - 7.3.7.1 Heating, ventilation and air conditioning.
 - 7.3.7.2 Smoke/fire detection and any other building code requirement.
- 7.3.8 USWC Responsibilities.
 - 7.3.8.1 Design the floor space within each wire center which will constitute Pilgrim's leased space.
 - 7.3.8.2 Ensure that the necessary construction work is performed to build Pilgrim's leased physical space and the riser from the vault to the leased physical space.
 - 7.3.8.3 Develop a quotation specific to Pilgrim's request.
 - 7.3.8.4 Extend USWC-provided and owned fiber optic cable from the POI through the cable vault and extend the cable to Pilgrim's leased physical space or place the cable in fire retardant tubing prior to extension to Pilgrim's leased physical space.
 - 7.3.8.5 Installation and maintenance and all related activity necessary to provide channel termination between USWC's and Pilgrim's equipment.

7.3.8.6 Work cooperatively with Pilgrim in matters of joint testing and maintenance.

7.3.8.7 USWC shall install and pre-provision copper cable from USWC's cross connect device to Pilgrim's mini-MDF, where present, in its Collocation space.

7.3.9 Pilgrim Responsibilities

7.3.9.1 Determine who constructs the cage, when requested by Pilgrim, or enclosure for the physical space.

7.3.9.2 Where applicable, procure, install and maintain all fiber optic facilities up to the USWC designated POI.

Where applicable, procure and provide all necessary fiber interconnection cable and connectors from the USWC fiber distribution panel and the cage enclosure.

Where applicable, procure and provide all necessary cable and connectors from the Collocation space to the USWC cross connection device.

7.3.9.3 Install, maintain, repair and service all Pilgrim's equipment located in the leased physical space.

7.3.9.4 Ensure that all equipment installed by Pilgrim complies with Bellcore Network Equipment Building System Generic Equipment requirements, USWC Wire Center environmental and transmission standards, and any statutory (local, federal, or state) or regulatory requirements in effect at the time of equipment installation or that subsequently become effective.

7.3.10 Once Pilgrim has accepted its leased physical space and has made its final payment USWC will provide Pilgrim with Common Language Location Identifier ("CLLI") code assignments as soon as the Trunk Integrated Record Keeping System ("TIRKS") data base is updated with Pilgrim's information. Thereafter, Pilgrim may order its DS0, DS1, DS3 or other Expanded Interconnection Channel Terminations.

7.3.11 USWC shall provide Pilgrim dark fiber as an unbundled network element at a cost-based price to be determined by the Commission. Pilgrim may not extend USWC dark fiber to Pilgrim's leased physical space or connect DS1/DS3 Channel Terminations to USWC dark fiber.

- 7.3.12 If, at any time, USWC reasonably determines that the equipment or the installation does not meet standard industry requirements, such failure being due to actions of Pilgrim or its agents, Pilgrim will be responsible for the costs associated with the removal, modification to, or installation of the equipment to bring it into compliance. If Pilgrim fails to correct any non-compliance within thirty (30) days or as soon as reasonably practical after the receipt of written notice of the non-compliance, USWC may have the equipment removed or the condition corrected at Pilgrim's expense.
- 7.3.13 If, during installation, USWC reasonably determines that Pilgrim activities or equipment are unsafe, non-industry standard or in violation of any applicable laws or regulations, USWC has the right to stop work until the situation is remedied. If such conditions pose an immediate threat to the safety of USWC employees, interfere with the performance of USWC's service obligations, or pose an immediate threat to the physical integrity of the conduit system or the cable facilities, USWC may perform such work and/or take action as is necessary to correct the condition at Pilgrim's expense.

Pilgrim may order and USWC shall provide a regular business line at Pilgrim's expense at the collocated space.

USWC will inform Pilgrim by telephone of any emergency related activity that USWC or its subcontractors may be performing which could potentially affect the equipment in the collocated space occupied by Pilgrim.

USWC shall construct the collocated space in compliance with the agreed upon request for cable holes, ground bars, doors, and convenience outlets, etc. Any deviation to the agreed upon request must be approved by Pilgrim.

USWC will provide Pilgrim with reasonable notice of scheduled AC or DC power work or related activity in the collocated facility that will or might cause an outage or any type of power disruption to Pilgrim equipment located in the USWC facility. USWC will notify Pilgrim immediately of any emergency power activity that would impact Pilgrim equipment.

USWC will take Pilgrim requests for Collocation space into account when renovating existing facilities and constructing new facilities.

Other than reasonable security restrictions, USWC shall place no restriction on access to the Pilgrim collocated space by Pilgrim's employees and designated agents. Such space shall be available to Pilgrim designated agents twenty-four (24) hours per day each day of the week. In no case shall any reasonable security restrictions be more restrictive than those USWC places on their own personnel. An Inspector call-out may be required after normal business hours.

7.4 Common Collocation

- 7.4.1 Common Collocation is a form of physical Collocation that is provided by USWC to Pilgrim in a non-caged area of a USWC central office. Pilgrim may order Common Collocation space on a single frame bay increment. USWC's standard equipment bay configurations will apply. USWC shall provide such space in an efficient manner that minimizes the time and costs. For example, USWC shall provide space, where available, in existing USWC line ups, under existing cable racking and ironwork, where there is existing HVAC and proximately available power supplies.
- 7.4.2 Pilgrim may place and maintain its own equipment in Common Collocation space at its own expense. Common Collocation will allow Pilgrim to connect its facilities to USWC unbundled elements via the SPOT frame where such a frame exists. USWC shall not be required to build a SPOT frame in any central office.
- 7.4.3. Pilgrim may submit a request for multiple bay space and, where available, USWC will provide such capability in adjacent bays. When contiguous space is not available, bays may be co-mingled with other CLEC or USWC equipment bays. Pilgrim may request through the USWC Space Reclamation Policy as approved by the Commission, a price quote to rearrange USWC equipment to provide Pilgrim with adjacent space.

7.5 CLEC Combination of Unbundled Network Elements

7.5.1 General Description

7.5.1.1 The SPOT frame is located in common space within USWC's Central Office. The SPOT frame consists of DS0, DS1, DS3 tie cables, terminations on the SPOT frame and terminations on the applicable USWC frame.

7.5.1.2 USWC agrees to perform the cross connects for Pilgrim at the appropriate cross connect device, as described in Section 7.5.1.2.1 below, subject to all of the provisions of this section. The Parties agree that there is a difference between recombining all USWC unbundled Network Elements and combining some USWC unbundled Network Elements with Pilgrim's collocated equipment. Among other things, however, the Parties disagree as to whether both recombining all or combining some unbundled Network Elements are within the scope of the pending appeal to the Supreme Court of the 8th Circuit Court of Appeals decision regarding combinations of unbundled Network Elements. Notwithstanding this disagreement, USWC agrees that Pilgrim is

entitled to certainty in its relationship with USWC as to combination of some USWC unbundled Network Elements to Pilgrim's collocated equipment. Thus, without waiving any of their legal rights, factual contentions, or arguments concerning the proper application of fact and law, the Parties agree that USWC will perform the cross connects for Pilgrim, as described in Section 7.5.1.2.1 below, until the date of the Supreme Court's ruling on the 8th Circuit Court of Appeals decision, December 31, 2000, or the date the arbitration discussed below, if any, is concluded, whichever date is the last to occur. Responsibility for cross connects after this date must be renegotiated by the Parties, and either Party may seek renegotiation of responsibility for cross connects as early as June 1, 2000. In the event the Parties cannot agree as to responsibility for cross connects during such renegotiation, the Parties agree to: (1) arbitrate the issue under the Dispute Resolution clause of this Agreement; and (2) take all reasonable steps to ensure resolution of the arbitration by December 31, 2000; provided, however, that USWC will continue to perform the cross connects for Pilgrim until the arbitration is concluded. In the event the Parties do not mutually agree to a different arrangement by December 31, 2000 and neither Party invokes the Dispute Resolution clause then USWC will continue to perform the cross connections as set forth herein.

7.5.1.2.1 USWC shall perform the cross connects of USWC unbundled Loops and Dedicated Transport to Pilgrim collocated equipment utilizing the Expanded Interconnection Channel Terminations ("EICTs") on the appropriate cross connect device. The Parties agree that the charges for such cross connections (EICT) are included in Appendix A. Pilgrim and USWC agree that Pilgrim will cross connect USWC unbundled Network Elements to USWC unbundled Network Elements at the appropriate cross connect device. The Parties shall work cooperatively to ensure that Pilgrim orders and USWC provisions unbundled Loops and Dedicated Transport in conjunction with their corresponding EICT, in which case the EICT nonrecurring charge is waived.

7.5.1.3 USWC will provide Pilgrim with access to the Central Office for the purpose of running jumpers on the SPOT frame when needed to install, maintain, operate or upgrade Pilgrim equipment. This access will be equal to the access USWC provides itself for similar purposes.

7.5.1.4 The SPOT frame or the applicable USWC frame will be the location where all USWC unbundled Network Elements and USWC's equipment are terminated. Pilgrim may run

jumpers on the SPOT frame to make connections in two basic types of configurations:

USWC unbundled Network Elements to USWC unbundled Network Elements;

Pilgrim's equipment to another Co-Provider's equipment.

7.5.1.5 The SPOT frame is the standard demarcation point between Pilgrim and USWC owned network facilities and equipment as well as the demarcation between unbundled Network Elements. This demarcation point can be used as the designated test point for Pilgrim. The demarcation point shall include an acceptable non-intrusive connector block equipped with continuity coils for testing, such that a jumper lift will not normally be required. Any modification to this testing capability shall be mutually agreed upon by the Parties.

7.5.2 Charges

7.5.2.1 The nonrecurring rates for the SPOT frame recover USWC's expenses (including engineering and installation) for all DS0, DS1, DS3 terminations, including tie cables, SPOT frame terminations, and terminations on the applicable USWC frame.

7.5.2.2 The recurring rate element for the SPOT frame recovers USWC's expense for the maintenance and administration for all DS0, DS1, DS3 terminations, including tie cables, SPOT frame terminations, and termination on the applicable USWC frame.

7.5.3 All USWC terminations on the SPOT frame will be given a frame address. USWC will establish and maintain frame address records for USWC's terminations. USWC will provide the frame address to Pilgrim for each USWC unbundled Network Element ordered and will maintain assignment records of such USWC unbundled Network Elements (Loop, local switching, etc.) and terminations (tie cable pair) on the SPOT frame.

7.5.4 Pilgrim will maintain assignment records for the terminations of Pilgrim's equipment on the SPOT frame or applicable USWC frame. Pilgrim will maintain the assignment records for those frame addresses involved in connecting Pilgrim's equipment to USWC unbundled Network Elements and the USWC unbundled Network Elements connected to USWC unbundled Network Elements. Pilgrim will transmit to USWC the appropriate frame assignment information for the cross connect on the unbundled Loop order.

7.5.5 Pilgrim will be required to make the jumper wire connection between frame addresses to complete Pilgrim's circuit where Pilgrim seeks to combine USWC Unbundled Network Elements to each other and not to Pilgrim's collocated equipment. Where Pilgrim seeks to connect its equipment to USWC's Unbundled Network Elements, USWC shall run all necessary jumpers and make all cross connections.

7.5.6 Ordering

7.5.6.1 When Pilgrim submits a Collocation request, USWC will respond confirming space availability for such request within twenty one (21) calendar days, or sooner, on a best effort basis. Within thirty (30) business days of USWC providing the space availability confirmation to Pilgrim, Pilgrim will accept or reject the USWC confirmation. Acceptance by Pilgrim shall require payment to USWC, fifty percent (50%) of the flat rated charges set forth in Appendix A; the remaining fifty percent (50%) shall be paid upon delivery of the Common Collocation space to Pilgrim.

7.5.6.2 Pursuant to the completion of the requirements specified in Section 7.5.6.1, above, the Common Collocation space shall be made available within ninety (90) calendar days. USWC shall use its best efforts to deliver fifty percent (50%) of all Common Collocation space orders in batches of ten (10) or more central offices within the ninety (90) day interval set forth above.

7.5.6.3 As part of the ordering process, Pilgrim will provide at a minimum a one-year forecast for each wire center in which it intends to utilize the SPOT frame. Included in this forecast will be the termination type (DS0, DS1, DS3) and the quantity of each termination required. SPOT frame terminations must be ordered in multiples of the following quantities:

- 100 DSO terminations
- 28 DS1 terminations
- 1 DS3 termination

7.5.7 Pilgrim Trunking Architecture

7.5.7.1 General Description. Pilgrim shall utilize the Custom Routing functionality of the port and combine this functionality with Dedicated Transport and unbundled tandem switching to create a local message trunk network.

- 7.5.7.2 Responsibility of Pilgrim. Pilgrim must determine local trunk capacity requirements, direct or tandem routed trunking, provide call routing instructions to the USWC, and provide quantity and forecasts of trunks per each A and Z location. The Pilgrim has complete responsibility for the design and engineering of its trunking network. All connections between the unbundled port and Dedicated Transport shall be made consistent with the SPOT rebundling requirements as set forth in this Agreement.
- 7.5.7.3 Responsibility of USWC. Upon receipt of Pilgrim routing instructions, the USWC will establish custom routing tables to direct traffic to the specific local trunk group as designated by Pilgrim. USWC will incorporate Pilgrim forecasts for trunk requirements consistent with USWC's forecasting practices.

7.6 Collocation Rate Elements

7.6.1 Common Rate Elements

The following rate elements specified in Appendix A are common to Virtual, Common, and Physical Collocation:

- 7.6.1.1 Quote Preparation Fee. This covers the work involved in verifying space and developing a quotation for Pilgrim for the total costs involved in its Collocation request.
- 7.6.1.2 Entrance Facility (EF1). Provides for fiber optic cable on a two-fiber basis from the Point of Interconnection utilizing USWC owned, conventional single mode type of fiber optic cable to the collocated equipment (for Virtual Collocation) or to the leased space (for Physical Collocation). Entrance facility includes riser, fiber placement, entrance closure, conduit/innerduct, and core drilling.
- 7.6.1.3 Cable Splicing. Represents the labor and equipment to perform a subsequent splice to the Pilgrim provided fiber optic cable after the initial installation splice. Includes per-setup and per-fiber-spliced rate elements.
- 7.6.1.4 -48 Volt Power. Provides -48 volt power to the Pilgrim collocated equipment. Charged on a per ampere basis.
- 7.6.1.5 48 Volt Power Cable. Provides for the transmission of -48 volt DC power to the collocated equipment. It includes

engineering, furnishing and installing the main distribution bay power breaker, associated power cable, cable rack and local power bay to the closest power distribution bay. It also includes the power cable (feeders) A and B from the local power distribution bay to the leased physical space (for Physical and Common Collocation) or to the collocated equipment (for Virtual Collocation).

- 7.6.1.6 Inspector Labor. Provides for the USWC qualified personnel necessary when Pilgrim requires access to the Point of Interconnection after the initial installation or access to its physical Collocation floor space, where an escort is required. A call-out of an inspector after business hours is subject to a minimum charge of four hours. The minimum call-out charge shall apply when no other employee is present in the location, and an 'off-shift' USWC employee (or contract employee) is required to go 'on-shift' on behalf of Pilgrim.
- 7.6.1.7 Interconnection Channel Regeneration. Required when the distance from the leased physical space (for Physical Collocation or Common Collocation) or from the collocated equipment (for Virtual Collocation) to the USWC network is of sufficient length to require regeneration.
- 7.6.1.8 Collocation Cross Connection. Pilgrim may cross connect its facilities at its Collocation premises with the facilities of another carrier also collocated at the same serving wire center through a USWC-provided SPOT. A SPOT charge set forth in Appendix A to connect two collocated carriers within the same serving wire center will be assessed by USWC. The cross connect is between like intermediary frames (e.g., DS0, DS1) within USWC's serving wire center. The monthly recurring charge and a nonrecurring installation charge set forth in Appendix A will apply, and both will be billed to the specific carrier requesting the cross connect.
- 7.6.1.9 Collocation Single Point of Termination (SPOT). A charge associated with the installation, change and maintenance of Pilgrim's equipment on the USWC SPOT cross-connect bay or frame within a wire center. Recurring and nonrecurring charges are assessed per two-wire pair, per Analog PLTS/DDS termination, Unbundled Network terminations, and per termination for each DS1 or DS3 requested, as set forth in Appendix A.

- 7.6.1.10 Collocation Cable Racking. A nonrecurring charge for cable racking required between Pilgrim's equipment and USWC's SPOT. Cable Racking is assessed on a per foot basis for each two-wire pair, per Analog PLTS/DDS termination, Unbundled Network terminations and per termination for each DS1 or DS3 requested.
- 7.6.1.11 Collocation Grounding. A charge associated with providing grounding for Pilgrim's cage enclosure and equipment. Recurring and nonrecurring charges are assessed per foot to Pilgrim's cage enclosure.

7.6.2 Physical/Common Collocation Rate Elements

The following rate elements, as specified in Appendix A, apply only to Physical and Common Collocation arrangements:

- 7.6.2.1 Floor Space Rental. Provides the monthly rent for the leased physical space, property taxes and base operating cost without -48 volt DC power. Includes convenience 110 AC, 15 amp electrical outlets provided in accordance with local codes and may not be used to power transmission equipment or -48 volt DC power generating equipment. Also includes maintenance for the leased space; provides for the preventative maintenance (climate controls, filters, fire and life systems and alarms, mechanical systems, standard HVAC); biweekly housekeeping services (sweeping, spot cleaning, trash removal) of the USWC wire center areas surrounding the leased physical space and general repair and maintenance.
 - 7.6.2.1.1 USWC agrees to apply flat recurring and nonrecurring charges for Common Collocation as set forth in Appendix A for the standard two (2), four (4), and six (6) bay configurations described below. These are interim charges. The Parties agree to meet and confer on or before June 30, 1999 in an effort to establish permanent flat nonrecurring and recurring charges for such standard configurations. All prior payments made by Pilgrim to USWC for common collocation in the standard configurations shall be trued up to reflect the permanent charges agreed to by the Parties. In the event the Parties cannot reach voluntary agreement on permanent charges, either Party may invoke the Dispute Resolution provision of this Agreement to establish permanent charges. Upon request by Pilgrim, USWC shall provide Pilgrim

with the relevant invoices for all charges incurred by USWC in providing Common Collocation to Pilgrim.

For Common Collocation the nonrecurring charge and recurring charges set forth in Appendix A are based on the following elements:

Pilgrim's standard bay configuration consists of two (2), four (4), or six (6) bays. Each bay is 7 feet high, 26 inches wide, 15 inches deep and requires a 2.5 inch spacer on either side of the uprights. The bay space also entails an appropriate front and back aisle space component; normally this requires a 36-inch front aisle and 24-inch back aisle. Any equipment bays built to dimension larger than these will require a new space calculation and charge since such bays cannot be accommodated in a standard transmission space footprint. The standard two (2) and four (4) bay configuration will consist of one 40 amp power cable including both A and B feeds and associated ground. The standard six (6) bay configuration will consist of two 40 amp power cables including both A and B feeds and associated ground. The nonrecurring charge for bay configuration includes all charges for any quote preparation, ironwork, cable racking, HVAC and all other space related charges, in addition to charges for customary central office lighting and AC outlets.

When Pilgrim seeks to collocate ATM equipment as described in Section 7.1.5, the Parties shall cooperate fully with each other in order for USWC to provide appropriate Collocation space to Pilgrim for the Collocation of such equipment at a mutually acceptable cost base nonrecurring charge. The recurring charges shall be the same as set forth in Appendix A on a pro rata basis for the square footage occupied by the equipment.

7.6.2.2

Enclosure Buildout. Except for Common Collocation, the Cage Enclosure Buildout element includes the material and labor to construct the enclosure. Pilgrim may choose from USWC approved contractors to construct the cage, in accordance with USWC's installation Technical Publication 77350. It includes a nine foot cage enclosure, air conditioning (to support Pilgrim loads specified), lighting

(not to exceed 2 watts per square foot), and convenience outlets (3 per cage or number required by building code). Also provides for humidification, if required. Pricing for the Enclosure Buildout will be provided on an individual basis due to the uniqueness of Pilgrim's requirements, central office structure and arrangements.

7.6.3 Virtual Collocation Rate Elements

The following rate elements, as specified in Appendix A, apply uniquely to Virtual Collocation:

- 7.6.3.1 Maintenance Labor -- Provides for the labor necessary for repair of out of service and/or service-affecting conditions and preventative maintenance of the Pilgrim virtually collocated equipment. Pilgrim is responsible for ordering maintenance spares. USWC will perform maintenance and/or repair work upon receipt of the replacement maintenance spare and/or equipment for Pilgrim. A call-out of a maintenance technician after business hours is subject to a minimum charge as specified above.
- 7.6.3.2 Training Labor -- Provides for the billing of vendor-provided training for USWC personnel on a metropolitan service area basis, necessary for Pilgrim virtually collocated equipment which is different from USWC provided equipment. USWC will require three USWC employees to be trained per metropolitan service area in which the Pilgrim virtually collocated equipment is located. If, by an act of USWC, trained employees are relocated, retired, or are no longer available, USWC will not require Pilgrim to provide training for additional USWC employees for the same virtually collocated equipment in the same metropolitan area. The amount of training billed to Pilgrim will be reduced by half, should a second collocator in the same metropolitan area select the same virtually collocated equipment as Pilgrim.
- 7.6.3.3 Equipment Bay -- Provides mounting space for the Pilgrim virtually collocated equipment. Each bay includes the 7 foot bay, its installation, all necessary environmental supports. Mounting space on the bay, including space for the fuse panel and air gaps necessary for heat dissipation is limited to 78 inches. The monthly rate is applied per shelf.

- 7.6.3.4 Engineering Labor -- Provides the planning and engineering of the Pilgrim virtually collocated equipment at the time of installation, change or removal.
- 7.6.3.5 Installation Labor -- Provides for the installation, change or removal of the Pilgrim virtually collocated equipment.

7.7 Collocation Installation Intervals:

The following intervals are common to both Virtual and Physical Collocation:

- 7.7.1 Acknowledgment of Floor Space Availability. Within fifteen days of the receipt by USWC from Pilgrim of a Request for Collocation, USWC will notify Pilgrim whether sufficient floor space is available to accommodate Pilgrim's request.
- 7.7.2 Quote Preparation. Within twenty-five business days of Pilgrim's receipt of space availability by USWC, USWC will provide Pilgrim with a written quotation containing all nonrecurring charges for the requested Collocation arrangement.
- 7.7.3 Quote Acceptance. Within thirty days of the receipt by Pilgrim of the USWC quotation, Pilgrim will accept the USWC proposed quotation. Acceptance shall require payment to USWC of fifty percent of the non-recurring charges provided on the quotation.
- 7.7.4 Completion of Enclosure Construction (Physical Collocation only). Within 90 days of the acceptance of the quotation by Pilgrim, the construction of the necessary cage enclosure shall be completed, subject to any delays caused by government agencies beyond USWC's control. At this time, the leased floor space will be available to Pilgrim for installation of its collocated equipment.
- 7.7.4 Completion of Enclosure Construction (Physical Collocation only). Within 90 days of the acceptance of the quotation by Pilgrim's, the construction of the necessary cage enclosure shall be completed, subject to any delays caused by government agencies beyond USWC's control. At this time, the leased floor space will be available to Pilgrim for installation of its collocated equipment.
- 7.7.5 Completion of Collocated Equipment Installation (Virtual Collocation only). USWC shall complete the installation of Pilgrim's collocated equipment within 90 days of USWC's receipt of Pilgrim's collocated equipment. The installation of line cards and other minor modifications shall be performed by USWC on intervals equivalent to those that USWC applies to itself, but in no instance shall any such interval exceed 90 days.

7.7.6 Microwave Collocation. USWC will make available to Pilgrim, at Pilgrim's option, the right to place wireless, antenna and dish transmission facility on the roof(s) of each building in which USWC has a local or access tandem for end office to which Pilgrim seeks to interconnect. Microwave rooftop Collocation is for the purposes of interconnection to that switch associated with that rooftop and access to unbundled network elements only. The location of said equipment will be permitted except where it is not practical for tech reasons, including city/county building zoning and electric code, Network Equipment Building System (NEBS) standards, or because of space limitations. Additionally, Pilgrim is not permitted to construct a tower on these buildings, but may lease space on any existing USWC owned and/or controlled tower. A tower specifically does not include a typical Pilgrim wireline installation. Spare microwave tower space will be accessed in terms of physical and structural loading constraints. Microwave frequency use will be limited by frequency availability to avoid Radio Frequency Interference. Compensation for radio frequency inquiry to the extent necessary and for the placement of microwave equipment and associated cabling will be on an individual case basis (ICB), unless otherwise covered by tariff, which may include without limitation cost associated with any tower or building structural modifications required to provide for the placement of microwave equipment or cabling. The price charged by USWC to Pilgrim for such Collocation shall be the same price that USWC charges other similarly situated CLECs for the same service. Pilgrim agrees to reciprocity relative to the aforementioned paragraph.

7.8 Adjacent Space Collocation:

USWC will provide adjacent space collocation in accordance with FCC Rule 51.323(k)(3). Such adjacent space collocation will only be available on USWC's premises.

8. UNBUNDLED ACCESS/ELEMENTS

8.1 General Terms

8.1.1 USWC agrees to provide the following unbundled Network Elements which are addressed in more detail in later sections of this Agreement: 1) local Loop, 2) local and tandem switches (including all vertical switching features provided by such switches), 3) interoffice transmission facilities, 4) network interface devices, 5) signaling and call-related database facilities, 6) operations support systems functions, and 7) operator and directory assistance functions.

8.1.2 This Agreement provides for the provision of unbundled Network Elements to Pilgrim which Pilgrim may connect or combine for the

purpose of offering finished retail services. USWC will not combine USWC's unbundled Network Elements to provide a finished service to Pilgrim. USWC agrees, however, to offer finished retail services to Pilgrim for resale pursuant to the Resale section of this Agreement.

- 8.1.3 USWC will not restrict the types of telecommunications services Pilgrim may offer through unbundled elements, nor will it restrict Pilgrim from combining elements with any technically compatible equipment Pilgrim owns. USWC will provide Pilgrim with the same features, functions and capabilities of a particular element that USWC provides to itself, so that Pilgrim can provide any telecommunications services that can be offered by means of the element.

8.2 Description of Unbundled Elements

8.2.1 Tandem Switching

USWC will provide a tandem switching element on an unbundled basis. The tandem switch element includes the facilities connecting the trunk distribution frames to the switch, and certain switching functions, including those facilities that establish a temporary transmission path between two other switches, but not including the transport needed to complete the call. The definition of the tandem switching element also includes the functions that are centralized in tandems rather than in separate end office switches, such as call recording, the routing of calls to operator services, and signaling conversion functions.

8.2.2 Dedicated Transport

USWC will provide to Pilgrim dedicated transmission facilities ("Dedicated Transport") as set forth herein. Dedicated Transport is defined consistent with § 51.319(d)(1)(i) of the FCC's regulations, 47 CFR and the FCC's First Report and Order, CC-Docket 96-98 dated August 8, 1996, § 51.319(d)(1)(i), as ILEC transmission facilities dedicated to a particular customer or carrier that provide telecommunications between wire centers owned by USWC or CLECs, or between switches owned by USWC or CLECs. USWC shall cooperate with adjacent ILECs to provide Dedicated Transport to Pilgrim, up to USWC boundaries, with the adjacent ILECs. For billing purposes, USWC shall provide such Dedicated Transport to the Billing Interconnection Point ("BIP") between USWC and such adjacent ILECs. Pilgrim may establish carrier POPS at its customer premises pursuant to the applicable FCC regulations. USWC shall not be required to construct new fiber optic or metallic based facilities for Pilgrim between USWC locations and Pilgrim's designated POP with respect to such POP except in the ordinary course of business.

8.2.3 Digital Cross Connect System.

USWC will provide Pilgrim with access to mutually agreed upon digital cross-connect system (DCS) points.

8.2.4 Unbundled Loops

8.2.4.1 Service Description

8.2.4.1.1 An Unbundled Loop establishes a transmission path between a central office distribution frame (or equivalent) up to, and including, USWC's network interface device (NID) and/or demarcation point. For existing Loops, the inside wire connection to the NID, and/or demarcation point, will remain intact. Pilgrim shall be responsible for performing its own inside wire and CPE provisioning functions. USWC shall deliver any USWC unbundled Loop ordered by Pilgrim to the NID or equivalent. The last provisioning Party will make the correct connection on its side of the NID.

8.2.4.1.2 Basic Unbundled Loops are available as a two-wire or four-wire, point-to-point configuration suitable for local exchange type services within the analog voice frequency range of 300 to 3000 Hz. For the two-wire configuration, Pilgrim is requested to specify Loop start or ground start option. The actual Loop facilities that provide this service may utilize various technologies or combinations of technologies. Basic Unbundled Loops provide an analog facility to Pilgrim.

USWC shall provide to Pilgrim two-wire and four-wire Loops, conditioned if necessary, such that they are capable of carrying digital signals. When Pilgrim orders a conditioned Loop USWC will, remove load coils from the Loop or Loops up to 25 pairs in the same binder group and up to 3 load coil locations and remove any bridged taps on the same Loop(s) up to 25 pairs per Loop in the same binder group if they are spare and available.

The above work operation will be considered one occurrence and will carry the agreed charge if and as expressly ordered by the Commission. Any additional work required will be billed, if

appropriate, as an additional occurrence by single load coil locations and underground splice entered.

Any rearrangement of cable pairs needed beyond 3 load coil locations to provision the service requested by Pilgrim will be charged by the hour for engineering and splicing. This and all additional work will be engineered and completed through a routine engineering work order and designed by USWC's design engineering department.

Where DLC currently exists in USWC's network, and copper facilities parallel that same route, and where facilities exist, then digital capable Loops for Pilgrim will be provisioned on the copper facility, at Pilgrim's option.

8.2.4.1.2.1 When Pilgrim requests a nonloaded Unbundled Loop and there are none available, USWC will dispatch a technician to remove load coils and excess bridge taps (i.e., "deload" and condition the Loop) in order to make a Loop available.

8.2.4.1.2.2 If Pilgrim orders multiplexing, Pilgrim will be responsible for notifying USWC of the multiplexing channel plug requirements and settings Pilgrim desires to be established. If Pilgrim wishes to establish a standard setting for all such multiplexing, the BFR process shall be used to document that request. The multiplexing channel plug requirements and settings may also be established on a case by case basis.

8.2.4.1.2.3 If Pilgrim orders multiplexing, Pilgrim will be responsible for notifying USWC of the multiplexing channel plug requirements and settings Pilgrim desires to be established. If Pilgrim wishes to establish a standard setting for all such multiplexing, the BFR process shall be used to document that request. The multiplexing channel plug requirements and settings may also be established on a case by case basis.

8.2.4.2 Unbundled Loops are provided in accordance with the specifications, interfaces and parameters described in the appropriate Technical Reference Publications. USWC's

sole obligation is to provide and maintain Unbundled Loops in accordance with such specifications, interfaces and parameters. USWC does not warrant that Unbundled Loops are compatible with any specific facilities or equipment or can be used for any particular purpose or service. Transmission characteristics may vary depending on the distance between Pilgrim's end user and USWC's end office and may vary due to characteristics inherent in the physical network. USWC, in order to properly maintain and modernize the network, may make necessary modifications and changes to the Network Elements in its network on an as needed basis. Such changes may result in minor changes to transmission parameters. Changes that affect network interoperability require advance notice pursuant to the Notice of Changes section of this Agreement.

8.2.4.3 USWC's sole obligation is to provide and maintain Unbundled Loops in accordance with such specifications, including conditioned or unconditioned status, interfaces and parameters. USWC does not warrant that Unbundled Loops are compatible with any specific facilities or equipment or can be used for any particular purpose or service. Transmission characteristics may vary depending on the distance between Pilgrim's end user and USWC's end office and may vary due to characteristics inherent in the physical network. USWC, in order to properly maintain and modernize the network, may make necessary modifications and changes to the Network Elements in its network on an as needed basis. Such changes may result in minor changes to transmission parameters. Changes that affect network interoperability require advance notice pursuant to the Notice of Changes section of this Agreement.

8.2.4.3.1 Digital Capable Loops -. Basic rate ISDN, xDSL and DS1 capable Loops. USWC shall provide Pilgrim with the appropriate NC/NCI ordering codes or information through its technical publications, purchased by Pilgrim, for each of the Digital Capable Loops listed above. These Loops should only be requested when the 2/4 wire non-loaded Loop is either not available or the non-loaded Loop does not meet the technical parameters of Pilgrim's service(s). USWC reserves the right to limit the provisioning of BRI and/or DS1 capable Loops in some areas served by Loop facilities and/or transmission equipment that are not compatible with BRI and/or DS1 service. USWC reserves the right to make some cables unavailable to Pilgrim

based on spectrum management considerations. USWC's reservation of rights set forth herein shall only be exercised on a nondiscriminatory basis, i.e. to the same extent that USWC provisions or restricts facilities for itself and others. USWC may utilize repeatered or repeater-less ISDN technology to provide the ISDN Loop to Pilgrim. End to end Loop performance is still contingent upon the underlying make-up of the existing Loop. The Parties shall cooperate fully to establish ordering processes, including ordering codes, so that Pilgrim may correctly order and USWC may efficiently provision and install the digital capable Loops. Unbundled digital Loops are transmission paths capable of carrying specifically formatted and line coded digital signals from the NI on an end user's premises to a USWC CO-NI. The cross connection of digital capable Loops from USWC frames to Pilgrim's equipment shall be provided to continue the transmission capability of such Loop pursuant to Section 7.5.1.2.1. Unbundled digital Loops may be provided using a variety of transmission technologies including but not limited to metallic wire, metallic wire based digital Loop carrier and fiber optic fed digital carrier systems. USWC will determine the specific transmission technology by which the Loop will be provided. Such technologies are used singularly or in tandem in providing service. DC continuity is not inherent in this service. The Parties acknowledge that the FCC in a pending NPRM, as well as state commissions in their own proceedings, are addressing issues pertaining to the deployment of DSL technologies by CLECs through ILEC digital Loop carrier systems. To the extent required by the FCC or the Commission, USWC shall unbundle network elements or facilities in a non-discriminatory manner.

8.2.4.4 Facilities and lines furnished by USWC on the premises of Pilgrim's end user and up to, and including, the NID or equivalent are the property of USWC. USWC must have access to all such facilities for network management purposes. USWC's employees and agents may enter said premises at any reasonable hour to test and inspect such facilities and lines in connection with such purposes or upon termination or cancellation of the Unbundled Loop Service to remove such facilities and lines.

8.2.4.5 Unbundled Loops include the facilities between the USWC distribution frame up to and including USWC's NID located at Pilgrim's end user premises. The connection between the distribution frame and Pilgrim facilities is accomplished

by ordering the applicable EICT in conjunction with Expanded Interconnection-Collocation as set forth in USWC's Private Line Tariff. Regeneration for the EICT may be required.

8.2.4.6 Unbundled Loops may not be used by Pilgrim to provide any service that would degrade or otherwise adversely affect the quality or reliability of USWC's network services (e.g., introduce harmful voltages or electrical currents in excess of standards used in common industry practice). USWC may not introduce any service that would degrade or otherwise adversely affect the quality or reliability of Pilgrim's network services (e.g., introduce harmful voltages or electrical currents in excess of standards used in common industry practice). USWC and Pilgrim further agree to cooperate in implementing any engineering guidelines that, as they are developed, will prevent the above-mentioned degradation or adverse affects to the quality or reliability of each other's network services.

8.2.4.7 Nothing in this Section shall affect the ability of any of the Parties to petition the appropriate state and/or federal regulatory bodies or industry organizations regarding the establishment of network interference and impairment standards and problem resolution procedures.

8.2.4.8 Ordering and Maintenance.

8.2.4.8.1 For the purposes of Loop assignment, tracking, and dispute resolution, USWC will require a Letter of Authorization for each existing USWC end user for which Pilgrim has requested reassignment of the Loop serving that end user.

8.2.4.8.2 If there is a conflict between an end user (and/or its respective agent) and Pilgrim regarding the disconnection or provision of Unbundled Loops, USWC will honor the latest dated Letter of Authorization designating an agent by the end user or its respective agent. If the end user's service has not been disconnected and Unbundled Loop Service is not yet established, Pilgrim will be responsible to pay the nonrecurring charge as set forth herein. If the end user's service has been disconnected and the end user's service is to be restored with USWC, Pilgrim will be responsible to pay the applicable nonrecurring charges as set

forth in USWC's applicable tariff, to restore the end user's prior service with USWC.

8.2.4.8.3 Each Party is responsible for its own end user base and will have the responsibility for resolution of any service trouble report(s) from its end users. USWC will work cooperatively with Pilgrim to resolve trouble reports when the trouble condition has been isolated and found to be within a portion of USWC's network. Pilgrim must provide to USWC test results where available when testing its end user's trouble prior to USWC performing any repair functions. The Parties will cooperate in developing mutually acceptable test report standards. When the trouble has been reported by Pilgrim and such trouble is not in USWC's network, USWC shall apply to Pilgrim the service charges in accordance with the applicable time and materials charges at state approved cost methodology.

8.2.4.8.4 Pilgrim will be responsible to submit to USWC a disconnect order for an Unbundled Loop that is relinquished by the end user due to cessation of service. Unbundled Loop facilities will be returned to USWC when the disconnect order is complete. In the event of transfer of the end user's service from one provider to another, the new provider will issue a request for transfer of service, resulting in the appropriate disconnection and reconnection of service.

8.2.4.8.5 The installation due date is a negotiated item. For related orders, new connects will be physically worked within the same calendar day.

USWC standard service intervals can be found on the U S WEST website address, "<http://tariffs.uswest.com>". At that site, select the carrier hotlink, then select the Interconnection Resource Guide and then select Service Order Intervals. USWC shall provide Pilgrim unbundled Loops and other services in accordance with such service intervals.

8.2.4.8.6 When ordering Unbundled Loops, Pilgrim is responsible for obtaining or providing facilities and equipment that are compatible with the service.

8.2.4.8.7 Pilgrim will have responsibility for testing the equipment, network facilities and the Unbundled Loop facility. If USWC performs tests of the Unbundled Loop facility at Pilgrim's request, and the fault is not in the USWC facilities, a charge shall apply.

8.2.4.8.8 Pilgrim will be responsible for providing battery and dial tone to its connection point two days prior to the due date on the service order.

8.2.4.8.9 Procedure for Basic Testing at Coordinated Time:
The following procedures shall apply to Unbundled Loops, including xDSL Loops, ordered with the option of Basic Testing at Coordinated Time:

Where technically capable and to the extent USWC can provide such extended Loop technology, it will do so. Such technology rates will be subject to Commission approval of the generic cost docket, pursuant to Section 8.2.4.1.2.1. Charges for coordinated cutovers will be in adherence with final resolution of the generic cost docket.

On each Unbundled Loop order, Pilgrim and USWC will agree on a cutover time at least 48 hours before that cutover time. The cutover time will be defined as a 30 minute window within which both the Pilgrim and USWC personnel will make telephone contact to complete the cutover.

The USWC technician will notify Pilgrim by telephone when any Loop order is completed. Additionally, the USWC technician will remain available at the site for at least ten minutes after the USWC technician has completed the order and notified Pilgrim. During this ten minute window, Pilgrim may test the circuit and recontact the USWC technician if trouble is encountered.

Within the appointed 30 minute cutover time, the Pilgrim person will call the USWC person designated to perform cross-connection work and when the USWC person is reached in that interval such work will be promptly performed. If the Pilgrim person fails to call or is not ready within the appointed interval, and if Pilgrim had not called to reschedule the work at least 2 hours prior to the

start of the interval, USWC and Pilgrim will reschedule the work order. Delays caused by the customer are the responsibility of Pilgrim.

- 8.2.4.9.9 Pilgrim and USWC will work cooperatively to develop forecasts for Unbundled Loop service. Initially Pilgrim will submit to USWC a six month forecast. USWC requests an eighteen month forecast of Unbundled Loop service. The forecast will include the specific serving Wire Center that will be requested, plus the specific quantity of each service desired. The forecast will be updated quarterly, and will be treated as Pilgrim confidential information.
- 8.2.4.9 Except as otherwise set forth in 8.2.4.1.2 concerning repeater, repeater replacement products, and incremental digital line card costs, Appendix A contains the rate information for Unbundled Loops, which shall apply to all Loops, including xDSL Loops.
- 8.2.4.10 If applicable, the Bona Fide Request Process will apply as detailed in the Bona Fide Request Process section of this Agreement.
- 8.2.4.11 If applicable, Construction Charges, pursuant to the Construction Charges section of this Agreement, may apply to the construction of new Unbundled Loops on behalf of Pilgrim. Such Construction Charges will not apply to any upgrades, expansions, enhancements, or additions undertaken by USWC in the ordinary course of its business.
- 8.2.4.12 Within 60 days of Commission approval of this Agreement, USWC will provide pricing for OCx services, subject to Pilgrim's detailed request. Pricing methodology will be consistent with the Act.
- 8.2.4.13 USWC currently utilizes NC/NCI codes for ISDN which Pilgrim may use when ordering digital capable Loops for its services. When USWC implements NC/NCI codes for its xDSL services, USWC shall make such codes available to Pilgrim for Pilgrim's ordering of xDSL Loops.
- 8.2.4.14 During or before, 3rd Quarter, 1998, USWC will implement performance measurements for digitally capable Loops. The performance measurements that will be available

starting in the 3d Quarter, 1998, pursuant to this Section, are specified in Section 24.

8.2.5 Local Switching Element

The unbundled switching element includes facilities that are associated with the switch (e.g., Port), facilities that are involved with switching the call, access to vertical features (e.g., custom calling), and all originating minutes of use from the unbundled switching element, but not including transport from or to the switch.

8.2.5.1 End Office Switching

8.2.5.1.1 Line-side and trunk-side Ports are available. The line-side Port is flat rated and it includes:

- 8.2.5.1.1.1 Telephone Number
- 8.2.5.1.1.2 Directory Listing
- 8.2.5.1.1.3 Dial Tone
- 8.2.5.1.1.4 Signaling (Loop or ground start)
- 8.2.5.1.1.5 On/Off Hook Detection
- 8.2.5.1.1.6 Audible and Power Ringing
- 8.2.5.1.1.7 Automatic Message Accounting (AMA) Recording
- 8.2.5.1.1.8 Access to 911, Operator Services, and Directory Assistance
- 8.2.5.1.1.9 Blocking Options (900 services)

8.2.5.1.2 Vertical features will be offered as elements. These elements are offered at the retail rate with the appropriate discounted rate offered under resale.

8.2.5.1.3 Local originating usage will be measured and billed on minutes of use.

8.2.5.1.4 The access point for line-side Port interconnection is the Single Point of Termination (SPOT) bay of the USWC designated serving Wire Center.

8.2.5.1.5 The price for local switching is described in Appendix A.

8.2.5.2 Customized Routing

8.2.5.2.1 Description

Customized routing will enable Pilgrim to direct particular classes of calls to prearranged outgoing trunks. Pilgrim can use customized routing to direct its end users' calls to 411, 555-1212, or O- to its own directory assistance, operator services platform or dedicated trunks.

8.2.5.2.2 Limitations

Because there is a limitation in the capacity of the 1A ESS switch, custom routing will be offered to Pilgrim on a first-come, first-served basis.

8.2.5.2.3 The price for custom routing will be provided on a case-by-case basis. The price for custom routing is comprised of a development charge for a customized Line Class Code and an installation charge for every switch the Line Class Code is implemented.

8.2.5.3 Coin signaling is only available as part of "smart PAL" service.

8.2.6 Network Interface Device (NID)

8.2.6.1 Service Description.

A device wired between a telephone protector and the inside wiring to isolate the end user's equipment from the network at the subscriber's premises. It is a device for the termination of inside wire that is available in single and multiple pair configurations.

8.2.6.2 Pilgrim may connect its Loops, via its own NID, to the USWC NID.

8.2.6.3 Any costs associated with USWC's connection of Pilgrim's NID to USWC's NID, will be the responsibility of Pilgrim.

8.2.6.4 The price for access to the NID will be provided on a case-by-case basis.

8.2.7 Additional Unbundled Elements

Pilgrim may request nondiscriminatory access to, and where appropriate, development of additional unbundled Network Elements not covered in this Agreement in response to specific requests therefor, pursuant to the Bona Fide Request Process detailed in the Bona Fide Request Process section of this Agreement.

9. ANCILLARY SERVICES AND ARRANGEMENTS

9.1 Signaling Access to Call-Related Databases

9.1.1 When Pilgrim is purchasing local switching from USWC, USWC will provide access via the STP to call related databases used in AIN services. The Parties agree to work in the industry to define the mediated access mechanisms for SCP access. Access to the USWC Service Management Systems (SMS) will be provided to Pilgrim, via the BFR process, to activate, modify, or update information in the call related databases, equivalent to the USWC access.

9.1.2 USWC will offer unbundled signaling via LIS-Common Channel Signaling Capability (CCSAC). CCSAC service utilizes the SS7 network and provides access to call-related databases that reside at USWC's SCPs, such as the Line Information Database (LIDB) and the 800 Database. The access to USWC's SCPs will be mediated via the STP Port in order to assure network reliability.

9.1.3 CCSAC includes:

9.1.3.1 Entrance Facility - This element connects Pilgrim's signaling point of interface with the USWC serving wire center (SWC). Pilgrim may purchase this element or it may self-provision the entrance facility. If the entrance facility is self-provisioned, Pilgrim would need to purchase Collocation and an Expanded Interconnection Channel Termination.

9.1.3.2 Direct Link Transport (DLT) - This element connects the SWC to the USWC STP. Pilgrim may purchase this element or self-provision transport directly to the STP. If Pilgrim provides the link to the STP, it must purchase Collocation, an Expanded Interconnection Channel Termination at the STP location, and a direct link from the EICT to the STP Port.

- 9.1.3.3 STP Port - This element provides the switching function at the STP. One STP Port is required for each DLT Link. The Port provides interaction with the Service Control Point (SCP). Port availability is limited.
- 9.1.3.4 Multiplexing - Multiplexing may be required at either/both the SWC and/or Port. The multiplexing options are the standard DS3 to DS1 and DS1 to DS0 requirements.
- 9.1.4 Access to Advanced Intelligent Network (AIN) functions is available only through the STP.
- 9.1.5 USWC will provide mediated access to SMS via the BFR process, for the purpose of activating, modifying or updating AIN service specification through its Service Creation Environment (SCE) on an equivalent basis as USWC provides to itself. SMS allows Pilgrim to provision, modify, or update information in call related databases. Currently, the SCE process is predominantly manual via a service center.
- 9.1.6 The pricing for CCSAC service is provided in Appendix A.

9.2 Interim Number Portability

9.2.1 General Terms

- 9.2.1.1 The Parties shall provide Number Portability on a reciprocal basis to each other to the extent technically feasible, and in accordance with rules and regulations as from time to time prescribed by the FCC and/or the Commission.
- 9.2.1.2 Until Permanent Number Portability is implemented by the industry pursuant to regulations issued by the FCC or the Commission, the Parties agree to provide Interim Number Portability ("INP") to each other through remote call forwarding, direct inward dialing and NXX migration.
- 9.2.1.3 Once Permanent Number Portability is implemented pursuant to FCC or Commission regulation, either Party may withdraw, at any time and at its sole discretion, its INP offerings, subject to advance notice to the other Party and coordination to allow the seamless and transparent conversion of INP end user numbers to Permanent Number Portability. Upon implementation of Permanent Number Portability pursuant to FCC regulations, both Parties agree to conform and provide such Permanent Number Portability.

- 9.2.1.4 USWC will update its Line Information Database ("LIDB") listings for retained numbers as directed by Pilgrim. USWC will restrict or cancel calling cards associated with these forwarded numbers. LIDB updates shall be completed by the Parties on the same business day each INP arrangement is activated.
- 9.2.1.5 Upon request, USWC shall provide to Pilgrim INP via Direct Inward Dial Trunks pursuant to applicable tariffs.
- 9.2.1.6 Where either Party has activated an entire NXX for a single end user, or activated a substantial portion of an NXX for a single end user with the remaining numbers in that NXX either reserved for future use or otherwise unused, if such end user chooses to receive service from the other Party, the first Party shall cooperate with the second Party to have the entire NXX reassigned in the LERG (and associated industry databases, routing tables, etc.) to an end office operated by the second Party. Such transfer will be accomplished with appropriate coordination between the Parties and subject to appropriate industry lead-times for movement of NXXs from one switch to another. Other applications of NXX migration will be discussed by the Parties as circumstances arise.

9.2.2 Description Of Service

- 9.2.2.1 Interim Number Portability ("INP") Service is a service arrangement that can be provided by USWC to Pilgrim or by Pilgrim to USWC. For the purposes of this section, the Party porting traffic to the other Party shall be referred to as the "INP Provider" and the Party receiving INP traffic for termination shall be referred to as the "INP Requestor".
- 9.2.2.2 INP applies to those situations where an end user elects to transfer service from the INP Provider to the INP Requestor and such end user also wishes to retain its existing telephone number. INP consists of INP Provider's provision to the INP Requestor the capability to route calls placed to telephone numbers assigned to the INP Provider's switches to the INP Requestor's switches. INP is available only for working telephone numbers assigned to the INP Provider's end users who request to transfer to the INP Requestor's service.
- 9.2.2.3 INP is available as INP-Remote Call Forwarding ("INP-RCF") permitting a call to an INP Provider's assigned

telephone number to be translated to the INP Requestor's dialable local number. INP Requestor may terminate the call as desired. Additional capacity for simultaneous call forwarding is available where technically feasible. The INP Requestor will need to specify the number of simultaneous calls to be forwarded for each number ported.

9.2.2.4 INP is subject to the following restrictions:

9.2.2.4.1 An INP telephone number may be assigned by INP Requestor only to the Requestor's end users located within the INP Provider's local calling area and toll rating area that is associated with the NXX of the portable number.

9.2.2.4.2 INP is applicable only if the INP Requestor is engaged in a reciprocal traffic exchange arrangement with the INP Provider.

9.2.2.4.3 Only the existing, INP Provider assigned end user telephone number may be used as a ported number for INP.

9.2.2.4.4 INP will not be provided by the INP Provider for end users whose accounts are in arrears and who elect to make a change of service provider unless and until the following conditions are met:

9.2.2.4.4.1 Full payment for the account (including directory advertising charges associated with the end user's telephone number) is made by end user or INP Requestor agrees to make full payment on behalf of end user.

9.2.2.4.4.2 INP Provider is notified in advance of the change in service provider and a Change of Responsibility form is issued.

9.2.2.4.4.3 INP Provider accepts the transfer of responsibility.

9.2.2.4.5 INP services shall not be re-sold, shared or assigned by either Party to another LEC or CLEC.

9.2.2.4.6 INP is not offered for NXX Codes 555, 976, 960 and coin telephones, and Service Access Codes (i.e. 500, 700, 800/888, 900). INP is not available for FGA seven-digit numbers, including foreign

exchange (FEX), FX and FX/ONAL and foreign Central Office Service. Furthermore, INP numbers may not be used for mass calling events.

9.2.2.4.7 The ported telephone number will be returned to the originating Party (or to the common pool of telephone numbers upon implementation of Permanent Number Portability) when the ported service is disconnected. The Party purchasing a ported number may not retain it and reassign it to another end user. The normal intercept announcement will be provided by the INP Provider for the period of time until the telephone number is reassigned by the INP Provider.

9.2.2.5 Ordering and Maintenance

9.2.2.5.1 The INP Requestor is responsible for all dealings with and on behalf of its end users, including all end user account activity, e.g. end user queries and complaints.

9.2.2.5.2 Each Party is responsible for obtaining a Letter of Authorization (LOA) from its end users who request a transfer of the end user's telephone number from the other Party.

9.2.2.5.3 The INP Provider will work cooperatively with the INP Requestor to ensure a smooth end user transition and to avoid unnecessary duplication of other facilities (e.g., Unbundled Loops). The Parties will cooperate to develop intercompany procedures to implement the requirements of this paragraph.

9.2.2.5.4 If an end user requests transfer of service from the INP Requestor back to the INP Provider, the INP Provider may rely on that end user request to institute cancellation of the INP service. The INP Provider will provide at least 48 hours notice to the INP Requestor of the cancellation of INP service, and will work cooperatively with the INP Requestor to ensure a smooth end user transition and to avoid unnecessary duplication of other facilities (e.g., Unbundled Loops). The Parties will cooperate to develop intercompany procedures to implement the requirements of this paragraph.

- 9.2.2.5.5 Certain features are not available on calls passed through INP service.
- 9.2.2.5.6 The INP Requestor's designated INP switch must return answer and disconnect supervision to the INP Provider's switch.
- 9.2.2.5.7 The INP Requestor will provide to the E911 database provider the network telephone number that the INP Requestor assigned to the INP Provider-assigned, ported telephone number. Updates to and maintenance of the INP information to the E911 database are the responsibility of the INP Requestor.
- 9.2.2.5.8 The INP Requestor will submit to the INP Provider a disconnect order for each ported number that is relinquished by the INP Requestor's end users.

9.2.2.6 Cost Recovery

The Parties agree that, for the purposes of this Agreement that the following cost structure is an acceptable measure of the costs incurred by the INP Provider.

- 9.2.2.6.1 Number Ported -- This cost is incurred per number ported, per month. Should the INP Requestor provide the transport from the INP Provider's end office to the INP Requestor's end office switch, a lower cost is incurred. This cost represents a single call path from the INP Provider's end office switch to the INP Requestor for the portable number.
- 9.2.2.6.2 Additional Call Path -- This cost is incurred per additional call path per month added to a particular ported telephone number. Should the INP Requestor provide the transport from the INP Provider's end office to the INP Requestor's end office switch, a lower cost is incurred.
- 9.2.2.6.3 Service Establishment – Per Route, Per Switch. This non-recurring cost is incurred for each INP Provider's end office switch that is equipped to provide INP to the INP Requestor.
- 9.2.2.6.4 Service Establishment – Additional number ported or changes to existing numbers, per number ported

-- This non-recurring cost is for each telephone number equipped with INP.

9.2.2.6.5 The Parties agree that Appendix A reasonably identifies the above costs.

9.2.2.6.6 Each of the above costs shall be borne by the INP Requestor.

9.2.2.6.7 The INP Provider will, when using RCF, send the original ("ported") number over the Interconnection arrangements as the Calling Party Number using the signaling protocol applicable to the arrangements. The INP Requestor will capture and measure the number of minutes of INP incoming traffic. USWC will provide (and update quarterly) percentage distributions of all terminating traffic in the LATA by jurisdictional nature of the traffic: a) local; b) intrastate, intraLATA switched access; c) intrastate, interLATA switched access; d) interstate, intraLATA switched access; e) interstate, interLATA switched access. Separate residence and business percentage distributions will be provided, to the extent possible. The Parties agree to work cooperatively to develop and exchange the data required to implement this paragraph. The appropriate percentage will be applied to the number of minutes of INP traffic in each category to determine the number of minutes eligible for additional "pass through" switched access compensation. Pass through switched access compensation will be paid at the following rates:

For all Intra-LATA Toll and inter-LATA minutes delivered over INP, USWC will pay, in addition to reciprocal compensation, the applicable CCLC for each minute.

9.2.2.6.8 Rates are contained in Appendix A.

9.3 911/E-911 Service

9.3.1 Scope.

9.3.1.1 Pilgrim exchanges to be included in USWC's E-911 Data Base will be indicated via written notice and will not require an amendment to this Agreement.

- 9.3.1.2 In counties where USWC has obligations under existing agreements as the primary provider of the 911 System to the county, Pilgrim will participate in the provision of the 911 System as described in this Agreement.
- 9.3.1.2.1 Each Party will be responsible for those portions of the 911 System for which it has total control, including any necessary maintenance to each Party's portion of the 911 System.
- 9.3.1.2.2 USWC, or its agent, will be responsible for maintaining the E-911 Data Base. USWC, or its agent, will provide to Pilgrim an initial copy of the most recent Master Street Address Guide ("MSAG"), and subsequent versions on a quarterly basis, at no charge. MSAGs provided outside the quarterly schedule will be provided and charged on an individual case basis. The data will be provided in computer readable format.
- 9.3.1.2.3 For selective routing table updates, Pilgrim will negotiate directly with USWC's data base provider for the input of end user data into the USWC Automatic Location Identification ("ALI") data base. Pilgrim will negotiate directly with the Public Safety Answering Point ("PSAP")'s (or PSAP agency's) DMS/ALI provider for input of end user data into the ALI data base. In most cases the selective routing table updates and the ALI data base will be managed by the same provider. Pilgrim assumes all responsibility for the accuracy of the data that Pilgrim provides for MSAG preparation and E-911 Data Base operation.
- 9.3.1.2.4 Pilgrim will provide end user data to USWC's agent for the USWC ALI data base utilizing NENA-02-001 Recommended Formats For Data Exchange, NENA-02-002 Recommended Standard For Street Thoroughfare Abbreviations and NENA-02-003 Recommended Protocols For Data Exchange. USWC will furnish Pilgrim any variations to NENA recommendations required for ALI data base input.
- 9.3.1.2.5 Pilgrim will provide end user data to USWC's agent for the USWC ALI data base that are MSAG valid and meet all components of the NENA-02-004 Recommended Measurements For Data Quality.

- 9.3.1.2.6 Pilgrim will update its end user records provided to USWC's agent for the USWC ALI data base to agree with the 911 MSAG standards for its service areas.
- 9.3.1.2.7 USWC will provide Pilgrim with the identification of the USWC 911 controlling office that serves each geographic area served by Pilgrim.
- 9.3.1.2.8 The Parties will cooperate in the routing of 911 traffic in those instances where the ALI/ANI information is not available on a particular 911 call.
- 9.3.1.2.9 USWC will provide Pilgrim with the ten-digit telephone numbers of each PSAP agency, for which USWC provides the 911 function, to be used by Pilgrim to acquire emergency telephone numbers for operators to handle emergency calls in those instances where the Pilgrim end user dials "O" instead of "911".
- 9.3.1.2.10 Pilgrim will provide USWC with the ten-digit telephone numbers of each PSAP agency, for which Pilgrim provides the 911 function, to be used by USWC to acquire emergency telephone numbers for operators to handle emergency calls in those instances where the USWC end user dials "O" instead of "911".
- 9.3.1.3 If a third party; i.e., LEC, is the primary service provider to a county, Pilgrim will negotiate separately with such third party with regard to the provision of 911 service to the county. All relations between such third party and Pilgrim are totally separate from this Agreement and USWC makes no representations on behalf of the third party.
- 9.3.1.4 If Pilgrim is the primary service provider to the county, Pilgrim and USWC will negotiate the specific provisions necessary for providing 911 service to the county and will include such provisions in an amendment to this Agreement.
- 9.3.1.5 Pilgrim will separately negotiate with each county regarding the collection and reimbursement to the county of applicable end user taxes for 911 service.

- 9.3.1.6 Pilgrim is responsible for network management of its network components in compliance with the Network Reliability Council Recommendations and meeting the network standard of USWC for the 911 call delivery.
 - 9.3.1.7 The Parties shall provide a single point of contact to coordinate all activities under this Agreement.
 - 9.3.1.8 Neither Party will reimburse the other for any expenses incurred in the provision of E-911 services up to P.01 grade of service.
- 9.3.2 Performance Criteria. E-911 Data Base accuracy shall be as set forth below:
- 9.3.2.1 Accuracy of ALI data will be measured jointly by the PSAPs and USWC in a format supplied by USWC. The reports shall be forwarded to Pilgrim by USWC when relevant and will indicate incidents when incorrect or no ALI data is displayed.
 - 9.3.2.2 Each discrepancy report will be jointly researched by USWC and Pilgrim. Corrective action will be taken immediately by the responsible Party.
 - 9.3.2.3 Each Party will be responsible for the accuracy of its end user records. Each Party specifically agrees to indemnify and hold harmless the other Party from any claims, damages, or suits related to the accuracy of end user data provided for inclusion in the E-911 Data Base.
 - 9.3.2.4 For PSAP default routing purposes, Pilgrim will establish separate trunks for the USWC selective router for each PSAP jurisdictional area it serves from a given switch.
 - 9.3.2.5 The additional parameters by which the Parties will utilize the 911 or E-911 database will be the subject of further discussion between the Parties.

9.4 Directory Assistance

- 9.4.1 USWC agrees to (1) provide to Pilgrim's operators on-line access to USWC's directory assistance database; (2) provide to Pilgrim unbranded directory assistance service (3) provide to Pilgrim directory assistance service under the Pilgrim brand (where technically feasible); (4) allow Pilgrim or Pilgrim's designated operator bureau to license USWC's directory assistance database for use in providing competitive directory

assistance services. Prices for all of these services will be determined on an individual case basis.

- 9.4.2 The price for directory assistance, provided pursuant to this Agreement, is specified in Appendix A. As an alternative, the Parties may obtain directory assistance service pursuant to retail directory assistance tariffs.
- 9.4.3 The price for directory call completion services is specified in Appendix A, pending the completion of an approved cost study. Additional charges, for USWC IntraLATA Toll services, also apply for completed IntraLATA Toll calls. IntraLATA Toll service shall be available pursuant to the wholesale discount provided in the Resale section of this Agreement. Call completion service is an optional service. Pilgrim may, at its option, request USWC to not provide call completion services to Pilgrim end users.

9.5 White Pages Directory Listings

9.5.1 Scope.

- 9.5.1.1 White Pages Listings Service ("Listings") consists of USWC placing the names, addresses and telephone numbers of Pilgrim's end users in USWC's listing database, based on end user information provided to USWC by Pilgrim. USWC is authorized to use Listings in Directory Assistance (DA) and as noted in paragraph 9.5.1.4, below.
- 9.5.1.2 Pilgrim will provide in standard, mechanized format, and USWC will accept at no charge, one primary listing for each main telephone number belonging to Pilgrim's end users. Primary listings are as defined for USWC end users in USWC's general exchange tariffs. Pilgrim will be charged for premium and privacy listings, e.g., additional, foreign, cross reference, informational, etc., at USWC's general exchange listing tariff rates, less the wholesale discount. If Pilgrim utilizes Remote Call Forwarding for local number portability, Pilgrim can list only one number without charge - either the end user's original telephone number or the Pilgrim-assigned number. The standard discounted rate for an additional listing applies to the other number.
- 9.5.1.3 USWC will furnish Pilgrim the Listings format specifications. Pilgrim may supply a maximum of one batch file daily, containing only Listings that completed on or prior to the transmission date. USWC cannot accept

Listings with advance completion dates. Large volume activity (e.g., 100 or more listings) on a caption set is considered a project that requires coordination between Pilgrim and USWC to determine time frames.

9.5.1.4 Pilgrim grants USWC a non-exclusive license to incorporate Listings information into its directory assistance database. Pilgrim hereby selects one of two options for USWC's use of Listings and dissemination of Listings to third parties.

EITHER:

9.5.1.4.1 Treat the same as USWC's end user listings - No prior authorization is needed for USWC to release Listings to directory publishers or other third parties. USWC will incorporate Listings information in all existing and future directory assistance applications developed by USWC. Pilgrim authorizes USWC to sell and otherwise make Listings available to directory publishers. USWC shall be entitled to retain all revenue associated with any such sales. Listings shall not be provided or sold in such a manner as to segregate end users by carrier.

OR:

9.5.1.4.2 Restrict to USWC's directory assistance -- Prior authorization required by Pilgrim for all other uses. Pilgrim makes its own, separate agreements with USWC, third parties and directory publishers for all uses of its Listings beyond directory assistance. USWC will sell Listings to directory publishers (including USWC's publisher affiliate), other third parties and USWC products only after the third party presents proof of Pilgrim's authorization. USWC shall be entitled to retain all revenue associated with any such sales. Listings shall not be provided or sold in such a manner as to segregate end users by carrier.

Pilgrim hereby selects Option : N/A.

9.5.1.5 To the extent that state tariffs limit USWC's liability with regard to Listings, the applicable state tariff(s) is incorporated herein and supersedes the Limitation of

Liability section of this Agreement with respect to Listings only.

9.5.2 USWC Responsibilities

- 9.5.2.1 USWC is responsible for maintaining Listings, including entering, changing, correcting, rearranging and removing Listings in accordance with Pilgrim orders. USWC will take reasonable steps in accordance with industry practices to accommodate non-published and non-listed Listings provided that Pilgrim has supplied USWC the necessary privacy indicators on such Listings.
- 9.5.2.2 USWC will include Pilgrim Listings in USWC's Directory Assistance service to ensure that callers to USWC's Directory Assistance service have non-discriminatory access to Pilgrim's Listings.
- 9.5.2.3 USWC will ensure the Pilgrim Listings provided to USWC are included in the white pages directory published on USWC's behalf, in accordance with Pilgrim's selection under Section 9.5.1.4, above.

9.5.3 Pilgrim Responsibilities

- 9.5.3.1 Pilgrim agrees to provide to USWC its end user names, addresses and telephone numbers in a standard mechanized format, as specified by USWC.
- 9.5.3.2 Pilgrim will supply its ACNA/CIC or CLCC/OCN, as appropriate, with each order to provide USWC the means of identifying Listings ownership.
- 9.5.3.3 Pilgrim represents and warrants the end user information provided to USWC is accurate and correct. Pilgrim further represents and warrants that it has reviewed all Listings provided to USWC, including end user requested restrictions on use such as non-published and non-listed. Pilgrim shall be solely responsible for knowing and adhering to state laws or rulings regarding Listings (e.g., no solicitation requirements in the states of Arizona and Oregon, privacy requirements in Colorado), and for supplying USWC with the applicable Listing information.
- 9.5.3.4 Pilgrim is responsible for all dealings with, and on behalf of, Pilgrim's end users, including:

- 9.5.3.4.1 All end user account activity, e.g. end user queries and complaints.
- 9.5.3.4.2 All account maintenance activity, e.g., additions, changes, issuance of orders for Listings to USWC.
- 9.5.3.4.3 Determining privacy requirements and accurately coding the privacy indicators for Pilgrim's end user information. If end user information provided by Pilgrim to USWC does not contain a privacy indicator, no privacy restrictions will apply.
- 9.5.3.4.4 Any additional services requested by Pilgrim's end users.

9.6 Busy Line Verify and Busy Line Interrupt Services

- 9.6.1 Busy Line Verification ("BLV") is performed when one Party's end user requests assistance from the operator bureau to determine if the called line is in use, however, the operator bureau will not complete the call for the end user initiating the BLV inquiry. Only one BLV attempt will be made per end user operator bureau call, and a charge shall apply whether or not the called party releases the line.
- 9.6.2 Busy Line Verification Interrupt ("BLVI") is performed when one Party's operator bureau interrupts a telephone call in progress after BLV has occurred. The operator bureau will interrupt the busy line and inform the called party that there is a call waiting. The operator bureau will only interrupt the call and will not complete the telephone call of the end user initiating the BLVI request. The operator bureau will make only one BLVI attempt per end user operator telephone call and the applicable charge applies whether or not the called party releases the line.
- 9.6.3 The rates for Busy Line Verify and Busy Line Verify and Interrupt are specified in Appendix A.
- 9.6.4 Each Party's operator bureau shall accept BLV and BLVI inquiries from the operator bureau of the other Party in order to allow transparent provision of BLV/BLVI traffic between the Parties' networks.
- 9.6.5 Each Party shall route BLV/BLVI traffic inquiries over separate direct trunks (and not the local/intraLATA trunks) established between the Parties' respective operator bureaus. Unless otherwise mutually agreed, the Parties shall configure BLV/BLVI trunks over the Interconnection architecture defined in the Interconnection section of this Agreement. Each Party shall compensate the other Party for BLV/BLVI traffic as set forth above.

9.7 Toll and Assistance Operator Services

9.7.1 Description of Service.

Toll and Assistance refers to functions end users associate with the "O" operator. Subject to availability and capacity, access may be provided via operator services trunks purchased from USWC or provided by Pilgrim via Collocation arrangements to route calls to Pilgrim's platform.

9.7.2 Functions include:

9.7.2.1 O-Coin, Automatic Coin Telephone Service (ACTS) - these functions complete coin calls, collect coins and provide coin rates.

9.7.2.2 Alternate Billing Services (ABS or O+ dialing): Bill to third party, Collect and Mechanized Credit Card System (MCCS).

9.7.2.3 O- or operator assistance which provides general assistance such as dialing instruction and assistance, rate quotes, emergency call completion and providing credit.

9.7.2.4 Automated Branding - ability to announce the carrier's name to the end user during the introduction of the call.

9.7.2.5 Rating Services - operators have access to tables that are populated with all toll rates used by the operator switch.

9.7.3 Pricing for Toll and Assistance Operator Services shall be determined on a case-by-case basis, upon request.

9.7.4 Interconnection to the USWC Toll and Assistance Operator Services from an end office to USWC T/A is technically feasible at three distinct points on the trunk side of the switch. The first connection point is an operator services trunk connected directly to the T/A host switch. The second connection point is an operator services trunk connected directly to a remote T/A switch. The third connection point is an operator services trunk connected to a remote access tandem with operator concentration capabilities.

9.7.5 Trunk provisioning and facility ownership will follow the guidelines recommended by the Trunking and Routing, IOF and Switch sub-teams. All trunk interconnections will be digital.

- 9.7.6 Toll and Assistance interconnection will require an operator services type trunk between the end office and the interconnection point on the USWC switch.
- 9.7.7 Connecting a position to the host system requires two circuits (one voice and one data) per position on a T1 facility.
- 9.7.8 The technical requirements of operator services type trunks and the circuits to connect the positions to the host are covered in the OSSGR under Section 6 (Signaling) and Section 10 (System Interfaces) in general requirements form.
- 9.7.9 Specific provisions regarding Operator Services will be addressed in a separate agreement between the Parties.

9.8 Interconnection to Line Information Data Base (LIDB)

9.8.1 Description of Line Information Data Base (LIDB).

Line Information Data Base (LIDB) stores various line numbers and Special Billing Number (SBN) data used by operator services systems to process and bill calls. The operator services system accesses LIDB data to provide origination line (calling number), billing number and termination line (called number) management functions. LIDB is used for calling card validation, fraud verification, preferred IC association with the calling card, billing or service restrictions and the sub-account information to be included on the call's billing record.

9.8.2 Interfaces.

Bellcore's GR-446-CORE defines the interface between the administration system and LIDB including specific message formats. (Bellcore's TR-NWP-000029, Section 10)

9.8.3 LIDB Access.

9.8.3.1 All LIDB queries and responses from operator services systems and end offices are transmitted over a CCS network using a Signaling System 7 (SS7) protocol (TR-NWT-000246, Bell Communications Research Specification of Signaling System 7).

9.8.3.2 The application data needed for processing LIDB data are formatted as TCAP messages. TCAP messages may be carried as an application level protocol using SS7 protocols for basic message transport.

9.8.3.3 The SCP node provides all protocol and interface support. Pilgrim SS7 connections will be required to meet Bellcore's GR905, TR954 and USWC's Technical Publication 77342 specifications.

9.8.3.4 Non-USWC companies will submit LIDB updates via a manual fax process being developed. An electronic capability is being designed to allow Pilgrim to add, update, and delete their line records.

9.8.3.5 It is currently USWC's policy to allow LIDB access to non-USWC companies through regional STPs.

9.8.4 Pricing for LIDB access shall be determined on a case-by-case basis and will be included in a separate LIDB agreement between the Parties.

9.9 Access to Poles, Ducts, Conduits, and Rights of Way

Each Party shall provide the other Party access to its poles, ducts, rights-of-way and conduits it controls on terms, conditions and prices comparable to those offered to any other competitive local exchange carrier pursuant to each Party's applicable tariffs and/or standard agreements. The Parties agree that the prices are based on costs plus a reasonable profit.

9.10 Miscellaneous Ancillary Services.

Miscellaneous ancillary services will be addressed in separate agreements between the Parties. These include, but are not limited to 800 and CMDS.

10. ACCESS TO OPERATIONAL SUPPORT SYSTEMS (OSS)

This section sets forth the interface requirements for pre-ordering, ordering and provisioning, maintenance and repair, and billing, where Pilgrim provides service to its customers through resale of Local Services or through the use of Unbundled Network Elements. For all Local Services, Network Elements ordered under this Agreement, USWC will provide Pilgrim pre-ordering, ordering and provisioning, maintenance and repair, and billing services within the same level of quality of service available to USWC. Systems capabilities will be implemented according to a mutually agreed upon and documented schedule.

Use of Standards. As described below, Pilgrim and USWC agree to implement each interface described below based upon existing and evolving industry standards or as mutually agreed upon. The Parties shall transition the electronic interfaces to industry standards within a time-frame mutually agreed to.

USWC is developing a proposal for access to its Operational Support Systems (OSS) to meet the requirements of the FCC's 1st and 2nd Orders and to provide Pilgrim with electronic interfaces for pre-ordering, ordering, demand repairs and billing functions for Plain Old Telephone Services (POTS). These interfaces will also have the necessary mediation to protect the integrity of the network as well as allay any privacy concerns for end user information. The components described in this section are conceptual in nature and will be subject to change as the implementation process proceeds. There will be charges associated with the introduction of the interface and ongoing access to OSS operations which will include an initial access fee and an ongoing charge as described more fully below.

10.1 Operational Systems Interfaces - Interface Implementation Timetable

USWC's initial operational systems interfaces have been deployed and will support Pre-ordering, Ordering, Provisioning and Repair capabilities for POTS (non-design) services and Billing capabilities for most USWC product offerings. Subsequent phases of the plan incorporate the capabilities to support designed services for Pre-ordering, Ordering, Provisioning, and Maintenance and Repair. The specific features and functions are not discussed in this Agreement.

10.2 OSS Interface Design

- 10.2.1 USWC will develop OSS interfaces using an electronic gateway solution consistent with the design prescribed by the FCC, Docket 96-98, FCC 96-325, paragraph 527. These gateways will act as a mediation or control point between Pilgrim's and USWC's Operations Systems. Additionally, these gateways will provide security for the interface, protecting the integrity of the USWC network and its databases.
- 10.2.2 USWC proposes the use of the existing Electronic Data Interchange ("EDI") standard for the transmission of monthly local billing information. EDI is an established standard under the auspices of the American National Standards Institute/Accredited Standards Committee (ANSI/ASC) X12 Committee. A proper subset of this specification has been adopted by the Telecommunications Industry Forum (TCIF) as the "811 Guidelines" specifically for the purposes of telecommunications billing.
- 10.2.3 For the exchange of daily usage data, including third party billed, collect, and card calls, USWC will use the Bellcore EMR format for the records, using the Network Data Mover ("NDM"), otherwise

Note:

10.3.1.1.1 No detailed facility information (i.e., cable pair) will be returned as part of this transaction.

10.3.1.1.2 Rural addresses will not be supported.

10.3.1.1.3 The AVQ/AVR transaction attributes currently don't reflect the attributes required to support the error scenarios.

10.3.1.2 Service Availability

This transaction will return the list of products and services available for resale in the central office serving a particular end user address. The USWC rates for the products and services will also be returned, but the Pilgrim discount will not be applied.

10.3.1.3 End User Service Information Request

Gives Pilgrim the ability to request a listing of services and features USWC is currently providing to an end user and the rates USWC is charging for such services.

10.3.1.4 View/Update Service Query/Service Request Response

Gives Pilgrim the ability to view or update an existing Service Request (SR).

10.3.1.5 Store Service Request

This transaction allows Pilgrim to store a new or existing SR.

This SR can be stored for the number of days specified in USWC's methods and procedures before the SR must be submitted to USWC as a Work Order.

USWC will store the SR on-line until the associated Work Order is canceled by Pilgrim or completed by USWC.

10.3.2 Ordering

With the pre-ordering steps completed, the requisite information will have been obtained from Pilgrim and the initiation of a service order can begin. Submitting a service order will result in the

provisioning and installation, if necessary, of an end user's service. The functional set required to order service is: open a service order, check facility availability, reserve an appointment if technician work is required in the field or at the end user's premises, reserve a telephone number if appropriate, cancel a service order, change a service order, send a firm order confirmation, support for work order status queries, and send notification of order completion.

10.3.2.1 Facility Availability

For each new line requested, this transaction will indicate if existing facilities are available or if new facilities are required, and if a technician must be dispatched to provide the facilities requested at the end user's address.

This transaction must be executed for any new line(s) requested.

Note:

10.3.2.1.1 This transaction does not reserve facilities and does not guarantee that facilities will be available when the work order is submitted. There shall be no charges to Pilgrim whatsoever in the event that a Pilgrim order remains unfulfilled. USWC shall fulfill orders for Pilgrim in parity with orders it fulfills for itself. If USWC has facilities which it utilizes to provide its own customers POTS or other services, it shall similarly make available those facilities to provide xDSL Loops for Pilgrim providing they are available.

10.3.2.1.2 USWC will automatically execute this transaction as part of order processing, any time a new line or transfer line is requested.

10.3.2.2 Telephone Number Availability

Enables a telephone number (TN) to be assigned to a line. Pilgrim will be able to accept the TN or exchange the TN for two other TNs. If the end user requests a specific number or a vanity number, Pilgrim must call the USWC Number Assignment Center (NAC) and the request will be handled manually. Pilgrim will not have direct access to the telephone number assignment system.

10.3.2.3 Exchange Telephone Numbers/Response

Enables Pilgrim to exchange the TN returned by the Telephone Number Availability Transaction for two more TNs. Pilgrim must select one of the three TNs to proceed with the Work Order.

10.3.2.4 Return Telephone Numbers

Enables Pilgrim to reject the TNs returned by the Telephone Number Availability transaction and the TNs will be returned to the pool.

10.3.2.5 Telephone Number Accept

Allows Pilgrim to reserve one telephone number returned by the Telephone Number Availability transaction for a period of one (1) day so that the end user can be informed of the TN(s) prior to the actual submission of a Work Order. The Work Order must be submitted before the TN expires, otherwise the TN will be returned to the available pool of TNs.

10.3.2.6 Appointment Availability

Allows Pilgrim to select an appointment from a calendar of available appointments. Pilgrim will not have direct access to the system but USWC will automatically execute this transaction after the Work Order has been submitted and a technician must be dispatched.

10.3.2.7 Appointment Reservation

Enables Pilgrim to reserve an available appointment after the appointment availability calendar has been returned to Pilgrim by USWC. USWC will return a confirmation number.

10.3.2.8 Work Order/Firm Order Completion

The work order provides the information and actions required for USWC to provision products, services and features. This transaction will also be used to cancel and change existing work orders. The information contained in a work order identifies Pilgrim, the end user desired due date, the service being requested, the order type (only change and migration to Pilgrim), POA (Proof of Authorization), class of service, telephone number and

additional information needed to successfully provision the requested service to the end user.

Once a work order is accepted by USWC, the assigned service order number will be returned to Pilgrim. This may not happen in real time. Pilgrim can then use the service order number to status the work order. Firm Order Confirmation means that USWC has received the order and assigned an order number for tracking. It does not mean that edits have been applied, so errors may still exist on the order.

10.3.2.9 Status Query/Response

This transaction will allow Pilgrim to obtain the status of a work order. USWC will return the current status, remarks and due date for specified work order.

Note: This status request is issued by Pilgrim on demand. Real Time Order Completion and Jeopardy Notification is not proactively issued by USWC.

10.3.2.10 Order Completion Report

Provides Pilgrim with a daily (Monday - Saturday) report, electronically, that identifies all work orders that were completed by USWC on that date. This report is called the CLEC Completion Report.

10.3.3. Repair

Repair functions allow Pilgrim to report trouble with communications circuits and services provided by USWC. The functions, processes and systems used in repair are based on a Trouble Report (TR), which is an electronic document maintained in one or more Operations Systems. A TR contains information about the end user, the trouble, the status of the work on the trouble and the results of the investigation and resolution efforts. These business processes have been summarized and will be made available to Pilgrim in the following functional set: open a trouble report, cancel a trouble report, send notification of status change and close a trouble report.

10.3.3.1 Verify Request

This transaction will be used to verify vertical features the end user currently owns. Technical discussions (e.g.,

Security) are currently ongoing within USWC as to how to provide this capability.

10.3.3.2 Open Trouble Report

Gives Pilgrim the capability to open a TR with USWC.

10.3.3.3 Open Trouble Report Response

Gives Pilgrim the capability to the Open TR request and contains information about the TR that Pilgrim needs to track or to convey to Pilgrim's end user.

10.3.3.4 Completion Notification

Provides notification to Pilgrim that a TR has been closed because the trouble was resolved.

10.3.3.5 Cancel Trouble Report Instruction

Allows Pilgrim to cancel a previously opened TR.

10.3.3.6 Status Change Notification

Provides notification to Pilgrim that the status of a previously opened TR has changed.

10.4 Billing Interfaces

USWC offers interfaces for the exchange of several types of billing data:

- Monthly Billing Information,
- Daily Usage Data,
- Local Account Maintenance Report,
- Centralized Message Distribution System (CMDS) messages,
- Routing of in-region intraLATA collect, calling card, and third number billed messages.

10.4.1 Monthly Billing Information

Includes all connectivity charges, credits, and adjustments related to network elements and USWC-provided local service.

10.4.2 Daily Usage Data

The accumulated set of call information for a given day as captured, or "recorded," by the network switches. USWC will

provide this data to Pilgrim with the same level of precision and accuracy it provides itself. Such precision cannot and will not exceed the current capabilities of the software in the switches today.

10.4.3 Local Account Maintenance Report

The list of phone numbers to which the carrier is no longer providing service since the last report.

10.4.4 Centralized Message Distribution System ("CMDS")

Distribution of CMDS messages for Pilgrim end users.

10.4.5 Routing of In-region IntraLATA Collect, Calling Card, and Third Number Billed Messages

USWC will distribute in-region intraLATA collect, calling card, and third number billed messages to Pilgrim and exchange with other Co-Providers operating in region in a manner consistent with existing inter-company processing agreements. Whenever the daily usage information is transmitted to a carrier, it will contain the records for these types of calls as well.

10.5 Compensation

10.5.1 If and as approved by the appropriate state Commission, compensation for OSS access will consist of an initial access fee which will be determined based on the specific access engineered and implemented for Pilgrim and is a function of the numbers of Pilgrim business office and repair service representatives accessing the system. The fee will include costs for hardware (if purchased through USWC), software (which must be purchased through USWC), telecommunications links and labor incurred to establish the interfaces to USWC's OSS for Pilgrim. The costs will be substantiated by purchasing invoices for the communications and computing hardware and software, and by time reports for the labor expended in their design and implementation. Labor will be billed at the prevailing rates for contract labor for similar services. Any and all charges set forth hereunder must be approved by the appropriate state Commission prior to USWC's sending Pilgrim any OSS invoices.

10.5.2 The ongoing charge will be billed at a rate to be specified by the Commission at the completion of an appropriate cost study hearing.

11. RESALE

11.1 Description

- 11.1.1 USWC Basic Exchange Telecommunications Service and Basic Exchange Switched Features (as defined in Section 3) and IntraLATA Toll originating from USWC exchanges will be available for resale from USWC pursuant to the Act and will reference terms and conditions (except prices) in USWC tariffs, where applicable. Appendix A lists services which are available for resale under this Agreement and applicable discounts.
- 11.1.2 The Parties agree that, at this time, certain USWC services are not available for resale under this Agreement and certain other USWC services are available for resale but at no discount, as identified in Appendix A or in individual state tariffs. The availability of services and applicable discounts identified in Appendix A or in individual tariffs are subject to change pursuant to the Rates and Charges sub-section of this Resale section.

11.2 Scope

- 11.2.1 Basic Exchange Telecommunications Service, Basic Exchange Switched Features and IntraLATA Toll may be resold only for their intended or disclosed use and only to the same class of end user to which USWC sells such services e.g., residence service may not be resold to business end users.
- 11.2.2 USWC shall provide to Pilgrim services for resale that are equal in quality, subject to the same conditions (including the conditions in USWC's effective tariffs), within provisioning time intervals that are substantially equal to the intervals USWC provides these services to others, including its end users, and in accordance with any applicable state Commission service quality standards, including standards a state Commission may impose pursuant to Section 252 (e)(3) of the Act.

11.3 Ordering and Maintenance

- 11.3.1 Pilgrim, or Pilgrim's agent, shall act as the single point of contact for its end users' service needs, including without limitation, sales, service design, order taking, provisioning, change orders, training, maintenance, trouble reports, repair, post-sale servicing, billing, collection and inquiry. Pilgrim shall make it clear to its end users that they are end users of Pilgrim for resold services. Pilgrim's end users contacting USWC will be instructed to contact Pilgrim;

however, nothing in this Agreement, except as provided below, shall be deemed to prohibit USWC from discussing its products and services with Pilgrim's end users who call USWC for any reason.

- 11.3.2 Pilgrim shall transmit to USWC all information necessary for the installation (billing, listing and other information), repair, maintenance and post-installation servicing according to USWC's standard procedures, as described in the USWC resale operations guide that will be provided to Pilgrim. When USWC's end user or the end user's new service provider discontinues the end user's service in anticipation of moving to another service provider, USWC will render its closing bill to the end user effective with the disconnection. If USWC is not the local service provider, USWC will issue a bill to Pilgrim for that portion of the service provided to Pilgrim should Pilgrim's end user, a new service provider, or Pilgrim request service be discontinued to the end user. USWC will notify Pilgrim by FAX, OSS, or other processes when an end user moves to another service provider. USWC will not provide Pilgrim with the name of the other Reseller or service provider selected by the end user. The Parties agree that they will not transfer to each other their respective end users whose accounts are in arrears. The Parties further agree that they will work cooperatively together to develop the standards and processes applicable to the transfer of such accounts.
- 11.3.3 Pilgrim shall provide USWC and USWC shall provide Pilgrim with points of contact for order entry, problem resolution and repair of the resold services.
- 11.3.4 Prior to placing orders on behalf of the end user, Pilgrim shall be responsible for obtaining and have in its possession Proof of Authorization ("POA"). POA shall consist of documentation acceptable to USWC of the end user's selection of Pilgrim. Such selection may be obtained in the following ways:
 - 11.3.4.1 The end user's written Letter of Authorization or LOA.
 - 11.3.4.2 The end user's electronic authorization by use of an 800 number,
 - 11.3.4.3 The end user's oral authorization verified by an independent third party (with third party verification as POA).
 - 11.3.4.4 A prepaid returnable postcard supplied by Pilgrim which has been signed and returned by end user. Pilgrim will

wait fourteen (14) days after mailing the postcard before placing an order to change.

- 11.3.5 Pilgrim shall make POAs available to USWC upon request. Prior to placing orders that will disconnect a line from another Reseller's account Pilgrim is responsible for obtaining all information needed to process the disconnect order and re-establish the service on behalf of the end user. Should an end user dispute or a discrepancy arise regarding the authority of Pilgrim to act on behalf of the end user, Pilgrim is responsible for providing written evidence of its authority to USWC within three (3) business days. If there is a conflict between the end user designation and Pilgrim's written evidence of its authority, USWC shall honor the designation of the end user and change the end user back to the previous service provider. If Pilgrim does not provide the POA within three (3) business days, or if the end user disputes the authority of the POA, then Pilgrim must, by the end of the third business day:
- 11.3.5.1 notify USWC to change the end user back to the previous Reseller or service provider, and
 - 11.3.5.2 provide any end user information and billing records Pilgrim has obtained relating to the end user to the previous Reseller, and
 - 11.3.5.3 notify the end user and USWC that the change has been made, and
 - 11.3.5.4 remit to USWC a charge of \$100.00 ("slamming charge") as compensation for the change back to the previous Reseller or service provider.
- 11.3.6 If an end user is switched from Pilgrim back to USWC and there is a dispute or discrepancy with respect to such change in service provider, Pilgrim may request to see a copy of the POA which USWC has obtained from the end user to effectuate a return to USWC as the end user's service provider. If USWC is unable to produce a POA within three (3) business days, USWC shall change the end user back to Pilgrim (or other previous Reseller) without imposition of any Customer Transfer Charge.
- 11.3.7 Pilgrim shall designate the Primary Interexchange Carrier (PIC) assignments on behalf of its end users for interLATA services and intraLATA services when intraLATA presubscription is implemented.

- 11.3.8 When end users switch from USWC to Pilgrim, or to Pilgrim from any other Reseller, such end users shall be permitted to retain their current telephone numbers if they so desire and do not change their service address to an address served by a different central office. USWC shall take no action to prevent Pilgrim end users from retaining their current telephone numbers.
- 11.3.9 Pilgrim and USWC will employ the procedures for handling misdirected repair calls as specified in the Coordinated Repair Calls section of this Agreement.

11.4 Pilgrim Responsibilities

- 11.4.1 Pilgrim must send USWC complete and accurate end-user listing information for Directory Assistance, Directory Listings, and 911 Emergency Services using USWC's resale order form and process. Pilgrim must provide to USWC accurate end-user information to ensure appropriate listings in any databases in which USWC is required to retain and/or maintain end-user information. USWC assumes no liability for the accuracy of information provided by Pilgrim.
- 11.4.2 Pilgrim may not reserve blocks of USWC telephone numbers, except as allowed by tariffs.
- 11.4.3 Pilgrim is liable for all fraud associated with service to its end-users and accounts. USWC takes no responsibility, will not investigate, and will make no adjustments to Pilgrim's account in cases of fraud unless such fraud is the result of any intentional act or gross negligence of USWC. Notwithstanding the above, if USWC becomes aware of potential fraud with respect to Pilgrim's accounts, USWC will promptly inform Pilgrim and, at the direction of Pilgrim, take reasonable action to mitigate the fraud where such action is possible.
- 11.4.4 In accordance with the Act, Pilgrim will indicate the date it will offer to residential and business subscribers telephone exchange services. Pilgrim will provide a three year forecast within ninety (90) days of signing this Agreement. During the first year of the term of this Agreement, the forecast shall be updated and provided to USWC on a quarterly basis. Thereafter, during the term of this Agreement Pilgrim will provide updated forecasts from time to time, as requested by USWC. The initial forecast will provide:
- The date service will be offered (by city and/or state)
 - The type and quantity of service(s) which will be offered

- Pilgrim's anticipated order volume
- Pilgrim's key contact personnel

The information provided pursuant to this paragraph shall be considered Proprietary Information under the Nondisclosure section of this Agreement.

- 11.4.5 In the event USWC terminates the provisioning of any resold services to Pilgrim for any reason, including disconnection of Pilgrim for failure to make payment as required herein, Pilgrim shall be responsible for providing any and all necessary notice to its end users of the termination. In no case shall USWC be responsible for providing such notice to Pilgrim's end users. USWC will provide notice to Pilgrim of USWC's termination of a resold service on a timely basis consistent with Commission rules and notice requirements.

11.5 Rates and Charges

- 11.5.1 Resold services as listed in Appendix A are available for resale at the applicable discount percentage or rate per minute set forth in Appendix A or at the retail tariff rates for services available for resale but excluded from the wholesale pricing arrangement in this Agreement.

However, state Commissions may do any of the following (collectively referred to hereinafter as "Order") during the term of this Agreement:

- establish wholesale discount rates through decisions in arbitration, interconnection and/or resale cost proceedings;
- establish other recurring and nonrecurring rates related to resale, including but not limited to Customer Transfer Charges and Slamming Charges ("Other Resale Charges"); and
- order that certain services be made available for resale at specified wholesale discount rates.

If a state Commission orders services to be available for resale, the Parties agree that they will, on a state-by-state basis, revise Appendix A to incorporate the services determined by such Order into this Agreement, effective on the date ordered by a Commission. When a state Commission, through a decision in arbitration, identifies services that must be available for resale at wholesale discount rates, such decision shall be deemed to have defined that such services are generally available to Resellers in that state. If a state Commission establishes wholesale discount rates and Other Resale Charges to be made generally available to

Resellers or establishes a resale tariff, the Parties agree that they will, on a state-by-state basis, revise Appendix A to incorporate such wholesale discount rates and/or Other Resale Charges into this Agreement effective on the date ordered by a Commission; provided, however, that USWC shall have a reasonable time to implement system or other changes necessary to bill the Commission ordered rates or charges.

The rates for those resold services initially included in the wholesale pricing arrangement under this Agreement shall be subject to true-up to the wholesale discount rates established by a Commission Order making such rates generally available to Resellers or established by a resale tariff, retroactively to the effective date of this Agreement. Any true-up shall be on a service-by-service basis if wholesale discount rates are established by a Commission on such a basis.

Services excluded from the wholesale pricing arrangement under this Agreement as identified in Appendix A, shall be made available on a going forward basis from the date of a Commission Order that orders such services be made generally available to any Reseller in the state where such a Commission Order is issued. Such services shall be available at the discount rate applicable to basic exchange business service identified in Appendix A; provided, however, that when a Commission Order establishes wholesale discount rates for such services as generally available to Resellers, Appendix A shall be revised to incorporate the wholesale discount rates generally available to Resellers.

If a state Commission fails to issue such an Order or make effective such a tariff by the end of the first year of this Agreement, either USWC or Pilgrim may elect to renegotiate this Section of the Agreement.

- 11.5.2 If the resold services are purchased pursuant to Tariffs and the Tariff rates change, charges billed to Pilgrim for such services will be based upon the new Tariff rates less the applicable wholesale discount as agreed to herein or established by resale Tariff. The new rate will be effective upon the Tariff effective date.
- 11.5.3 A Customer Transfer Charge (CTC) as specified in Appendix A applies when transferring any existing account or lines to Pilgrim. Tariffed, non-recurring charges will apply to new installations.
- 11.5.4 A Subscriber Line Charge (SLC) will continue to be paid by Pilgrim without discount for each local exchange line resold under

this Agreement. All federal and state rules and regulations associated with SLC as found in the applicable tariffs also apply.

- 11.5.5 Pilgrim will pay to USWC the PIC change charge without discount associated with Pilgrim end user changes of inter-exchange or intraLATA carriers.
- 11.5.6 Pilgrim agrees to pay USWC when its end user activates any services or features that are billed on a per use or per activation basis subject to the applicable discount in Appendix A as such may be amended pursuant to Section 11.5.1 above (e.g., continuous redial, last call return, call back calling, call trace, etc.).
- 11.5.7 Resold services are available only where facilities currently exist and are capable of providing such services without construction of additional facilities or enhancement of existing facilities. However, if Pilgrim requests that facilities be constructed or enhanced to provide resold services, USWC will review such requests on a case-by-case basis and determine, in its sole discretion, if it is economically feasible for USWC to build or enhance facilities. If USWC decides to build or enhance the requested facilities, USWC will develop and provide to Pilgrim a price quote for the construction. If the quote is accepted, Pilgrim will be billed the quoted price and construction will commence after receipt of payment.
- 11.5.8 Nonrecurring charges will not be discounted and will be billed at the applicable Tariff rates.
- 11.5.9 As a part of the resold line, USWC provides and Pilgrim accepts, at this time, operator services, directory assistance, and intraLATA long distance with standard USWC branding. Pilgrim is not permitted to alter the branding of these services in any manner when the services are a part of the resold line without the prior written approval of USWC. However, at the request of Pilgrim and where technically feasible, USWC will rebrand operator services and directory assistance in Pilgrim's name, provided the costs associated with such rebranding are paid by Pilgrim.

11.6 Collateral and Training

The Parties will jointly develop procedures regarding Pilgrim's use of USWC's retail product training materials. Except for any rights granted by USWC to Pilgrim for the use or copying of product training material, product training provided under this Agreement shall be considered "Proprietary Information" as

described in this Agreement, and shall be subject to the terms and conditions specified therein.

11.7 Directory Listings

USWC will accept at no charge one primary listing for each main telephone number belonging to Pilgrim's end user based on end user information provided to USWC by Pilgrim. USWC will place Pilgrim's listings in USWC's directory listing database for directory assistance purposes and will make listings available to directory publishers and to other third parties. Additional terms and conditions with respect to directory listings are described in the Ancillary Services and Arrangements section of this Agreement.

11.8 Billing

11.8.1. USWC shall bill Pilgrim and Pilgrim is responsible for all applicable charges for the resold services as provided herein. Pilgrim shall also be responsible for all tariffed charges and charges separately identified in this Agreement associated with services that Pilgrim resells to an end user under this Agreement.

11.8.2 USWC shall provide Pilgrim, on a monthly basis, within 7-10 days of the last day of the most recent billing period, in an agreed upon standard electronic billing format, billing information including (1) a summary bill, and (2) individual end user sub-account information consistent with the samples provided to Pilgrim for Pilgrim to render end user bills indicating all recurring and nonrecurring charges associated with each individual end user's account for the most recent billing period.

11.9 Deposit

11.9.1 USWC may require Pilgrim to make a suitable deposit to be held by USWC as a guarantee of the payment of charges. Any deposit required of an existing Reseller is due and payable within ten days after the requirement is imposed. The amount of the deposit shall be the estimated charges for the resold service which will accrue for a two-month period.

11.9.2 When the service is terminated, or when Pilgrim has established satisfactory credit, the amount of the initial or additional deposit, with any interest due as set forth in applicable Tariffs, will, at Pilgrim's option, either be credited to Pilgrim's account or refunded. Satisfactory credit for a Reseller is defined as twelve consecutive months service as a Reseller without a termination for nonpayment and with no more than one notification of intent to terminate service for nonpayment. Interest on the deposit shall be

accumulated by USWC at a rate equal to the federal discount rate, as published in the Wall Street Journal from time to time.

11.10 Payment

- 11.10.1 Amounts payable under this Resale Section are due and payable within thirty (30) days after the bill date of USWC's invoice. During the initial three billing cycles of this Agreement, Pilgrim and USWC agree that undisputed amounts shall be paid as provided herein. Pilgrim and USWC further agree that, during said three billing cycle period, they will cooperate to resolve amounts in dispute or billing process issues in a timely manner but no later than sixty (60) days after the bill date of USWC's invoice or identification and notice of the billing process issue. Disputed amounts will be paid within thirty (30) days following resolution of the dispute.
- 11.10.2 After the three (3) month period outlined above, Pilgrim will pay the bill in full within 30 days after the bill date of the invoice. Billing disputes will be processed and jointly resolved. Any disputed amounts that USWC remits to Pilgrim will be credited on the next billing cycle including an interest credit of 1.5% per month compounded.
- 11.10.3 A late payment charge of 1.5% applies to all billed balances which are not paid by 30 days after the bill date shown on the invoice. USWC agrees, however, that the application of this provision will be suspended for the initial three billing cycles of this Agreement and will not apply to amounts billed during those three cycles.
- 11.10.4 USWC may discontinue processing orders for the failure by Pilgrim to make full payment for the resold services provided under this Agreement within thirty (30) days of the due date on Pilgrim's bill. USWC agrees, however, that the application of this provision will be suspended for the initial three billing cycles of this Agreement and will not apply to amounts billed during those three cycles.
- 11.10.5 USWC may disconnect for the failure by Pilgrim to make full payment for the resold services provided under this Agreement within sixty (60) days of the due date on Pilgrim's bill. Pilgrim will pay the Tariff charge required to reconnect each end user line disconnected pursuant to this paragraph. USWC agrees, however, that the application of this provision will be suspended for the initial three billing cycles of this Agreement and will not apply to amounts billed during those three cycles.

- 11.10.6 Collection procedures and the requirements for deposit are unaffected by the application of a late payment charge.
- 11.10.7 USWC shall credit Pilgrim's account the amount due for any trouble or out-of-service conditions in the same manner that USWC credits the accounts of its own end users and pursuant to any applicable provisions in USWC's Tariffs. USWC shall reflect the amount of such credits on an individual end user telephone number basis in the billing information USWC provides Pilgrim.
- 11.10.8 In the event billing disputes relate to service quality issues, the dispute shall be referred to the USWC account executive assigned to Pilgrim who will evaluate the facts and circumstances of the service quality issues and will work with Pilgrim to resolve the dispute.

12. ACCESS TO TELEPHONE NUMBERS

12.1 Number Resources Arrangements.

- 12.1.1 Nothing in this Agreement shall be construed in any manner to limit or otherwise adversely impact either Party's right to the request and assignment of any NANP number resources including, but not limited to, central office (NXX) codes pursuant to the Central Office Code Assignment Guidelines (last published by the Industry Numbering Committee ("INC") as INC 95-0407-008, Revision 4/19/96, formerly ICCF 93-0729-010).
- 12.1.2 To the extent USWC serves as Central Office Code Administrator for a given region, USWC will support all Pilgrim requests related to central office (NXX) code administration and assignments in the manner required and consistent with the Central Office Code Assignment Guidelines.
- 12.1.3 The Parties will comply with code administration requirements as prescribed by the Federal Communications Commission, the Commission, and accepted industry guidelines.
- 12.1.4 It shall be the responsibility of each Party to program and update its own switches and network systems pursuant to the Local Exchange Routing Guide (LERG) guidelines to recognize and route traffic to the other Party's assigned NXX codes at all times. Neither Party shall impose any fees or charges whatsoever on the other Party for such activities. The Parties will cooperate to establish procedures to ensure the timely activation of NXX assignments in their respective networks.

- 12.1.5 Each Party shall be responsible for notifying its end users of any changes in numbering or dialing arrangements to include changes such as the introduction of new NPAs or new NXX codes.
- 12.1.6 Until an impartial entity is appointed to administer telecommunications numbering and to make such numbers available on an equitable basis, USWC will assign NXX codes to Pilgrim in accordance with national guidelines at no charge.
- 12.1.7 Each Party is responsible for administering NXX codes assigned to it. Each Party is responsible for obtaining LERG listings of CLLI codes assigned to its switches. Each Party shall use the LERG published by Bellcore or its successor for obtaining routing information and shall provide all required information to Bellcore for maintaining the LERG in a timely manner.

13. DIALING PARITY

The Parties shall provide Dialing Parity to each other as required under Section 251(b)(3) of the Act. This Agreement does not impact either Party's ability to default IntraLATA Toll via a specific dialing pattern until otherwise required by the Act.

14. U S WEST DEX ISSUES

USWC and Pilgrim agree that certain issues, such as yellow page advertising, directory distribution, access to call guide pages, yellow page listings, will be the subject of negotiations between Pilgrim and directory publishers, including U S WEST Dex. USWC acknowledges that Pilgrim may request USWC to facilitate discussions between Pilgrim and U S WEST Dex.

15. ACCESS TO DATABASES

In accordance with Section 271 of the Act, USWC shall provide Pilgrim with interfaces to access USWC's databases and associated signaling necessary for the routing and completion of Pilgrim traffic. Except where otherwise specified, access to such databases, and the appropriate interfaces, shall be requested by Pilgrim via a Bona Fide Request.

16. NOTICE OF CHANGES

If a Party makes a change in its network which it believes will materially affect the inter-operability of its network with the other Party, the Party making the change shall provide advance notice of such change to the other Party in accordance with the applicable FCC regulations.

17. REFERRAL ANNOUNCEMENT

When an end user changes from USWC to Pilgrim, or from Pilgrim to USWC, and does not retain its original main/listed telephone number, the Party formerly providing service to the end user will provide a transfer of service announcement on the abandoned telephone number. Each Party will provide this referral service consistent with its Tariff. This announcement will provide details on the new number that must be dialed to reach this end user.

18. COORDINATED REPAIR CALLS

18.1 Pilgrim and USWC will employ the following procedures for handling misdirected repair calls;

18.1.1 Pilgrim and USWC will provide their respective end users with the correct telephone numbers to call for access to their respective repair bureaus.

18.1.2 End users of Pilgrim shall be instructed to report all cases of trouble to Pilgrim. End users of USWC shall be instructed to report all cases of trouble to USWC.

18.1.3 To the extent the correct provider can be determined, misdirected repair calls will be referred to the proper provider of Basic Exchange Telecommunications Service.

18.1.4 Pilgrim and USWC will provide their respective repair contact numbers to one another on a reciprocal basis.

18.1.5 In responding to repair calls, neither Party shall make disparaging remarks about each other, nor shall they use these repair calls as the basis for internal referrals or to solicit end users to market services. Either Party may respond with accurate information in answering end user questions.

19. BONA FIDE REQUEST PROCESS

19.1 Any request for Interconnection or access to an unbundled Network Element that is not already available as described herein shall be treated as a Bona Fide Request (BFR). USWC shall use the BFR Process to determine the terms and timetable for providing the requested Interconnection or access to unbundled Network Elements, if available, and the technical feasibility of new/different points of Interconnection. USWC will administer the BFR Process in a non-discriminatory manner.

- 19.2 A BFR shall be submitted in writing and on the appropriate USWC form for BFRs. The form will request, and Pilgrim will need to provide, at a minimum: (a) a technical description of each requested Network Element or new/different points of Interconnection; (b) the desired interface specification; (c) each requested type of Interconnection or access; (d) a statement that the Interconnection or Network Element will be used to provide a telecommunications service; (e) the quantity requested; (f) the specific location requested; (g) if the requested unbundled Network Element is a proprietary element as specified in Section 251(d)(2) of the Act, Pilgrim must submit documentation that demonstrates that access to such Network Element is necessary, that the failure to provide access to such Network Element would impair the ability of Pilgrim to provide the services that it seeks to offer, and that Pilgrim's ability to compete would be significantly impaired or thwarted without access to such requested proprietary element; and (h) if the requested unbundled Network Element is a non-proprietary element as specified in Section 251(d)(2) of the Act, Pilgrim must submit documentation that demonstrates that denial of access to such unbundled non-proprietary Network Element would decrease the quality or increase the cost of the service sought to be offered by Pilgrim.
- 19.3 Within 15 business days of its receipt, USWC shall acknowledge receipt of the BFR and in such acknowledgment advise Pilgrim of missing information, if any, necessary to process the BFR. Thereafter, USWC shall promptly advise Pilgrim of the need for any additional information that will facilitate the analysis of the BFR.
- 19.4 Within 30 calendar days of its receipt of the BFR and all information necessary to process it, USWC shall provide to Pilgrim a preliminary analysis of the BFR. The preliminary analysis shall specify USWC's conclusions as to whether or not the requested Interconnection or access to an unbundled Network Element complies with the unbundling requirements set forth above.
- 19.4.1 If USWC determines during the 30 day period that a BFR does not qualify as a Network Element or Interconnection that is required to be provided under the Act, USWC shall advise Pilgrim as soon as reasonably possible of that fact, and USWC shall promptly, but in no case later than ten days after making such a determination, provide a written report setting forth the basis for its conclusion.
- 19.4.2 If USWC determines during the thirty day period that the BFR qualifies under the Act, it shall notify Pilgrim in writing of such determination within ten days.
- 19.4.3 As soon as feasible, but in any case within 90 days after USWC notifies Pilgrim that the BFR qualifies under the Act, USWC shall provide to Pilgrim a BFR quote. The BFR quote will include, at a minimum, a description of each Interconnection and Network

Element, the quantity to be provided, any interface specifications, and the applicable rates (recurring and nonrecurring) including the separately stated development costs and construction charges of the Interconnection or the Network Elements and any minimum volume and term commitments required.

- 19.5 If USWC has indicated minimum volume and term commitments, then within 30 days of its receipt of the BFR quote, Pilgrim must either agree to purchase under those commitments, cancel its BFR, or seek mediation or arbitration.
- 19.6 If Pilgrim has agreed to minimum volume and term commitments under the preceding paragraph, Pilgrim may cancel the BFR or volume and term commitment at any time, but in the event of such cancellation Pilgrim will pay USWC's reasonable development costs incurred in providing the Interconnection or Network Element, to the extent that those development costs are not otherwise amortized.
- 19.7 If either Party believes that the other Party is not requesting, negotiating or processing any BFR in good faith, or disputes a determination, or quoted price or cost, it may seek arbitration pursuant to the Dispute Resolution provision of this Agreement.

20. AUDIT PROCESS

- 20.1 "Audit" shall mean the comprehensive review of:
 - 20.1.1 Data used in the billing process for services performed and facilities provided under this Agreement; and
 - 20.1.2 Data relevant to provisioning and maintenance for services performed or facilities provided by either of the Parties for itself or others that are similar to the services performed or facilities provided under this Agreement for Interconnection or access to unbundled elements.
- 20.2 The data referred to above shall be relevant to any performance standards that are adopted in connection with this Agreement, through negotiation, arbitration or otherwise.

This Audit shall take place under the following conditions:

- 20.2.1 Either Party may request to perform an Audit.
- 20.2.2 The Audit shall occur upon 30 business days written notice by the requesting Party to the non-requesting Party.

- 20.2.3 The Audit shall occur during normal business hours.
- 20.2.4 There shall be no more than one Audit requested by each Party under this Agreement in any 12-month period.
- 20.2.5 The requesting Party may review the non-requesting Party's records, books and documents, as may reasonably contain information relevant to the operation of this Agreement.
- 20.2.6 The location of the Audit shall be the location where the requested records, books and documents are retained in the normal course of business.
- 20.2.7 All transactions under this Agreement which are over 24 months old will be considered accepted and no longer subject to Audit.
- 20.2.8 Each Party shall bear its own expenses occasioned by the Audit, provided that the expense of any special data collection shall be born by the requesting Party.
- 20.2.9 The Party requesting the Audit may request that an Audit be conducted by a mutually agreed-to independent auditor. Under this circumstance, the costs of the independent auditor shall be paid for by the Party requesting the Audit.
- 20.2.10 In the event that the non-requesting Party requests that the Audit be performed by an independent auditor, the Parties shall mutually agree to the selection of the independent auditor. Under this circumstance, the costs of the independent auditor shall be shared equally by the Parties.
- 20.2.11 The Parties agree that if an Audit discloses error(s), the Party responsible for the error(s) shall, in a timely manner, undertake corrective action for such error(s).
- 20.3 All information received or reviewed by the requesting Party or the independent auditor in connection with the Audit is to be considered Proprietary Information as defined by this Agreement. The non-requesting Party reserves the right to require any non-employee who is involved directly or indirectly in any Audit or the resolution of its findings as described above to execute a nondisclosure agreement satisfactory to the non-requesting Party. To the extent an Audit involves access to information of other competitors, Pilgrim and USWC will aggregate such competitors' data before release to the other Party, to insure the protection of the proprietary nature of information of other competitors. To the extent a competitor is an affiliate of the Party being audited (including itself and its subsidiaries), the Parties shall be allowed to examine such affiliates' disaggregated data, as required by reasonable needs of the Audit.

21. AUDIOTEXT AND MASS ANNOUNCEMENT SERVICES

- 21.1 The Parties agree that access to the audiotext, mass announcement and information services of each Party should be made available to the other Party upon execution of an agreement defining terms for billing and compensation of such calls. Services included in this category include 976 calls, if available, whether flat rated or usage sensitive, intra-LATA 900 services and other intra-LATA 976-like services. Such calls will be routed over the Local Interconnection Trunks.
- 21.2 Pilgrim and USWC will work together in good faith to negotiate and execute the agreement for billing and compensation for these services. The Parties agree that their separate agreement on audiotext and mass announcement services will include details concerning the creation, exchange and rating of records, all of which will occur without any explicit charge between the Parties, as well as a process for the handling of uncollectables so that the originating Party does not have any responsibility for uncollectables.
- 21.3 Until such time that such an agreement is executed, Pilgrim may choose to block such calls, or Pilgrim will agree to back-bill and compensate retroactively for such calls once the subsequent agreement is executed retroactive to the effective date of this Agreement.

21.3.1 Usage Sensitive Compensation.

All audiotext and mass announcement calls shall be considered toll calls for purposes of reciprocal compensation between the Parties. Compensation will be paid based on the compensation for toll calls referenced in this Agreement with respect to reciprocal compensation between the Parties, except that such compensation shall be paid by the Party terminating the call, rather than the Party originating the call.

21.3.2 Billing and Collection Compensation.

Billing and collection compensation will be dealt with in the separate agreement referenced in this section.

22. LOCAL INTERCONNECTION DATA EXCHANGE FOR BILLING

- 22.1 There are certain types of calls or types of Interconnection that require exchange of billing records between the Parties, including, for example, alternate billed and Toll Free Service calls. The Parties agree that all call types must be routed between the networks, accounted for, and settled among the Parties. Certain calls will be handled via the Parties' respective operator service platforms. The

Parties agree to utilize, where possible and appropriate, existing accounting and settlement systems to bill, exchange records and settle revenue.

- 22.2 The exchange of billing records for alternate billed calls (e.g., calling card, bill-to-third number, and collect) will be distributed through the existing CMDS processes, unless otherwise separately agreed to by the Parties.
- 22.3 Inter-Company Settlements ("ICS") revenues will be settled through the Calling Card and Third Number Settlement System ("CATS"). Each Party will provide for its own arrangements for participation in the CATS processes, through direct participation or a hosting arrangement with a direct participant.
- 22.4 Non-ICS revenue is defined as collect calls, calling card calls, and billed to third number calls which originate on one service provider's network and terminate on another service provider's network in the same Local Access Transport Area ("LATA"). The Parties agree to negotiate and execute an agreement for settlement of non-ICS revenue. This separate arrangement is necessary since existing CATS processes do not permit the use of CATS for non-ICS revenue. The Parties agree that the CMDS system can be used to transport the call records for this traffic.
- 22.5 Both Parties will provide the appropriate call records to the intraLATA Toll Free Service provider, thus permitting the service provider to bill its subscribers for the inbound Toll Free Service. No adjustments to bills via tapes, disks or NDM will be made without the mutual agreement of the Parties.

23. CONSTRUCTION CHARGES

- 23.1 All rates, charges and initial service periods specified in this Agreement contemplate the provision of network Interconnection services and access to Network Elements to the extent existing facilities are available. Except for modifications to existing facilities necessary to accommodate Interconnection and access to Network Elements specifically provided for in this Agreement, USWC will consider requests to build additional or further facilities for network Interconnection and access to Network Elements as described in this Section.
- 23.2 Resale

Construction charges associated with the resale of services will be applied in the same manner that construction charges apply to USWC's retail end users. Contracts may be negotiated on an individual case basis when construction is required for large retail or resale customers.

23.3 Interconnection

To the extent that USWC constructs facilities for Interconnection services, Pilgrim will provide USWC with a forecast of interoffice trunks and switch ports. USWC will perform a validated traffic engineering estimate based on the forecasted demand and will then negotiate an agreed upon quantity of interoffice trunks and switch ports with Pilgrim before constructing facilities. If Pilgrim's forecasted quantity exceeds USWC's validated traffic engineering estimate, and if USWC finds it necessary to construct added facilities, then construction charges will apply to the exceeded quantity. USWC will track utilization of trunks, and when minimum trunk utilization requirements are not met, a recurring charge will apply for all unused trunks below the minimum utilization level.

23.4 Unbundled Network Elements

When Pilgrim requests USWC will conduct an individual financial assessment of any request which requires construction of network capacity, facilities, or space for access to or use of unbundled Network Elements. If USWC constructs to fulfill Pilgrim's request for unbundled Network Elements, USWC will bid this construction on a case-by-case basis. USWC will charge for the construction through non-recurring charges and a term agreement for the remaining recurring charge. However, none of these charges shall apply specifically or solely to Pilgrim to the extent that such construction is undertaken by USWC in the ordinary course of its business.

23.5 All necessary construction will be undertaken at the discretion of USWC, consistent with budgetary responsibilities, consideration for the impact on the general body of end users, and without discrimination among the various carriers.

23.6 A quote for Pilgrim's portion of a specific job will be provided to Pilgrim. The quote will be in writing and will be binding for ninety (90) days after the issue date. When accepted, Pilgrim will be billed the quoted price and construction will commence after receipt of payment. If Pilgrim chooses not to have USWC construct the facilities, USWC reserves the right to bill Pilgrim for the expense incurred for producing the engineered job design.

23.7 In the event a construction charge is applicable, Pilgrim's service application date will become the date upon which USWC receives the required payment.

24. SERVICE PERFORMANCE RESULTS

24.1 USWC agrees to provide to Pilgrim the same level of service that USWC provides to itself and/or its affiliates as determined by measuring and comparing a statistically significant number of activities listed below.

24.1.1 For those services procured by Pilgrim and unless otherwise noted below, USWC shall measure its results and those of its affiliates as a percentage. USWC shall also measure the percentage results of Pilgrim.

Pilgrim agrees to measure its performance related to these performance indicators in providing service to USWC.

24.1.2 In some instances, USWC may not provide the listed service to itself or its affiliates. If USWC does not provide a statistically significant number of a listed activity for itself or its affiliates, USWC will provide data which will allow comparison between Pilgrim's performance results and the average performance results of the same performance indicator for a statistically significant number of total activities provided to all other within the state in which the service was provided.

24.1.3 In no event shall percentage results be provided if the number of measured activities is less than a statistically significant universe of fewer than sixty (60) activities during the time period of measurement.

24.1.4 The list of performance indicators to be measured monthly are as follows:

Resale Indicators

Residence Installation Intervals Offered (Facilities in Place)

Business Installation Intervals Offered (Facilities in Place)

Firm Order Confirmations within 48 hours (DS0) (Facilities in Place)

Firm Order Confirmations within 48 hours (DS1) (Facilities in Place)

Firm Order Confirmations within 48 hours (DS3) (Facilities in Place)

Firm Order Confirmations within 48 hours (Switched) (Facilities in Place)

Average Installation Intervals Delivered (Residence) (Facilities in Place) (Days and Hours)

Average Installation Intervals Delivered (Business) (Facilities in Place) (Days and Hours)

Average Installation Intervals Delivered (DS0) (Facilities in Place) (Days and Hours)

Average Installation Intervals Delivered (DS1) (Facilities in Place) (Days and Hours)

Average Installation Intervals Delivered (DS3) (Facilities in Place) (Days and Hours)

Average Installation Intervals Delivered (Switched) (Facilities in Place) (Days and Hours)

Residence Installation Commitments Met (Facilities in Place)
Business Installation Commitments Met (Facilities in Place)
Designed Installation Commitments Met (DS0) (Facilities in Place)
Designed Installation Commitments Met (DS1) (Facilities in Place)
Designed Installation Commitments Met (DS3) (Facilities in Place)
Designed Installation Commitments Met (Switched) (Facilities in Place)
CLEC-caused Installation Misses

Residence Disconnect Commitments Met
Business Disconnect Commitments Met

Residence Installation Reports (Repair Report After Installation) Within 7 Days
Business Installation Reports (Repair Report After Installation) Within 7 Days
Designed Installation Reports (Repair Report After Installation) Within 30 Days
(DS0)
Designed Installation Reports (Repair Report After Installation) Within 30 Days
(DS1)
Designed Installation Reports (Repair Report After Installation) Within 30 Days
(DS3)
Designed Installation Reports (Repair Report After Installation) Within 30 Days
(Switched Access)

Residence Percent Out of Service Cleared < 24 hours
Business Percent Out of Service Cleared in < 24 hours
Designed Percent Out of Service Cleared < 4 hours (DS0)
Designed Percent Out of Service Cleared in < 4hours (DS1)
Designed Percent Out of Service Cleared < 4 hours (DS3)
Designed Percent Out of Service Cleared in < 4 hours (Switched)

Residence Percent Out of Service and Service Affecting Cleared < 48 hours
Business Percent Out of Service and Service Affecting Cleared < 48 hours

Residence Repair Commitments Met
Business Repair Commitments Met

Residence Repair Repeated Reports Within 30 Days
Business Repair Repeated Reports Within 30 Days
Designed Repair Repeated Reports Within 30 Days (DS0)
Designed Repair Repeated Reports Within 30 Days (DS1)
Designed Repair Repeated Reports Within 30 Days (DS3)
Designed Repair Repeated Reports Within 30 Days (Switched)

Residence Report Rate per 100 Lines
Business Report Rate per 100 Lines
CLEC-caused Trouble Reports

Unbundled Loop Indicators

Firm Order Confirmations Within 48 hours (Facilities in Place) 2 Wire
Firm Order Confirmations Within 48 hours (Facilities in Place) 4 Wire
Average Installation Intervals Delivered (Facilities in Place) 2 Wire (Days and
Hours)
Average Installation Intervals Delivered (Facilities in Place) 4 Wire (Days and
Hours)
Percent Installation Commitments Met (Facilities in Place) 2 Wire
Percent Installation Commitments Met (Facilities in Place) 4 Wire
Installation Reports Within 30 Days 2 Wire
Installation Reports Within 30 Days 4 Wire

Percent Out of Service Cleared in < 24 hours 2 Wire
Percent Out of Service Cleared in < 24 hours 4 Wire
Percent Out of Service and Service Affecting Cleared in < 48 hours 2 Wire
Percent Out of Service and Service Affecting Cleared in < 48 hours 4 Wire
Mean Time to Restore 2 Wire
Mean Time to Restore 4 Wire
Repair Repeated Reports Within 30 Days 2 Wire
Repair Repeated Reports Within 30 Days 4 Wire

Digital Capable Loop Indicators (available 3d Quarter, 1998)

Installation Commitments Met (percentages)
Average Installation Intervals Delivered (days)
CLEC-caused Installation Misses (percentages)
Installation Reports Within 30 Days (percentages)
Report Rate (percentages)
CLEC-caused Trouble Tickets (percentages)
Mean time to Restore (hours)
Repeated Repair Reports Within 30 days (percentages)

LIS Trunk Indicators

Firm Order Confirmations Within Six Days (Facilities in Place)
Average Installation Intervals Delivered (Facilities in Place) (Days and Hours)
Installation Commitments Met (Facilities in Place)
Installation Reports Within 30 Days
Out of Service Cleared in < 4 hours
Repair Repeated Reports Within 30 Days
CLEC-caused Trouble Reports

- 24.2 Failure to Meet the Service Standard. If during a specified review period, the performing Party fails to deliver the same level of service that it provides to itself, such Party will use its best efforts to meet the service standard for the next specified review period. If the performing Party fails to meet the service standard for two consecutive periods, the Parties agree, in good faith, to attempt to resolve such issues through negotiation or pursuant to the Dispute Resolution section of this Agreement. This paragraph shall not be construed to waive either Party's right to seek legal or regulatory intervention as provided by state or federal law.
- 24.3 The performing Party's failure to meet the service standard cannot be as a result, directly or indirectly, of a Delaying Event. A "Delaying Event" means (a) a failure by the receiving Party to perform any of its obligations set forth in this Agreement, (b) any delay, act or failure to act by an end user, agent or subcontractor of the receiving Party or (c) any Force Majeure Event. If a Delaying Event prevents the performing Party from performing a measured activity, then such measured activity shall be excluded from the calculation of the performing Party's compliance with the service standard.
- 24.4 Records. Each Party shall maintain complete and accurate records, for the specified review period of its performance under this Agreement for each measured activity and its compliance with the service standard. Each Party shall provide to the other such records in a self-reporting format. Such records shall

be in the format kept in the performing Party's ordinary course of business. The Parties agree that such records shall be deemed "Proprietary Information".

- 24.5 Cost Recovery. Each Party reserves the right to recover the costs associated with the creation of the above reports and standards through a future proceeding before a regulatory body. Such a proceeding may address a wide range of implementation costs not otherwise recovered through charges established herein.

25. IMPLEMENTATION SCHEDULE

- 25.1 Within six months from the date of final approval of this Agreement, the Parties agree to make a good faith effort to complete each of the following interconnection arrangements:
- 25.1.1 Two-way trunk groups, as listed in Section 6.7.2 herein, necessary for the mutual exchange of traffic.
 - 25.1.2 E-911 trunking and database access.
 - 25.1.3 SS7 Interconnection and Certification.
 - 25.1.4 Directory Listings Arrangements and Directory Assistance Interconnection.
 - 25.1.5 Access to Unbundled Loops in at least one wire center.
 - 25.1.6 Completion of Physical Collocation arrangements in at least one USWC Wire Center.
 - 25.1.7 Completion of inter-carrier billing arrangements necessary for the joint provision of Switched Access Services and for reciprocal traffic exchange.

26. MISCELLANEOUS TERMS

26.1 General Provisions

- 26.1.1 Each Party shall use its best efforts to comply with the Implementation Schedule.
- 26.1.2 The Parties are each solely responsible for participation in and compliance with national network plans, including the National Network Security Plan and the Emergency Preparedness Plan.

- 26.1.3 Neither Party shall use any service related to or use any of the services provided in this Agreement in any manner that interferes with other persons in the use of their service, prevents other persons from using their service, or otherwise impairs the quality of service to other carriers or to either Party's end users, and each Party may discontinue or refuse service if the other Party violates this provision. Upon such violation, either Party shall provide the other Party notice of such violation, if practicable, at the earliest practicable time.
- 26.1.4 Each Party is solely responsible for the services it provides to its end users and to other Telecommunications Carriers.
- 26.1.5 The Parties shall work cooperatively to minimize fraud associated with third-number billed calls, calling card calls, and any other services related to this Agreement.
- 26.1.6 USWC shall, within ten (10) days of receiving a request from Pilgrim, provide Pilgrim a letter substantially in the form set forth below:

[On U S WEST letterhead]

To Whom It May Concern:

U S WEST ("USWC") is the owner and landlord of certain real property including its central offices within its fourteen states region ("Premises"). Pursuant to that certain Interconnection Agreement between USWC and Pilgrim Telephone, Inc. ("Pilgrim") made as of _____ ("Interconnection Agreement"), related USWC tariffs and applicable law, Pilgrim has the right to place certain of its own personal property or equipment ("Equipment") on such Premises. Equipment thus placed by Pilgrim on the Premises is deemed, as between USWC and Pilgrim, to be the personal property of Pilgrim even though it may be placed on or affixed to the Premises.

This letter is to provide assurance that USWC does not now possess and does not now assert any claim of title to, any other right to or interest in any equipment placed by Pilgrim on the Premises under the Interconnection Agreement and related USWC tariffs. This letter does not preclude or prevent USWC from obtaining or possessing a subsequent security interest in Equipment as may arise in the future from time to time. USWC will not oppose any reasonable attempt by any financial institution or other lender of Pilgrim, or any successor in interest of assignee of such lender ("Lender") to enter, at reasonable times, the Premises to exercise any legal right it may have to take possession and dispose of the, provided any such possession and disposal can be achieved without a breach of the peace and without interference in any way with any prior perfected security interest USWC may have in such Equipment.

Any right or interest in the Equipment which USWC now has or may hereafter acquire because of the location or installation of the Equipment on the Premises or otherwise is hereby made subject, subordinate and inferior to the rights of Lender in the Equipment existing at the date hereof. USWC shall retain any rights it may have to bring any legal actions against Pilgrim for non-payment of charges otherwise due, subject to Lender's rights with respect to the Equipment and to enforce any properly perfected security interest it may have in such Equipment arising after the date hereof.

Any damage to the Premises caused by Lender when removing the Equipment must be promptly repaired by Lender and/or Pilgrim.

Lender and Pilgrim hereby agree to hold USWC harmless from any and all actions or nonactions of any nature whatsoever taken by any party pursuant to this letter. All parties acknowledge that this letter is furnished by USWC solely at Pilgrim's request and to facilitate the efforts of Pilgrim to finance the purchase of equipment that Pilgrim proposes to place on the Premises pursuant to Pilgrim's rights under the Interconnection Agreement, related USWC tariffs and applicable law, and this letter is not intended to alter, and shall not have the effect of altering, the rights and obligations of either Pilgrim or USWC under their existing contractual and other arrangements.

Sincerely,

By US WEST On Behalf of Itself, its Successors and Assigns
[name, title and date]

26.2 Term of Agreement

This Agreement shall become effective upon Commission approval, pursuant to Sections 251 and 252 of the Act and shall terminate on May 1, 2002 (Termination Date), and shall be binding upon the Parties during the term, notwithstanding Section 252 (i) of the Act. The Parties agree to commence negotiation on a new Agreement no later than six (6) months before the Agreement terminates. If within 135 days before the termination date of the Agreement, the Parties have not reached agreement on a new Interconnection Agreement, either Party shall have the right to seek arbitration under 252(i) of the Act within 25 days after the Termination Date. Further, upon the conclusion of the term of the this Agreement, Pilgrim, consistent with Section 252 (i) of the Act, may opt into a then-existing, valid Interconnection Agreement, in its entirety. During the pendency of the arbitration proceeding this Agreement shall remain in effect.

26.3 Letter of Authorization

Where so indicated in specific sections of this Agreement, Pilgrim is responsible to have a Letter of Authorization. Pilgrim is solely responsible to obtain authorization from its end user for the handling of the disconnection of the end user's service with USWC, the provision of service by Pilgrim, and the provision of Unbundled Loops and all other ancillary services. Should a dispute or discrepancy arise regarding the authority of Pilgrim to act on behalf of the end user, Pilgrim is responsible for providing written evidence of its authority to USWC. After this Agreement is approved and Pilgrim is providing telecommunications services in the state of North Dakota, should a dispute or discrepancy arise regarding the authority of either Party to act on behalf of the end user, such Party is responsible for providing written evidence of its authority to the other Party.

26.4 Payment

- 26.4.1 Amounts payable under this Agreement are due and payable within thirty (30) days after the date of invoice.
- 26.4.2 Except as specified in the Resale section of this Agreement or elsewhere in this Agreement, any amount due and not paid by the due date stated above shall be subject to a late charge equal to either i) 0.03 percent per day compounded daily for the number of calendar days from the payment due date to and including, the date of payment, that would result in an annual percentage rate of 12% or ii) the highest lawful rate, whichever is less. If late payment charges for services are not permitted by local jurisdiction, this provision shall not apply.
- 26.4.3 Accept for bills submitted by USWC to Pilgrim pursuant to Section 4.1, or as otherwise ordered by the Commission with respect to rates and charges, USWC shall submit monthly bills to Pilgrim no later than 60 days after the month in which service is provided. Pilgrim shall not be responsible for paying untimely bills. Should Pilgrim dispute any portion of the monthly billing under this Agreement, Pilgrim will notify USWC in writing within thirty (30) days of the receipt of such billing, identifying the amount and details of such dispute. Both Pilgrim and USWC agree to expedite the investigation of any disputed amounts in an effort to resolve and settle the dispute prior to initiating any other rights or remedies. Pilgrim shall notify USWC in the event that it does not receive a bill from USWC within 45 days of ordering the Service.
- 26.4.4 If Pilgrim is repeatedly delinquent in making its payments, USWC may, in its sole discretion, require a deposit to be held as security for the payment of charges. "Repeatedly delinquent" means being thirty (30) days or more delinquent for three (3) consecutive months. The deposit may not exceed the estimated total monthly charges for a two (2) month period. The deposit may be a cash deposit, a letter of credit with terms and conditions acceptable to USWC in its sole discretion, or some other form of mutually acceptable security.
- 26.4.5 Interest will be paid on cash deposits at the rate applying to deposits under applicable Commission rules, regulations, or Tariffs. Cash deposits and accrued interest will be credited to Pilgrim's account or refunded, as appropriate, upon the earlier of the termination of this Agreement or one full year of timely payments in full by Pilgrim. The fact that a deposit has been made does not relieve Pilgrim from any requirements of this Agreement.

26.5 Taxes

Each Party purchasing services hereunder shall pay or otherwise be responsible for all applicable federal, state, or local sales, use, excise, gross receipts, transaction or similar taxes, fees or surcharges levied against or upon such purchasing Party (or the providing Party when such providing Party is permitted to pass along to the purchasing Party such taxes, fees or surcharges), except for any tax on either Party's corporate existence, status or income. Whenever possible, these amounts shall be billed as a separate item on the invoice. To the extent a sale is claimed to be for resale tax exemption, the purchasing Party shall furnish the providing Party a proper resale tax exemption certificate as authorized or required by statute or regulation by the jurisdiction providing said resale tax exemption. Failure to timely provide said resale tax exemption certificate will result in no exemption being available to the purchasing Party.

26.6 Force Majeure

Neither Party shall be liable for any delay or failure in performance of any part of this Agreement from any cause beyond its control and without its fault or negligence including, without limitation, acts of nature, acts of civil or military authority, government regulations, embargoes, epidemics, terrorist acts, riots, insurrections, fires, explosions, earthquakes, nuclear accidents, floods, work stoppages, equipment failure, power blackouts, volcanic action, other major environmental disturbances, unusually severe weather conditions, inability to secure products or services of other persons or transportation facilities or acts or omissions of transportation carriers (collectively, a "Force Majeure Event"). In the event of a labor dispute or strike the Parties agree to provide service to each other at a level equivalent to the level they provide themselves.

26.7 Limitation of Liability

26.7.1 Except as otherwise provided in the indemnity section, no Party shall be liable to the other Party for any loss, defect or equipment failure caused by the conduct of the other Party, the other Party's agents, servants, contractors or others acting in aid or concert with the other Party.

26.7.2 Except for indemnity obligations, each Party's liability to the other Party for any loss relating to or arising out of any negligent act or omission in its performance of this Agreement, whether in contract or in tort, shall be limited to the total amount that is or would have been charged to the other Party by such negligent or breaching Party for the service(s) or function(s) not performed or improperly performed.

- 26.7.3 In no event shall either Party have any liability whatsoever to the other Party for any indirect, special, consequential, incidental or punitive damages, including but not limited to loss of anticipated profits or revenue or other economic loss in connection with or arising from anything said, omitted or done hereunder (collectively, "Consequential Damages"), even if the other Party has been advised of the possibility of such damages; provided, that the foregoing shall not limit a Party's obligation to indemnify, defend and hold the other Party harmless against any amounts payable to a third party, including any losses, costs, fines, penalties, criminal or civil judgments or settlements, expenses (including attorneys' fees) and Consequential Damages of such third party. Nothing contained in this Section 26 shall limit either Party's liability to the other for (i) willful or intentional misconduct (including gross negligence); (ii) bodily injury, death or damage to tangible real or tangible personal property proximately caused by such Party's negligent act or omission or that of their respective agents, subcontractors or employees nor shall anything contained in this section limit the Parties' indemnification obligations, as specified above.
- 26.7.4 Nothing contained in this Section shall limit either Party's liability to the other for intentional, malicious misconduct.
- 26.7.5 Nothing contained in this Section shall limit either Party's obligations of indemnification as specified in the Indemnity Section of this Agreement.

26.8 Indemnity

- 26.8.1 With respect to third party claims, each of the Parties agrees to release, indemnify, defend and hold harmless the other Party and each of its officers, directors, employees and agents (each an "Indemnitee") from and against and in respect of any loss, debt, liability, damage, obligation, claim, demand, judgment or settlement of any nature or kind, known or unknown, liquidated or unliquidated including, but not limited to, costs and attorneys' fees, whether suffered, made, instituted, or asserted by any other party or person, for invasion of privacy, personal injury to or death of any person or persons, or for loss, damage to, or destruction of property, whether or not owned by others, resulting from the indemnifying Party's performance, breach of applicable law, or status of its employees, agents and subcontractors; or for failure to perform under this Agreement, regardless of the form of action.

26.8.2 The indemnification provided herein shall be conditioned upon:

26.8.2.1 The indemnified Party shall promptly notify the indemnifying Party of any action taken against the indemnified Party relating to the indemnification. Failure to so notify the indemnifying Party shall not relieve the indemnifying Party of any liability that the indemnifying Party might have, except to the extent that such failure prejudices the indemnifying Party's ability to defend such claim.

26.8.2.2 The indemnifying Party shall have sole authority to defend any such action, including the selection of legal counsel, and the indemnified Party may engage separate legal counsel only at its sole cost and expense.

26.8.2.3 In no event shall the indemnifying Party settle or consent to any judgment pertaining to any such action without the prior written consent of the indemnified Party.

26.9 Intellectual Property

26.9.1 Each Party hereby grants to the other Party the limited, personal and nonexclusive right and license to use its patents, copyrights and trade secrets but only to the extent necessary to implement this Agreement or specifically required by the then applicable federal and state rules and regulations relating to Interconnection and access to telecommunications facilities and services, and for no other purposes. With regard to any such other intellectual property not necessary to implement this Agreement, the Parties may enter into a separate agreement pertaining thereto. Nothing in this Agreement shall be construed as the grant to the other Party of any rights or licenses to trademarks.

26.9.2 The rights and licenses above are granted "AS IS" and the other Party's exercise of any such right and license shall be at the sole and exclusive risk of the other Party. Neither Party shall have any obligation to defend, indemnify or hold harmless, or acquire any license or right for the benefit of, or owe any other obligation or have any liability to, the other based on or arising from any claim, demand, or proceeding (hereinafter "claim") by any third party alleging or asserting that the use of any circuit, apparatus, or system, or the use of any software, or the performance of any service or method, or the provision of any facilities by either Party under this Agreement constitutes infringement, or misuse or misappropriation of any patent, copyright, trade secret, or any other proprietary or intellectual property right of any third party.

- 26.9.3 As a condition to the access or use of patents, copyrights, trade secrets and other intellectual property (including software) owned or controlled by a third party to the extent necessary to implement this Agreement or specifically required by the then applicable federal and state rules and regulations relating to Interconnection and access to telecommunications facilities and services, the Party providing access may require, the other Party upon written notice, from time to time, to obtain a license or permission for such access or use, make all payments in connection with obtaining such license, and provide evidence of such license. However, nothing stated in this Section shall constitute a waiver of either Party's rights under applicable law involving such third party intellectual property and the right to raise any such legal arguments in a Federal court action.
- 26.9.4 Except as expressly provided in this Intellectual Property Section, nothing in this Agreement shall be construed as the grant of a license, either express or implied, with respect to any patent, copyright, logo, trademark, tradename, trade secret or any other intellectual property right now or hereafter owned, controlled or licensable by either Party. Neither Party may use any patent, copyright, logo, trademark, tradename, trade secret or other intellectual property right of the other Party or its affiliates without execution of a separate agreement between the Parties.
- 26.9.5 Neither Party shall, without the express written permission of the other Party, state or imply that; 1) it is connected, or in any way affiliated with the other Party or its affiliates, 2) it is part of a joint venture, business association, or any similar arrangement with the other Party or its affiliates, 3) a Party and its affiliates are in any way sponsoring, endorsing or certifying the other Party and its goods and services, or 4) with respect to either Party's advertising or promotional activities or materials, that the resold goods and services are in any way associated with or originated from the other Party or any of its affiliates. Nothing in this paragraph shall prevent either Party from truthfully describing the Network Elements and wholesale services it uses to provide service to its customers.
- 26.9.6 For purposes of resale only and notwithstanding the above, unless otherwise prohibited by USWC pursuant to an applicable provision herein, Pilgrim may use the phrase "Pilgrim is a reseller of U S WEST Communications services" (the "Authorized Phrase") in Pilgrim's printed materials provided:

- 26.9.6.1 The Authorized Phrase is not used in connection with any goods or services other than USWC services resold by Pilgrim.
- 26.9.6.2 Pilgrim's use of the Authorized Phrase does not, in USWC's sole discretion, cause end users to believe that Pilgrim is USWC.
- 26.9.6.3 The Authorized Phrase, when displayed, appears only in text form (Pilgrim may not use the U S WEST logo) with all letters being the same font and point size. The point size of the Authorized Phrase shall be no greater than one fourth the point size of the smallest use of Pilgrim's name and in no event shall exceed 8 point size.
- 26.9.6.4 Pilgrim shall provide all printed materials to USWC for its prior written approval.
- 26.9.6.5 If USWC determines that Pilgrim's use of the Authorized Phrase causes end user confusion, USWC may in its sole discretion, immediately terminate Pilgrim's right to use the Authorized Phrase.
- 26.9.6.6 Upon termination of Pilgrim's right to use the Authorized Phrase or termination of this Agreement, all permission or right to use the Authorized Phrase shall immediately cease to exist and Pilgrim shall immediately cease any and all such use of the Authorized Phrase. Pilgrim shall either promptly return to USWC or destroy all materials in its possession or control displaying the Authorized Phrase.
- 26.9.7 Each Party acknowledges the value of the other Party's marks (the "Marks") and the goodwill associated therewith and acknowledges that such goodwill is a property right belonging to the other Party (the "Owners"). Each Party recognizes that nothing contained in this Agreement is intended as an assignment or grant to the other Party of any right, title or interest in or to the Marks and that this Agreement does not confer any right or license to grant sublicenses or permission to third parties to use the Marks and is not assignable. Neither Party will do anything inconsistent with the Owner's ownership of the Marks, and all rights, if any, that may be acquired by use of the Marks shall inure to the benefit of the Owners. Neither Party will adopt, use (other than as authorized herein), register or seek to register any mark anywhere in the world which is identical or confusingly similar to the Marks or which is so similar thereto as to constitute a deceptive colorable imitation thereof or to suggest or imply some association, sponsorship, or endorsement by the Owners. The

Owners make no warranties regarding ownership of any rights in or the validity of the Marks.

26.10 Warranties

NOTWITHSTANDING ANY OTHER PROVISION OF THIS AGREEMENT, THE PARTIES AGREE THAT NEITHER PARTY HAS MADE, AND THAT THERE DOES NOT EXIST, ANY WARRANTY, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE.

USWC SHALL CONDUCT ALL ACTIVITIES AND INTERFACES WHICH ARE PROVIDED FOR UNDER THIS AGREEMENT WITH PILGRIM CUSTOMERS IN A CARRIER-NEUTRAL, NONDISCRIMINATORY MANNER.

26.11 Assignment

Neither Party may assign or transfer (whether by operation of law or otherwise) this Agreement (or any rights or obligations hereunder) to a third party without the prior written consent of the other Party provided that each Party may assign this Agreement to a corporate affiliate or an entity under its common control or an entity acquiring all or substantially all of its assets or equity by providing prior written notice to the other Party of such assignment or transfer. Any attempted assignment or transfer that is not permitted is void ab initio. Without limiting the generality of the foregoing, this Agreement shall be binding upon and shall inure to the benefit of the Parties' respective successors and assigns.

26.12 Default

If either Party defaults in the payment of any amount due hereunder, or if either Party violates any other provision of this Agreement, and such default or violation shall continue for thirty (30) days after written notice thereof, the other Party may seek legal and/or regulatory relief. The failure of either Party to enforce any of the provisions of this Agreement or the waiver thereof in any instance shall not be construed as a general waiver or relinquishment on its part of any such provision, but the same shall, nevertheless, be and remain in full force and effect.

26.13 Disclaimer of Agency

Except for provisions herein expressly authorizing a Party to act for another, nothing in this Agreement shall constitute a Party as a legal representative or agent of the other Party, nor shall a Party have the right or authority to assume, create or incur any liability or any obligation of any kind, express or implied, against or in the name or on behalf of the other Party unless otherwise expressly permitted by such other Party. Except as otherwise expressly provided in this

Agreement, no Party undertakes to perform any obligation of the other Party whether regulatory or contractual, or to assume any responsibility for the management of the other Party's business.

26.14 Severability

In accordance with Section 1 of this Agreement, if one or more of the provisions contained herein must be modified because of changes in Existing Rules or modifications to arbitration proceedings, the Parties will negotiate in good faith for replacement language. If replacement language cannot be agreed upon, either Party may seek regulatory intervention, including negotiations pursuant to Sections 251 and 252 of the Act. In all other respects, the provisions of this Agreement are not severable.

26.15 Nondisclosure

26.15.1 All information, including but not limited to specifications, microfilm, photocopies, magnetic disks, magnetic tapes, drawings, sketches, models, samples, tools, technical information, data, employee records, maps, financial reports, and market data, (i) furnished by one Party to the other Party dealing with end user specific, facility specific, or usage specific information, other than end user information communicated for the purpose of publication of directory database inclusion, or (ii) in written, graphic, electromagnetic, or other tangible form and marked at the time of delivery as "Confidential" or "Proprietary", or (iii) communicated and declared to the receiving Party at the time of delivery, or by written notice given to the receiving Party within ten (10) days after delivery, to be "Confidential" or "Proprietary" (collectively referred to as "Proprietary Information"), shall remain the property of the disclosing Party. A Party who receives Proprietary Information via an oral communication may request written confirmation that the material is Proprietary Information. A Party who delivers Proprietary Information via an oral communication may request written confirmation that the Party receiving the information understands that the material is Proprietary Information. USWC acknowledges that Pilgrim is a private company and the existence of an affiliated relationship between Pilgrim and each of its corporate affiliates is Proprietary Information.

26.15.2 Upon request by the disclosing Party, the receiving Party shall return all tangible copies of Proprietary Information, whether written, graphic or otherwise, except that the receiving Party may retain one copy for archival purposes.

- 26.15.3 Each Party shall keep all of the other Party's Proprietary Information confidential and shall use the other Party's Proprietary Information only in connection with this Agreement. Neither Party shall use the other Party's Proprietary Information for any other purpose except upon such terms and conditions as may be agreed upon between the Parties in writing.
- 26.15.4 Unless otherwise agreed, the obligations of confidentiality and non-use set forth in this Agreement do not apply to such Proprietary Information as:
- 26.15.4.1 was at the time of receipt already known to the receiving Party free of any obligation to keep it confidential evidenced by written records prepared prior to delivery by the disclosing Party; or
 - 26.15.4.2 is or becomes publicly known through no wrongful act of the receiving Party; or
 - 26.15.4.3 is rightfully received from a third person having no direct or indirect secrecy or confidentiality obligation to the disclosing Party with respect to such information; or
 - 26.15.4.4 is independently developed by an employee, agent, or contractor of the receiving Party which individual is not involved in any manner with the provision of services pursuant to the Agreement and does not have any direct or indirect access to the Proprietary Information; or
 - 26.15.4.5 is disclosed to a third person by the disclosing Party without similar restrictions on such third person's rights; or
 - 26.15.4.6 is approved for release by written authorization of the disclosing Party; or
 - 26.15.4.7 is required to be made public by the receiving Party pursuant to applicable law or regulation provided that the receiving Party shall give sufficient notice of the requirement to the disclosing Party to enable the disclosing Party to seek protective orders.
- 26.15.5 **Effective Date Of This Section.** Notwithstanding any other provision of this Agreement, the Proprietary Information provisions of this Agreement shall apply to all information furnished by either Party to the other in furtherance of the purpose of this Agreement, even if furnished before the date of this Agreement. The Parties shall not make public announcements, press releases or communicate to the media in any way the signing of this contract

without the express written permission of the other Party. This shall not be construed to restrict either Party's ability to convey such information in regulatory or legal proceedings.

26.16 Survival

The Parties' obligations under this Agreement which by their nature are intended to continue beyond the termination or expiration of this Agreement shall survive the termination or expiration of this Agreement.

26.17 Dispute Resolution

If any claim, controversy or dispute between the Parties, their agents, employees, officers, directors or affiliated agents related solely to and arising directly from a breach of this Agreement ("Dispute") cannot be settled through negotiation, it shall be resolved by arbitration conducted by a single arbitrator engaged in the practice of law, under the then current rules of the American Arbitration Association ("AAA"). The Federal Arbitration Act, 9 U.S.C. Secs. 1-16, not state law, shall govern the arbitrability of all Disputes. In all such proceedings each Party shall have reasonable discovery rights. The arbitrator shall not have authority to award punitive damages. All expedited procedures prescribed by the AAA rules shall apply. The arbitrator in his/her discretion may award the prevailing Party some or all of its reasonable attorneys' fees and costs; provided, however, that a Party shall not be considered a "prevailing Party" unless it obtains an award more favorable than that offered by the other Party in its last written offer made at least thirty (30) days prior to the beginning of the arbitration. The arbitrator's award shall be final and binding and may be entered in any court having jurisdiction thereof. The arbitration shall occur in the largest city, in the state of North Dakota, unless otherwise mutually agreed to by the Parties. Nothing in this Section shall be construed to waive or limit either Party's right to seek any relief from the Commission, or the Federal Communications Commission, or Federal Court (including equitable or injunctive relief), as provided by state or federal law.

No Dispute, regardless of the form of action, arising out of this Agreement, may be brought by either Party more than two (2) years after the cause of action accrues.

26.18 Controlling Law

This Agreement was negotiated by the Parties in accordance with the terms of the Act and the laws of the state where service is provided hereunder. It shall be interpreted solely in accordance with the terms of the Act and other applicable state and federal law.

26.19 Joint Work Product

This Agreement is the joint work product of the Parties and has been negotiated by the Parties and their respective counsel and shall be fairly interpreted in accordance with its terms and, in the event of any ambiguities, no inferences shall be drawn against either Party.

26.20 Responsibility for Environmental Contamination

Neither Party shall be liable to the other for any costs whatsoever resulting from the presence or release of any environmental hazard that either Party did not introduce to the affected work location. Both Parties shall defend and hold harmless the other, its officers, directors and employees from and against any losses, damages, claims, demands, suits, liabilities, fines, penalties and expenses (including reasonable attorneys' fees) that arise out of or result from (i) any environmental hazard that the indemnifying Party, its contractors or agents introduce to the work locations or (ii) the presence or release of any environmental hazard for which the indemnifying Party is responsible under applicable law.

26.21 Notices

Any notices required by or concerning this Agreement shall be sent to the Parties at the addresses shown below:

USWC

Director - Interconnection Compliance
1801 California Street, Suite 2410
Denver, CO 80202

With copy to:

U S WEST, Inc. Law Department
ATTN: General Counsel
1801 California Street, Suite 5100
Denver, CO 80202

Pilgrim

Mr. Stan Kugell - V.P.
One Kendall Square
Cambridge, Massachusetts 02139
Phone: 617-225-7000
FAX: 617-747-3573

With copy to:
Walter E. Steimel Jr. Esq.
Greenberg Traurig, L.L.P.
800 Connecticut Ave. N.W.
Suite 500
Washington, D.C. 20006

Each Party shall inform the other of any changes in the above addresses.

26.22 Responsibility of Each Party

Each Party is an independent contractor, and has and hereby retains the right to exercise full control of and supervision over its own performance of its obligations under this Agreement and retains full control over the employment, direction, compensation and discharge of all employees assisting in the performance of such obligations. Each Party will be solely responsible for all matters relating to payment of such employees, including compliance with social security taxes, withholding taxes and all other regulations governing such matters. Each Party will be solely responsible for proper handling, storage, transport and disposal at its own expense of all (i) substances or materials that it or its contractors or agents bring to, create or assume control over at work locations or, (ii) waste resulting therefrom or otherwise generated in connection with its or its contractors' or agents' activities at the work locations. Subject to the limitations on liability and except as otherwise provided in this Agreement, each Party shall be responsible for (i) its own acts and performance of all obligations imposed by applicable law in connection with its activities, legal status and property, real or personal and, (ii) the acts of its own affiliates, employees, agents and contractors during the performance of that Party's obligations hereunder.

26.23 No Third Party Beneficiaries

Except as may be specifically set forth in this Agreement, this Agreement does not provide and shall not be construed to provide third parties with any remedy, claim, liability, reimbursement, cause of action, or other privilege.

26.24 Referenced Documents

All references to Sections or Appendices shall be deemed to be references to Sections of, and Appendices to, this Agreement unless the context shall otherwise require. Whenever any provision of this Agreement refers to a technical reference, technical publication, Pilgrim practice, USWC practice, any publication of telecommunications industry administrative or technical standards, or any other document specifically incorporated into this Agreement, it will be deemed to be a reference to the most recent version or edition (including any amendments, supplements, addenda, or successors) of such document that is in effect, and will include the most recent version or edition (including any

amendments, supplements, addenda, or successors) of each document incorporated by reference in such a technical reference, technical publication, Pilgrim practice, USWC practice, or publication of industry standards (unless Pilgrim elects otherwise). Should there be any inconsistency between or among publications or standards, Pilgrim shall elect which requirement shall apply.

26.25 Publicity and Advertising

Neither Party shall publish or use any advertising, sales promotions or other publicity materials that use the other Party's logo, trademarks or service marks without the prior written approval of the other Party.

26.26 Amendment

Pilgrim and USWC may mutually agree to amend this Agreement in writing. Since it is possible that amendments to this Agreement may be needed to fully satisfy the purposes and objectives of this Agreement, the Parties agree to work cooperatively, promptly and in good faith to negotiate and implement any such additions, changes and corrections to this Agreement.

26.27 Executed in Counterparts

This Agreement may be executed in any number of counterparts, each of which shall be deemed an original; but such counterparts shall together constitute one and the same instrument.

26.28 Headings of No Force or Effect

The headings of Sections of this Agreement are for convenience of reference only, and shall in no way define, modify or restrict the meaning or interpretation of the terms or provisions of this Agreement.

26.29 Cancellation Charges

Except as provided pursuant to a Network Element, Bona Fide Request, or as otherwise provided in any applicable Tariff or contract referenced herein, no cancellation charges shall apply.

26.30 Regulatory Approval

The Parties understand and agree that this Agreement will be filed with the Commission and may thereafter be filed with the FCC and shall, at all times, be subject to review by the Commission or the FCC. In the event any such review rejects any portion of this Agreement, renders it inoperable or creates any ambiguity of requirement for further amendment, the Parties agree to meet and negotiate in good faith to arrive at a mutually acceptable modification.

26.31 Compliance

Each Party shall comply with all applicable federal, state, and local laws, rules and regulations applicable to its performance under this Agreement.

26.32 Compliance with the Communications Law Enforcement Act of 1994 ("CALEA")

In the provision of POTS services, each Party represents and warrants that any equipment, facilities or services provided to the other Party under this Agreement comply with CALEA. Each Party shall indemnify and hold the other Party harmless from any and all penalties imposed upon the other Party for such noncompliance and shall at the non-compliant Party's sole cost and expense, modify or replace any equipment, facilities or services provided to the other Party under this Agreement to ensure that such equipment, facilities and services fully comply with CALEA.

26.33 Cooperation

The Parties agree that this Agreement involves the provision of USWC services in ways such services were not previously available and the introduction of new processes and procedures to provide and bill such services. Accordingly, the Parties agree to work jointly and cooperatively in testing and implementing processes for pre-ordering, ordering, maintenance, provisioning and billing and in reasonably resolving issues which result from such implementation on a timely basis.

26.34 Entire Agreement

This Agreement constitutes the entire agreement between the Parties and supersedes all prior oral or written agreements, representations, statements, negotiations, understandings, proposals and undertakings with respect to the subject matter hereof.

IN WITNESS WHEREOF, the Parties hereto have caused this Agreement, for services in the state of North Dakota, to be executed by their respective duly authorized representatives.

Pilgrim Telephone, Inc

U S WEST Communications, Inc.




Signature



Signature




Name Printed/Typed




Name Printed/Typed




Title



Title



Date



Date

* This Agreement is made pursuant to Section 252 (i) of the Act and is premised upon the Interconnection Agreement between New Edge Network, Inc. dba New Edge Networks and U S WEST Communications, Inc. (the "Underlying Agreement"). The Underlying Agreement was approved by the Commission on January 26, 2000.

With respect to this Agreement, the Parties understand and agree:

i) The Parties shall request the Commission to expedite its review and approval of this Agreement.

ii) Notwithstanding the mutual commitments set forth herein, the Parties are entering into this Agreement without prejudice to any positions they have taken previously, or may take in the future, in any legislative, regulatory, or other public forum addressing any matters, including those relating to the types of arrangements contained in this Agreement.

iii) This Agreement contains provisions based upon the decisions and orders of the FCC and the Commission under and with respect to the Act. Currently, court and regulatory proceedings affecting the subject matter of this Agreement are in various stages, including the proceedings where certain of the rules and regulations of the FCC are being challenged. In addition, there is uncertainty in the aftermath of the Supreme Court's decision in AT&T Corp. et al. v. Iowa Utilities Board. Based on that uncertainty, and the regulatory and judicial proceedings which will occur as a result of that decision, the Parties acknowledge that this Agreement may need to be changed to reflect any changes in law. The Agreement has not been corrected to reflect the requirements, claims or outcomes of any of the Proceedings, although the pricing does reflect the Commission's most current generic order, if any. Accordingly, when a final, decision or decisions are made in the Proceedings that automatically change and modify the Underlying Agreement, then like changes and modifications will similarly be made to this Agreement. In addition, to the extent rules or laws are based on regulatory or judicial proceedings as a result of the recent Supreme Court decision, this Agreement will be amended to incorporate such changes.

iv) Subsequent to the execution of this Agreement, the FCC or the Commission may issue decisions or orders that change or modify the rules and regulations governing implementing of the Act. If such changes or modifications alter the state of the law upon which the Underlying Agreement was negotiated and agreed, and it reasonably appears that the parties to the Underlying Agreement would have negotiated and agreed to different term(s) condition(s) or covenant(s) than as contained in the Underlying Agreement had such change or modification been in existence before execution of the Underlying Agreement, then this Agreement shall be amended to reflect such different terms(s), condition(s), or covenant(s). Where the parties fail to agree upon such an amendment, it shall be resolved in accordance with the Dispute Resolution provision of this Agreement.

v) This Agreement shall continue in force and effect until terminated by either Party. The Agreement can be terminated on thirty (30) days notice, if another Interconnection Agreement will not replace the current Agreement. If there is a replacement Interconnection Agreement, one Party can notify the other Party that it is requesting Section 251/252 negotiations under the Federal Telecommunications Act of 1996 ("Act"). That notification will trigger the timeframes and procedures contained in Section 252 of the Act. In the event of such notice, the arrangements between our companies shall continue and be governed by the terms of the expired agreement until the new agreement is approved by the appropriate state commission.

**NORTH DAKOTA
APPENDIX A
Rates and Charges**

The rates contained in this Appendix A are interim in nature and are subject to revision upon the Commission's approval of rates contained in USWC's cost docket. Such Commission approved rates shall be incorporated into this Appendix A. Any additional rates not included in this Appendix A and included in the cost docket, such as non-recurring charges, shall also be incorporated into this Appendix A.

In the event that the text of this Agreement references a rate (or rate element) that is not contained in this Appendix A and Pilgrim wishes to obtain such element from USWC, USWC will provide the applicable rate upon request by Pilgrim.

INTERCONNECTION - LOCAL EXCHANGE		
	Price Recurring	Price Nonrecurring
Entrance Facility (EF2)		
DS1, Electrical	\$102.22	\$513.56
DS3, Electrical	\$403.34	\$609.20
Call Termination	Price	
Per Minute of Use (Note 1)	\$0.002500	
Call Transport	Price	
Direct Trunked Transport		
per DS0 Equivalent per month (Note 1)	\$4.12	
Tandem-Switched Transport	Price	
Tandem Switching, Per Minute of Use (Note 1)	\$0.008400	
Common Transport, per MOU per leg (Note 1)	\$0.000690	
Multiplexing, per arrangement	Recurring	Nonrecurring
DS3 to DS1	\$236.79	\$286.18

INTERCONNECTION - EXCHANGE ACCESS	
--	--

Call Termination	Per Switched Access Tariff
Call Transport	Per Switched Access Tariff
Call Transit	Per Switched Access Tariff

COMMON CHANNEL SIGNALING ACCESS SERVICE

<i>Entrance Facility (EF2)</i>	Recurring	Nonrecurring
DS1, Electrical	\$102.22	\$513.56
DS3, Electrical	\$403.34	\$609.20
	Recurring	Nonrecurring
<i>CCS Link -- First Link</i>	\$192.83	\$459.60
<i>CCS Link -- Each additional Link</i>	\$192.83	\$65.94
	Price	
<i>STP Port -- Per Message</i>	\$0.000240	
<i>SCP/Databases - Per Message</i>	\$0.001020	
	Recurring	Nonrecurring
<i>Multiplexing</i>		
DS1 to DS0	\$225.18	\$279.55
DS3 to DS1	\$236.79	\$286.18

PHYSICAL, VIRTUAL AND COMMON COLLOCATION

per FCC Tariff No. 5, USWC Access Svc, Section 21,

	Recurring	Nonrecurring
<i>Pilgrim Typical Cageless Collocation</i>		
2 Bay Configuration	\$700.00	\$18,000.00
4 Bay Configuration	\$770.00	\$27,656.00
6 Bay Configuration	\$1,390.00	\$45,656.00
<i>SPOT Frame Terminations</i>		
DS0, per termination	\$0.01	\$5.01
DS1, per termination	\$0.02	\$11.87
DS3, per termination	\$0.32	\$179.92
<i>SPOT Frame, Block Terminations</i>		
DS0, per 100 terminations	\$1.30	\$598.07
DS1, per 28 terminations	\$0.78	\$435.77
DS3, per each termination	\$0.43	\$241.99
<i>Cable Racking</i>		ICB
<i>HVAC</i>		ICB

Common Collocation

The Physical Collocation rates shall apply, without the Cage Enclosure or Grounding rates.

ANCILLARY SERVICES	Price
Directory Assistance	
Price per Call -- Facilities-Based Providers	\$0.34
Listings	
Primary Listings, Directory Assistance, White & Yellow Pages	No Charge
E911	
LEC and AECs recover costs from PSAP	No Charge
Assignment of Numbers	
Assignments per industry guidelines	No Charge
Busy Line Verification	
Per Call	\$0.72
Busy Line Interrupt	
Per Call	\$0.87

UNBUNDLED ELEMENTS	Recurring	Nonrecurrin
Unbundled Loops		
2-Wire LIS-Link, Statewide	\$19.75	
Basic rate ISDN capable Loop	\$19.75	
DS1 capable Loop	\$102.22	
Regeneration		
DS1	\$6.30	
DS3	\$41.32	
ISDN Extension Increment, Per Loop (Note 2)	\$22.67	
First DS1 Loop		\$513.56
Basic Installation, First LIS-Link		\$105.79
Basic Installation, Each Additional LIS-Link		\$58.20
Installation with Conformance Testing, First LIS-Link		\$170.04
Installation with Conformance Testing, Each Additional LIS-Link		\$86.24
Coordinated Installation with Testing, First LIS-Link		\$217.05
Coordinated Installation with Testing, Each Additional LIS-Link		\$133.23
Network Interface Device (Note 3)		\$58.32
Cable Unloading and Bridge Tap Removal (Note 4)		\$538.16

Unbundled Ports	Recurring	Nonrecurring
End Office Port, Per First Port	\$1.27	\$97.97
End Office Port, Per Each Additional Port	\$1.27	\$52.71
Per Minute of Use, Per Port	\$0.002500	

RESALE RATES

Wholesale Rates	Percent of Retail Rate
Residence Basic	83.15%
Centrex Plus	83.15%
Operator Services & Directory Assistance	83.15%
Private Line Transport	83.15%
Business Basic	83.15%
PBX Trunks	83.15%
Frame Relay	83.15%
ISDN	83.15%
Listings	83.15%
Features	83.15%
IntraLATA Toll	83.15%
WATS	83.15%
Volume Packaged Services	91.85%

Customer Transfer Charge (Mechanized or Manual)

	Price
Residence, First Line	\$5.00
Residence, Each Additional Line	\$5.00
Business, First Line	\$5.00
Business, Each Additional Line	\$5.00

Notes

- 1 "Bill and Keep" for one year
- 2 This charge applies when a CLEC requests ISDN capability on an unbundled loop greater than 18kft.
- 3 This charge applies when USWC must install or expand a Network Interface Device for a CLEC or when USWC must connect a CLEC's loop to the USWC Network Interface Device (per Decision, page 24).
- 4 This charge applies only when loop unloading is necessary.

PU-2451-00-630

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Stan Kugell
 Pilgrim Telephone Inc
 1 Kendall Sq
 Cambridge MA 02139

2. Article Number (Copy from service label)

7000 0520 0022 8654 0322

PS Form 3811, July 1999

Domestic Return Receipt

102595-99-M-1789

COMPLETE THIS SECTION ON DELIVERY

A. Received by (Please Print Clearly) B. Date of Delivery

Kristy Sauer 2/5/01

C. Signature

X Kristy Sauer Agent Addressee

D. Is delivery address different from item 1? Yes
If YES, enter delivery address below: No

3. Service Type

- Certified Mail Express Mail
- Registered Return Receipt for Merchandise
- Insured Mail C.O.D.

4. Restricted Delivery? (Extra Fee) Yes

PU-2451-00-630

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Stan Kugell
 Pilgrim Telephone Inc
 1 Kendall Square
 Cambridge MA 02139

2. Article Number (Copy from service label)

7099 3400 0014 4513 6262

PS Form 3811, July 1999

Domestic Return Receipt

102595-99-M-1789

COMPLETE THIS SECTION ON DELIVERY

A. Received by (Please Print Clearly) B. Date of Delivery

Judy Griffin 12-11-00

C. Signature

X Judy Griffin Agent Addressee

D. Is delivery address different from item 1? Yes
If YES, enter delivery address below: No

3. Service Type

- Certified Mail Express Mail
- Registered Return Receipt for Merchandise
- Insured Mail C.O.D.

4. Restricted Delivery? (Extra Fee) Yes

PU-618, 619, 620, 624, 627, 628, 629, 630

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

John Munn
 Quest Corporation
 1801 California St Rm 5100
 Denver Co 80202

2. Article Number (Copy from service label)

COMPLETE THIS SECTION ON DELIVERY

A. Received by (Please Print Clearly) B. Date of Delivery

R Hunt DEC 11 2000

C. Signature

X R Hunt Agent Addressee

D. Is delivery address different from item 1? Yes
If YES, enter delivery address below: No

3. Service Type

- Certified Mail Express Mail
- Registered Return Receipt for Merchandise
- Insured Mail C.O.D.

4. Restricted Delivery? (Extra Fee) Yes