


- Setbacks provided by NextEra Energy Resources, LLC and are as follows:
- 1) Minimum distance of 1400' from the closet corner of a occupied structure (house, mobile home, manufactured home)
 - 2) Minimum distance of 440' from a non-participating landowner
 - 3) Minimum distance of 440' from any and all overhead power lines
 - 4) Minimum distance of 440' from the nearest edge of road
 - 5) Minimum distance between turbines needs to be 866.14' or 3.2 rotor diameters
 - 6) 500' from a 50 plus acres wetland
 - 7) No wind turbine placed within 0.25 mile of any USFWS WPA.



Luverne South Field Wind Farm

Griggs & Steele County, North Dakota

Date: 5/20/09

Overall Setback Map