

Exam Date: 09/02/2008

Barlow Grain
 260 Elevator Road
 Carrington, ND
 County:
 Phone: 701-984-2617
 CCC Number:

Page: 1

Examiner: 1

Location/Container Numbers/Comments	Section	Capacity
PART A - ADDITIONAL SPACE TO BE INCLUDED UNDER LICENSE		
108	A	111,064
006	F <i>Leased site Tank added 09-02-08</i>	21,914
H-3	A	3,933
H-4	A	3,933
300	K <i>Bremen add - 09-02-08</i>	44,296
		Total: 185,140

PART B - SPACE TO BE DELETED UNDER LICENSE		
106	E	34,914
107	E	34,914
001	F	38,982
002	F	38,982
H-1	A	3,933
H-2	A	3,933
		Total: 155,658

PART C - ALL SPACE TO BE INCLUDED UNDER LICENSE		
	A	910,000
	B	43,000
	C	43,000
	D	43,000
	F	22,000
	K	255,000
	L	190,000
		Total: 1,506,000

PART D - TOTAL CAPACITY BY FUNCTIONAL UNIT			
Barlow	44	A B C D F	1,061,000
Bremen	1183	K L	445,000
			Total: 1,506,000

Client ID: 661

NDPSC Bin Capacity Chart

09/02/2008 10:38:40 AM

Exam Date:09/02/2008
Examiner: 1

Barlow Grain
260 Elevator Road
Carrington , ND
County:

Page: 1

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak Capac.	Depth for	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	---------------------	-----------	------------------	------------	---------------------------

Facility: Barlow

Section: A

A		002 T	Square	floor over bins	0.000	6.300	4.700	15.20	0.00	0.00	15.200	0.000	15.2	23.8	2.00	369
A		002 B	Square	floor over bins-top 15.2'	0.000	5.900	4.300	32.80	0.00	0.00	32.800	0.000	32.8	20.4	2.00	682
A		004 T	Square	bin floor	0.000	6.400	5.000	15.20	0.00	0.00	15.200	0.000	15.2	25.7	2.50	401
A		004 B	Square	bin floor - top 15.2'	0.000	5.900	4.600	32.80	0.00	0.00	32.800	0.000	32.8	21.8	2.00	729
A		005 T	Square	bin floor	0.000	7.000	4.600	18.40	0.00	0.00	18.400	0.000	18.4	25.9	2.50	489
A		005 B	Square	bin floor -top 18.4'	0.000	9.000	6.800	29.60	0.00	0.00	29.600	0.000	29.6	49.2	4.20	1,517
A		006 T	Square	bin floor	0.000	6.300	5.500	15.20	0.00	0.00	15.200	0.000	15.2	27.9	2.50	435
A		006 B	Square	bin floor - top 15.2'	0.000	5.900	5.100	16.80	0.00	0.00	16.800	0.000	16.8	24.2	2.50	417
A		007 T	Square	bin floor	0.000	12.20	6.400	15.20	0.00	0.00	15.200	0.000	15.2	62.8	5.00	1,003
A		007 B	Square	bin floor - top 15.2'	0.000	12.00	6.000	32.80	0.00	0.00	32.800	0.000	32.8	57.9	4.80	1,990
A		008 T	Square	bin floor	0.000	12.20	6.400	15.20	0.00	0.00	15.200	0.000	15.2	62.8	5.00	1,003
A		008 B	Square	bin floor - top 15.2'	0.000	12.00	6.000	32.80	0.00	0.00	32.800	0.000	32.8	57.9	4.80	1,990
A		009 T	Square	bin floor	0.000	12.90	9.500	15.20	0.00	0.00	15.200	0.000	15.2	98.5	6.00	1,587
A		009 M	Square	bin floor -top 15.2'	0.000	12.60	9.000	36.30	0.00	0.00	36.300	0.000	36.3	91.2	5.80	3,503
A		009B	Square	bin floor -top & middle 51.5'	0.000	12.30	8.800	14.00	0.00	0.00	14.000	0.000	14.0	87.0	5.80	1,289
A		010 T	Square	bin floor	0.000	6.400	4.700	15.20	0.00	0.00	15.200	0.000	15.2	24.2	2.50	377
A		010 B	Square	bin floor-top 15.2'	0.000	6.000	4.300	32.80	0.00	0.00	32.800	0.000	32.8	20.7	2.00	693
A		011 T	Square	bin floor	0.000	12.90	9.500	15.20	0.00	0.00	15.200	0.000	15.2	98.5	6.00	1,587
A		011 M	Square	bin floor - top 15.2'	0.000	12.60	9.000	36.30	0.00	0.00	36.300	0.000	36.3	91.2	5.80	3,503
A		011B	Square	bin floor-top&mdl 51.5'	0.000	12.30	8.800	14.00	0.00	0.00	14.000	0.000	14.0	87.0	5.80	1,289
A		012 T	Square	bin floor	0.000	6.300	5.000	15.20	0.00	0.00	15.200	0.000	15.2	25.3	2.50	395

Exam Date:09/02/2008
 Examiner: 1

Barlow Grain
 260 Elevator Road
 Carrington, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Facility: Barlow

Section: A

A	012 B	Square	bin floor - top 15.2'	0.000	5.900	4.600	33.80	0.00	0.00	33.800	0.000	33.8	21.8	2.00	752
A	013 T	Square	bin floor	0.000	12.20	6.400	15.20	0.00	0.00	15.200	0.000	15.2	62.8	5.00	1,003
A	013 B	Square	bin floor - top 15.2'	0.000	12.00	6.000	32.80	0.00	0.00	32.800	0.000	32.8	57.9	4.80	1,990
A	014L1	Square	bin floor	0.000	6.400	5.500	15.20	0.00	0.00	15.200	0.000	15.2	28.3	2.50	441
A	014L2	Square	bin floor-top 15.2'	0.000	6.100	5.100	16.80	0.00	0.00	16.800	0.000	16.8	25.0	2.50	431
A	014L3	Square	bin floor-32' above	0.000	12.60	5.100	16.00	0.00	0.00	16.000	0.000	16.0	51.7	4.50	864
A	014L4	Square	bin floor - 48' above	0.000	12.60	10.10	3.500	0.00	0.00	3.500	0.000	3.5	102.3	6.00	379
A	014L5	Square	bin floor L1-2-3-4 = 51.5'	0.000	12.30	9.800	14.00	0.00	0.00	14.000	0.000	14.0	96.9	6.00	1,438
A	015 T	Square	bin floor	0.000	12.20	6.400	15.20	0.00	0.00	15.200	0.000	15.2	62.8	5.00	1,003
A	015 B	Square	bin floor - top 15.2'	0.000	12.00	6.000	32.80	0.00	0.00	32.800	0.000	32.8	57.9	4.80	1,990
A	016 T	Square	bin floor	0.000	12.90	5.000	15.20	0.00	0.00	15.200	0.000	15.2	51.8	4.50	822
A	016 M	Square	bin floor - top 15.2'	0.000	12.60	4.600	36.30	0.00	0.00	36.300	0.000	36.3	46.6	4.00	1,760
A	016B	Square	bin floor 51.5' above	0.000	12.30	9.800	14.00	0.00	0.00	14.000	0.000	14.0	96.9	6.00	1,438
A	017 T	Square	bin floor	0.000	12.20	7.000	15.20	0.00	0.00	15.200	0.000	15.2	68.6	5.20	1,097
A	017 B	Square	bin floor - top 15.2'	0.000	12.00	6.800	32.80	0.00	0.00	32.800	0.000	32.8	65.6	5.00	2,260
A	018 T	Square	bin floor	0.000	10.50	3.700	15.20	0.00	0.00	15.200	0.000	15.2	31.2	2.50	486
A	018 B	Square	bin floor-top 15.2'	0.000	10.20	3.400	32.80	0.00	0.00	32.800	0.000	32.8	27.9	2.50	938
A	019 T	Square	bin floor	0.000	9.500	7.000	18.40	0.00	0.00	18.400	0.000	18.4	53.5	4.50	1,028
A	019 B	Square	bin floor-top 18.4'	0.000	9.000	6.800	29.60	0.00	0.00	29.600	0.000	29.6	49.2	4.20	1,517
A	020 T	Square	bin floor	0.000	12.20	7.000	15.20	0.00	0.00	15.200	0.000	15.2	68.6	5.20	1,097
A	020 B	Square	bin floor-top 15.2'	0.000	12.00	6.800	32.80	0.00	0.00	32.800	0.000	32.8	65.6	5.00	2,260

Exam Date:09/02/2008

Barlow Grain

Page: 3

Examiner: 1

260 Elevator Road
Carrington, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Det. for Obst.	Effective Depth	Add for Peak Capac.	Depth	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	-------------------------------	--------	-------	--------------	----------------------	----------------------	--------------------	------------------------------	-------	------------------------	---------------	------------------------------

Facility: Barlow

Section: A

A		021 T	Square	bin floor	0.000	16.00	13.20	14.50	0.00	0.00	14.500	0.000	14.5	169.8	7.00	2,634
A		021 M	Square	bin floor - top 14.5'	0.000	15.70	13.00	45.00	0.00	0.00	45.000	0.000	45.0	164.1	7.00	7,902
A		021 B	Square	bin floor 59.5' above	0.000	13.30	12.80	7.400	0.00	0.00	7.400	0.000	7.4	136.8	6.50	1,078
A		022 T	Square	bin floor	0.000	16.00	11.80	14.50	0.00	0.00	14.500	0.000	14.5	151.8	6.80	2,351
A		022 M	Square	bin floor - top 14.5'	0.000	15.70	11.60	45.00	0.00	0.00	45.000	0.000	45.0	146.4	6.80	7,036
A		022 B	Square	bin floor 59.5' above	0.000	13.30	11.40	7.400	0.00	0.00	7.400	0.000	7.4	121.9	6.50	961
A		023 T	Square	bin floor	0.000	16.00	13.20	14.50	0.00	0.00	14.500	0.000	14.5	169.8	7.00	2,634
A		023 M	Square	bin floor - top 14.5'	0.000	15.70	13.00	45.00	0.00	0.00	45.000	0.000	45.0	164.1	7.00	7,902
A		023 B	Square	bin floor 59.5' above	0.000	13.30	12.80	7.400	0.00	0.00	7.400	0.000	7.4	136.8	6.50	1,078
A		024 T	Square	bin floor	0.000	16.00	11.80	14.50	0.00	0.00	14.500	0.000	14.5	151.8	6.80	2,351
A		024 M	Square	bin floor - top 14.5'	0.000	15.70	11.60	45.00	0.00	0.00	45.000	0.000	45.0	146.4	6.80	7,036
A		024 B	Square	bin floor 59.5' above	0.000	13.30	11.40	7.400	0.00	0.00	7.400	0.000	7.4	121.9	6.50	961
A		025 T	Square	bin floor	0.000	16.00	11.80	14.50	0.00	0.00	14.500	0.000	14.5	151.8	6.80	2,351
A		025 M	Square	bin floor - top 14.5'	0.000	15.70	11.60	45.00	0.00	0.00	45.000	0.000	45.0	146.4	6.80	7,036
A		025 B	Square	bin floor 59.5' above	0.000	13.30	11.40	7.400	0.00	0.00	7.400	0.000	7.4	121.9	6.50	961
A		026 T	Square	bin floor	0.000	16.00	11.60	14.50	0.00	0.00	14.500	0.000	14.5	149.2	6.80	2,310
A		026 M	Square	bin floor - top 14.5'	0.000	15.70	11.40	45.00	0.00	0.00	45.000	0.000	45.0	143.9	6.80	6,916
A		026 B	Square	bin floor 59.5' above	0.000	13.30	11.20	7.400	0.00	0.00	7.400	0.000	7.4	119.7	6.20	941
A		027 T	Square	bin floor	0.000	16.00	11.80	14.50	0.00	0.00	14.500	0.000	14.5	151.8	6.80	2,351
A		027 M	Square	bin floor - top 14.5'	0.000	15.70	11.60	45.00	0.00	0.00	45.000	0.000	45.0	146.4	6.80	7,036
A		027 B	Square	bin floor 59.5' above	0.000	13.30	11.40	7.400	0.00	0.00	7.400	0.000	7.4	121.9	6.50	961

Exam Date: 09/02/2008

Barlow Grain

Page: 4

Examiner: 1

260 Elevator Road
Carrington, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	-------------------------------	--------	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: Barlow

Section: A

A		028 T	Square	bin floor	0.000	16.00	11.60	14.50	0.00	0.00	14.500	0.000	14.5	149.2	6.80	2,310
A		028 M	Square	bin floor - top 14.5'	0.000	15.70	11.40	45.00	0.00	0.00	45.000	0.000	45.0	143.9	6.80	6,916
A		028B	Square	bin floor 59.5' above	0.000	13.30	11.20	7.400	0.00	0.00	7.400	0.000	7.4	119.7	6.20	941
A		101	Peaked	eave at side wall	29.900	0.000	0.000	57.00	0.00	0.00	57.000	1.800	58.8	564.4	9.00	36,174
A		102	Peaked	eave at side wall	29.900	0.000	0.000	57.00	0.00	0.00	57.000	1.800	58.8	564.4	9.00	36,174
A		103	Peaked	eave at side wall	48.000	0.000	0.000	58.70	0.00	0.00	58.700	3.400	62.1	1454.6	10.0	99,364
A		104	Peaked	eave at side wall	47.800	0.000	0.000	73.30	0.00	0.00	73.300	2.900	76.2	1442.5	10.0	120,911
A		105	Peaked	eave at side wall	47.800	0.000	0.000	73.30	0.00	0.00	73.300	2.900	76.2	1442.5	10.0	120,911
A		106	Peaked	eave at side wall	47.800	0.000	0.000	73.30	0.00	0.00	73.300	2.900	76.2	1442.5	10.0	120,911
A		107	Peaked	eave at side wall	47.800	0.000	0.000	73.30	0.00	0.00	73.300	2.900	76.2	1442.5	10.0	120,911
Added	A	108	Peaked	eave at side wall	47.900	0.000	0.000	66.75	0.00	0.00	66.750	2.900	69.7	1448.6	10.0	111,064
Added	A	H-3	Peaked	eave at side wall	16.000	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	161.6	5.80	3,933
Added	A	H-4	Peaked	eave at side wall	16.000	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	161.6	5.80	3,933

Bin count: 76 Facility: Barlow Section: A Total: 909,482

To Even: 910,000

Section: B

B		001	Quonset	consult diagram	0.000	40.00	100.0	12.00	0.00	0.00	12.000	0.000	12.0	3184.2	10.0	42,032
---	--	-----	---------	-----------------	-------	-------	-------	-------	------	------	--------	-------	------	--------	------	--------

Bin count: 1 Facility: Barlow Section: B Total: 42,032

To Even: 43,000

Exam Date:09/02/2008

Examiner: 1

Barlow Grain
260 Elevator Road
Carrington , ND
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obs.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	---------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Facility: Barlow

Section: C

C	001		Quonset	consult diagram	0.000	40.00	100.0	12.00	0.00	0.00	12.000	0.000	12.0	3184.2	10.0	42,032
Bin count: 1																
Facility: Barlow Section: C Total: <u>42,032</u>																
To Even: <u>43,000</u>																

Section: D

D	001		Quonset	consult diagram	0.000	40.00	100.0	12.00	0.00	0.00	12.000	0.000	12.0	3184.2	10.0	42,032
Bin count: 1																
Facility: Barlow Section: D Total: <u>42,032</u>																
To Even: <u>43,000</u>																

Section: F

Added	F	006	Peaked	eave at side wall -Leased	35.600	0.000	0.000	22.80	0.00	0.00	22.800	2.100	24.9	800.1	10.0	21,914
Bin count: 1																
Facility: Barlow Section: F Total: <u>21,914</u>																
To Even: <u>22,000</u>																

Exam Date:09/02/2008

Barlow Grain

Page: 6

Examiner: 1

260 Elevator Road
Carrington , ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg)		Side for Hopper	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak Capac.	Depth for	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width									

Facility: Bremen

Section: K

K		001 T	Square	floor over bins	0.000	5.100	3.900	25.00	0.00	0.00	25.000	0.000	25.0	16.0	2.00	408
K		001 B	Square	floor over bins top 25'	0.000	10.50	3.900	28.00	0.00	0.00	28.000	0.000	28.0	32.9	2.50	944
K		002	Square	floor over bins	0.000	5.600	3.900	25.00	0.00	0.00	25.000	0.000	25.0	17.6	2.00	449
K		003	Square	floor over bins	0.000	6.400	5.600	52.00	0.00	0.00	52.000	0.000	52.0	28.8	2.50	1,535
K		004	Square	floor over bins	0.000	6.100	5.600	53.00	0.00	0.00	53.000	0.000	53.0	27.5	2.50	1,494
K		005 T	Square	floor over bins	0.000	12.50	5.100	52.00	0.00	0.00	52.000	0.000	52.0	51.2	4.50	2,782
K		005 B	Square	floor over bins top 52'	0.000	12.40	10.50	18.00	0.00	0.00	18.000	0.000	18.0	104.7	6.00	1,998
K		006	Square	floor over bins	0.000	13.50	6.100	53.00	0.00	0.00	53.000	0.000	53.0	66.2	5.00	3,684
K		007	Square	floor over bins	0.000	6.800	6.500	54.00	0.00	0.00	54.000	0.000	54.0	35.5	3.00	1,975
K		009	Square	floor over bins	0.000	13.50	6.400	53.00	0.00	0.00	53.000	0.000	53.0	69.5	5.20	3,876
K		010 T	Square	floor over bins	0.000	10.50	6.100	52.00	0.00	0.00	52.000	0.000	52.0	51.5	4.50	2,799
K		010 B	Square	floor over bins top 52'	0.000	12.40	10.50	18.00	0.00	0.00	18.000	0.000	18.0	104.7	6.00	1,998
K		011	Square	floor over bins	0.000	6.500	6.500	54.00	0.00	0.00	54.000	0.000	54.0	34.0	2.50	1,882
K		012	Square	floor over bins	0.000	10.50	6.400	52.00	0.00	0.00	52.000	0.000	52.0	54.0	4.50	2,934
K		013	Square	floor over bins	0.000	10.50	6.500	53.50	0.00	0.00	53.500	0.000	53.5	54.9	4.50	3,069
K		015	Square	floor over bins	0.000	10.50	6.500	53.00	0.00	0.00	53.000	0.000	53.0	54.9	4.50	3,041
K		017	Square	floor over bins	0.000	10.50	6.400	52.00	0.00	0.00	52.000	0.000	52.0	54.0	4.50	2,934
K		018 T	Irregular	floor over bins 6.5 x 6.5	21.100	0.000	0.000	9.000	0.00	0.00	9.000	0.000	9.0	21.1	2.00	194
K		018 B	Square	floor over bins top 9'	0.000	6.500	6.500	45.00	0.00	0.00	45.000	0.000	45.0	34.0	2.50	1,568
K		019 T	Square	floor over bins	0.000	10.50	6.400	52.00	0.00	0.00	52.000	0.000	52.0	54.0	4.50	2,934
K		019 B	Square	floor over bins top 52'	0.000	12.40	10.50	17.00	0.00	0.00	17.000	0.000	17.0	104.7	6.00	1,887

Exam Date:09/02/2008

Barlow Grain
260 Elevator Road
Carrington, ND

Page: 7

Examiner: 1

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Facility: Bremen

Section: K

K	021	Square	floor over bins		0.000	13.50	6.400	52.50	0.00	0.00	52.500	0.000	52.5	69.5	5.20	3,839
K	022	Square	floor over bins		0.000	6.800	6.500	54.00	0.00	0.00	54.000	0.000	54.0	35.5	3.00	1,975
K	023	Square	floor over bins		0.000	13.50	6.400	53.00	0.00	0.00	53.000	0.000	53.0	69.5	5.20	3,876
K	024 T	Square	floor over bins		0.000	12.80	5.500	52.00	0.00	0.00	52.000	0.000	52.0	56.6	4.80	3,084
K	024 B	Square	floor over bins top 52'		0.000	12.40	10.50	16.00	0.00	0.00	16.000	0.000	16.0	104.7	6.00	1,776
K	025	Square	floor over bins		0.000	5.500	3.900	53.00	0.00	0.00	53.000	0.000	53.0	17.2	2.00	930
K	026	Square	floor over bins		0.000	6.400	5.100	52.00	0.00	0.00	52.000	0.000	52.0	26.2	2.50	1,396
K	027	Square	floor over bins		0.000	6.400	5.100	52.00	0.00	0.00	52.000	0.000	52.0	26.2	2.50	1,396
K	101	Square	floor over bins		0.000	9.500	7.600	45.50	0.00	0.00	45.500	0.000	45.5	58.0	4.80	2,766
K	102	Square	floor over bins		0.000	9.500	7.700	45.50	0.00	0.00	45.500	0.000	45.5	58.8	4.80	2,803
K	103 A	Square	floor over bins		0.000	10.30	6.000	32.00	0.00	0.00	32.000	0.000	32.0	49.7	4.20	1,657
K	103 T	Square	floor over bins		0.000	10.30	3.000	32.00	0.00	0.00	32.000	0.000	32.0	24.8	2.50	814
K	103 B	Square	floor over bins top 32'		0.000	10.30	9.500	13.50	0.00	0.00	13.500	0.000	13.5	78.7	5.50	1,120
K	104	Square	floor over bins		0.000	9.500	7.600	34.00	0.00	0.00	34.000	0.000	34.0	58.0	4.80	2,067
K	105	Square	floor over bins		0.000	9.500	7.700	44.00	0.00	0.00	44.000	0.000	44.0	58.8	4.80	2,711
K	106 A	Square	floor over bins		0.000	10.30	6.000	32.00	0.00	0.00	32.000	0.000	32.0	49.7	4.20	1,657
K	106 T	Square	floor over bins		0.000	10.30	3.000	32.00	0.00	0.00	32.000	0.000	32.0	24.8	2.50	814
K	106 B	Square	floor over bins top 32'		0.000	10.30	9.500	13.50	0.00	0.00	13.500	0.000	13.5	78.7	5.50	1,120
K	107	Square	floor over bins		0.000	11.20	7.600	35.50	0.00	0.00	35.500	0.000	35.5	68.4	5.20	2,554
K	108	Square	floor over bins		0.000	11.20	7.700	32.00	0.00	0.00	32.000	0.000	32.0	69.3	5.20	2,333
K	109	Square	floor over bins		0.000	10.30	5.400	28.00	0.00	0.00	28.000	0.000	28.0	44.7	3.50	1,296

Exam Date:09/02/2008
 Examiner: 1

Barlow Grain
 260 Elevator Road
 Carrington, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Facility: Bremen

K		110	Square	floor over bins	0.000	10.30	5.400	28.00	0.00	0.00	28.000	0.000	28.0	44.7	3.50	1,296
Added	K	300	Quonset	flat storage	0.000	110.0	47.00	10.00	0.00	0.00	10.000	0.000	10.0	4026.8	10.0	44,296
	K	301	Peaked	top of sidewall	35.900	0.000	0.000	66.00	0.00	0.00	66.000	2.200	68.2	813.7	10.0	61,043
	K	302	Peaked	top of sidewall	35.900	0.000	0.000	66.00	0.00	0.00	66.000	2.200	68.2	813.7	10.0	61,043

Bin count: 46 Facility: Bremen Section: K Total: 254,047
 To Even: 255,000

Section: L

L		001	Round	top of sidewall	26.000	0.000	0.000	32.00	0.00	0.00	32.000	0.000	32.0	426.8	8.20	14,778
	L	002	Round	top of sidewall	26.000	0.000	0.000	32.00	0.00	0.00	32.000	0.000	32.0	426.8	8.20	14,778
	L	003	Peaked	top of sidewall 37.8' to peak	42.000	0.000	0.000	25.70	0.00	0.00	25.700	2.500	28.2	1113.7	10.0	34,547
	L	004	Peaked	top of sidewall 38' to peak of 43.000	0.000	0.000	26.50	0.00	0.00	0.00	26.500	2.600	29.1	1167.4	10.0	37,368
	L	005	Peaked	top of sidewall 38' to peak of 43.000	0.000	0.000	26.50	0.00	0.00	0.00	26.500	2.600	29.1	1167.4	10.0	37,368
	L	006	Peaked	top of sidewall 38' to peak of 43.000	0.000	0.000	26.50	0.00	0.00	0.00	26.500	2.600	29.1	1167.4	10.0	37,368
	L	401	Peaked	top of sidewall 6' above	15.500	0.000	0.000	17.50	2.20	0.00	19.700	0.900	20.6	151.7	5.50	3,297
	L	402	Peaked	top of sidewall 6' above	15.500	0.000	0.000	17.50	2.20	0.00	19.700	0.900	20.6	151.7	5.50	3,297
	L	403	Peaked	top of sidewall 6' above	15.500	0.000	0.000	17.50	2.20	0.00	19.700	0.900	20.6	151.7	5.50	3,297
	L	404	Peaked	top of sidewall 6' above	15.500	0.000	0.000	17.50	2.20	0.00	19.700	0.900	20.6	151.7	5.50	3,297

Bin count: 10 Facility: Bremen Section: L Total: 189,395
 To Even: 190,000

Overall Licensed Bin Capacity for:

Barlow Grain

Bin count: 136

Licensed Capacity:
(includes pack)

1,500,934 Bu.

Licensed Capacity (to even):

(includes pack and section totals are rounded up to next highest 1000)

1,506,000 Bu.