

Exam Date:09/23/2008

Busch Agricultural Resources, Inc.

Page: 1

Examiner: 1

PO Box 427

West Fargo , ND

County:

Phone: 701-282-5752

CCC Number:

Location/Container Numbers/Comments	Section	Capacity
PART A - ADDITIONAL SPACE TO BE INCLUDED UNDER LICENSE		
807	A	745,758
808	A	745,758
	Total:	1,491,516
PART B - SPACE TO BE DELETED UNDER LICENSE		
<NO BINS DELETED>		
	Total:	0
PART C - ALL SPACE TO BE INCLUDED UNDER LICENSE		
	A	2,220,000
	Total:	2,220,000
PART D - TOTAL CAPACITY BY FUNCTIONAL UNIT		
Sutton 610	A	2,220,000
	Total:	2,220,000

Exam Date:09/23/2008
Examiner: 1

Busch Agricultural Resources, Inc.
PO Box 427
West Fargo , ND
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Del. for Obs.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	---------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Facility: Sutton

Section: A

A		002	Irregular	floor over bins	34.100	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	34.1	3.00	1,756
A		003	Irregular	floor over bins	36.500	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	36.5	3.00	1,880
A		004	Irregular	floor over bins	16.700	0.000	0.000	49.00	0.00	0.00	49.000	0.000	49.0	16.7	2.00	834
A		005	Irregular	floor over bins	97.200	0.000	0.000	68.50	0.00	0.00	68.500	0.000	68.5	97.2	6.00	7,057
A		007	Peaked	top of sidewall	37.000	0.000	0.000	28.70	0.00	0.00	28.700	2.200	30.9	864.3	10.0	29,378
A		008	Irregular	floor over bins	108.00	0.000	0.000	46.50	0.00	0.00	46.500	0.000	46.5	108.0	6.20	5,333
A		009	Irregular	floor over bins	37.800	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	37.8	3.00	1,947
A		011	Irregular	floor over bins	100.80	0.000	0.000	68.50	0.00	0.00	68.500	0.000	68.5	100.8	6.00	7,319
A		012	Irregular	floor over bins	69.300	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	69.3	5.20	3,645
A		013 T	Irregular	floor over bins	27.200	0.000	0.000	7.000	0.00	0.00	7.000	0.000	7.0	27.2	2.50	195
A		013 B	Irregular	floor over bins - top 7'	64.800	0.000	0.000	43.00	0.00	0.00	43.000	0.000	43.0	64.8	5.00	2,925
A		014	Irregular	floor over bins	35.300	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	35.3	3.00	1,818
A		016	Irregular	floor over bins	77.400	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	77.4	5.50	4,083
A		017 T	Irregular	floor over bins	80.100	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	80.1	5.50	4,225
A		017 B	Irregular	floor over bins - top 50'	161.20	0.000	0.000	18.50	0.00	0.00	18.500	0.000	18.5	161.2	7.00	3,191
A		018	Irregular	floor over bins	43.600	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	43.6	3.50	2,256
A		019 T	Irregular	floor over bins	144.10	0.000	0.000	61.50	0.00	0.00	61.500	0.000	61.5	144.1	6.80	9,465
A		019 B	Irregular	floor over bins - top 61.5'	122.20	0.000	0.000	6.500	0.00	0.00	6.500	0.000	6.5	122.2	6.50	846
A		020	Irregular	floor over bins	40.800	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	40.8	3.00	2,101
A		022	Irregular	floor over bins	43.600	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	43.6	3.50	2,256
A		023	Irregular	floor over bins	42.200	0.000	0.000	50.00	0.00	0.00	50.000	0.000	50.0	42.2	3.50	2,184

Exam Date:09/23/2008
 Examiner: 1

Busch Agricultural Resources, Inc.
 PO Box 427
 West Fargo, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Facility: Sutton

Section: A

A		025 T	Irregular	floor over bins	144.10	0.000	0.000	61.50	0.00	0.00	61.500	0.000	61.5	144.1	6.80	9,465
A		025 B	Irregular	floor over bins - top 61.5'	122.20	0.000	0.000	6.500	0.00	0.00	6.500	0.000	6.5	122.2	6.50	846
A		026 T	Irregular	floor over bins	77.300	0.000	0.000	46.00	0.00	0.00	46.000	0.000	46.0	77.3	5.50	3,752
A		026 B	Irregular	floor over bins - top 46'	155.40	0.000	0.000	22.50	0.00	0.00	22.500	0.000	22.5	155.4	6.80	3,735
A		027	Irregular	floor over bins	74.700	0.000	0.000	46.00	0.00	0.00	46.000	0.000	46.0	74.7	5.50	3,625
A		028	Irregular	floor over bins	15.600	0.000	0.000	49.00	0.00	0.00	49.000	0.000	49.0	15.6	2.00	779
A		101 T	Irregular	floor over bins	148.30	0.000	0.000	61.50	0.00	0.00	61.500	0.000	61.5	148.3	6.80	9,740
A		101 B	Irregular	floor over bins - top 61.5'	125.80	0.000	0.000	6.500	0.00	0.00	6.500	0.000	6.5	125.8	6.50	871
A		102 T	Irregular	work floor	148.30	0.000	0.000	61.50	0.00	0.00	61.500	0.000	61.5	148.3	6.80	9,740
A		102 B	Irregular	work floor - top 61.5'	125.80	0.000	0.000	6.500	0.00	0.00	6.500	0.000	6.5	125.8	6.50	871
A		103 T	Irregular	work floor	146.90	0.000	0.000	61.50	0.00	0.00	61.500	0.000	61.5	146.9	6.80	9,648
A		103 B	Irregular	work floor - top 61.5'	124.60	0.000	0.000	6.500	0.00	0.00	6.500	0.000	6.5	124.6	6.50	863
A		104 T	Irregular	work floor	146.90	0.000	0.000	61.50	0.00	0.00	61.500	0.000	61.5	146.9	6.80	9,648
A		104 B	Irregular	work floor - top 61.5'	124.60	0.000	0.000	6.500	0.00	0.00	6.500	0.000	6.5	124.6	6.50	863
A		105 T	Irregular	work floor	148.30	0.000	0.000	61.50	0.00	0.00	61.500	0.000	61.5	148.3	6.80	9,740
A		105 B	Irregular	work floor - top 61.5'	125.80	0.000	0.000	6.500	0.00	0.00	6.500	0.000	6.5	125.8	6.50	871
A		106 T	Square	work floor	0.000	17.40	10.60	61.50	0.00	0.00	61.500	0.000	61.5	148.3	6.80	9,740
A		106 B	Square	work floor - top 61.5'	0.000	14.90	10.50	6.500	0.00	0.00	6.500	0.000	6.5	125.8	6.50	871
A		107 T	Square	work floor	0.000	17.40	10.50	61.50	0.00	0.00	61.500	0.000	61.5	146.9	6.80	9,648
A		107 B	Square	work floor - top 61.5'	0.000	14.90	10.40	6.500	0.00	0.00	6.500	0.000	6.5	124.6	6.50	863
A		108 T	Square	work floor	0.000	17.40	10.20	61.50	0.00	0.00	61.500	0.000	61.5	142.7	6.80	9,373

NDPSC Bin Capacity Chart

Exam Date: 09/23/2008
 Examiner: 1

Busch Agricultural Resources, Inc.
 PO Box 427
 West Fargo, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (irreg):		Side Length	Add for Hopper	Ded. for Obs.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width									

Facility: Sutton

Section: A

A	108 B	Square	work floor- top 61.5'	0.000	14.90	10.10	6.500	0.00	0.00	6.500	0.000	6.5	121.0	6.50	838
A	110 T	Square	work floor	0.000	17.40	10.20	61.50	0.00	0.00	61.500	0.000	61.5	142.7	6.80	9,373
A	110 B	Square	work floor- top 61.5'	0.000	14.90	10.10	6.500	0.00	0.00	6.500	0.000	6.5	121.0	6.50	838
A	111 T	Square	work floor	0.000	17.40	10.50	61.50	0.00	0.00	61.500	0.000	61.5	146.9	6.80	9,648
A	111 B	Square	work floor - top 61.5'	0.000	14.90	10.40	6.500	0.00	0.00	6.500	0.000	6.5	124.6	6.50	863
A	801	Peaked	top of sidewall	42.000	0.000	0.000	64.50	0.00	0.00	64.500	2.500	67.0	1113.7	10.0	82,080
A	802	Peaked	top of sidewall	42.000	0.000	0.000	66.80	0.00	0.00	66.800	2.500	69.3	1113.7	10.0	84,897
A	803	Peaked	top of sidewall	42.000	0.000	0.000	66.80	0.00	0.00	66.800	2.500	69.3	1113.7	10.0	84,897
A	804	Peaked	top of sidewall	42.000	0.000	0.000	66.80	0.00	0.00	66.800	2.500	69.3	1113.7	10.0	84,897
A	805	Peaked	top of sidewall	42.000	0.000	0.000	66.80	0.00	0.00	66.800	2.500	69.3	1113.7	10.0	84,897
A	806	Peaked	top of sidewall	42.000	0.000	0.000	66.80	0.00	0.00	66.800	2.500	69.3	1113.7	10.0	84,897
A	807	Peaked	top of sidewall	105.00	0.000	0.000	90.00	0.00	0.00	90.000	7.400	97.4	6960.6	10.0	745,758
A	808	Peaked	top of sidewall	105.00	0.000	0.000	90.00	0.00	0.00	90.000	7.400	97.4	6960.6	10.0	745,758
Bin count: 55													Facility: Sutton Section: A Total:		2,219,887
													To Even:	2,220,000	

Overall Licensed Bin Capacity for:
 Busch Agricultural Resources, Inc.

Bin count: 55

Licensed Capacity: _____
 (includes pack) **2,219,887 Bu.**

Licensed Capacity (to even): _____
 (includes pack and section totals are rounded up to next highest 1000) **2,220,000 Bu.**