

STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION

Enbridge Pipeline (North Dakota) LLC
Stanley Pump Station Upgrades
Siting Application

Case No. PU-08-812

AFFIDAVIT OF SERVICE BY REGULAR, INSIDE MAIL, OR EMAIL

STATE OF NORTH DAKOTA
COUNTY OF BURLEIGH

Janet Marquart deposes and says that:

she is over the age of 18 years and not a party to this action and, on the **8th** day of **December, 2008**, she deposited in the United States Mail, Bismarck, North Dakota, 35 envelopes by first class mail, fully prepaid, securely sealed and each containing a photocopy and 13 envelopes via inside mail, securely sealed and each containing a photocopy, and 24 electronic mail messages, each with an attached electronic copy of:

Order Granting Certificate of Corridor Compatibility and Route Permit


The envelopes were addressed as follows:

See attached list.

Each post office address shown is the respective addressee's last reasonably ascertainable post office address.

Subscribed and sworn to before me
this **8th** day of **December, 2008**.

SEAL



Janet Marquart

John G. Hamre
Notary Public

Rep. Dawn Marie Charging

7276 14th St NW #16
Garrison ND 58540-9610

Nyle Burchill

835 8th Ave NW
Valley City ND 58072

Rep. Kenton Onstad

3515 66th Ave. NW
Parshall ND 58770-9468

Sen. John M. Warner

33200 331st Ave. SW
Ryder ND 5877-9105

Roger Johnson
Agriculture Department
State Capitol
Bismarck ND 58505

Arvid Barstad
Cementing Service
710 W 15th St
Williston ND 58801

Todd Lindquist
Corp of Engineers
PO Box 527
Riverdale ND 58565-0527

Department of Commerce
1600 E Century Ave Ste 20
Bismarck ND 58503-0649

Dept of Career and Technical Education
State Capitol
Bismarck ND 58505

Jeff Engleson
Energy Development Impact Office
1707 N 9th St
Bismarck ND 58501

Stanley Wright

Box 97
Stanley ND 58784-0097

Sen. John M. Andrist

PO Box E
Crosby ND 58730-0660

Rep. Dorvan Solberg

11395 66th St. NW
Ray ND 58849-9473

Rep. Bob Skarpohl

PO Box 725
Tioga ND 58852-0725

Mike Hummel
BNI Coal, Ltd.
PO Box 897
Bismarck ND 58502-0897

Bob Fogarty
Cenex Minot Terminal
Box 429
Minot ND 58701-0429

Dakota Resource Council
PO Box 1095
Dickinson ND 58602-1095

Carol Olson
Department of Human Services
State Capitol
Bismarck ND 58505

J Williams
Dome Pipeline Corporation
2959 Sierra Ct SW
Iowa City IA 52246

Cathy Callahan
Geo Resources Inc
PO Box 1505
Williston ND 58801-1505

John Hoeven
Governor's Office
State Capitol
Bismarck ND 58505

Historical Society
North Dakota Heritage Center
Bismarck ND 58505

Jay Casler
INDEPTH DATA INC
44 S Bdwy 18th Fl
White Plains NY 10601-4425

Jeff Burgess
Lignite Energy Council
PO Box 2277
Bismarck ND 58502-2277

Harvey Ness
Lignite Energy Council
PO Box 2277
Bismarck ND 58502-2277

City of Palermo
Mayor
PO Box 65
Palermo ND 58769

City of Stanley
Mayor
211 S. Main
Stanley ND 58784

Mountrail County Auditor
101 N. Main St. PO Box 69
Stanley ND 58784-0069

Chairman
Mountrail County Commission
101 N. Main St. PO Box 69
Stanley ND 58784-0069

Galen Anderson
Nakota Company
PO Box 1633
Bismarck ND 58502-1633

Thomas Hanson
ND Assoc of Soil Conservation Dist
3310 University Drive
Bismarck ND 58504-7564

Harlan Fuglesten
ND Association of RECs
PO Box 727
Mandan ND 58554-0727

MR ED MURPHY
ND GEOLOGICAL SURVEY
INSIDE MAIL

Lisa K Fair-McEvers
ND Labor Dept
600 E Blvd Ave

Mike Haupt
ND Land Department
1707 N 9th St
Bismarck ND 58501

Wes Wiedenmeyer
NRCS
Box 1458
Bismarck ND 58502-1458

NuStar Pipeline Operating Partnership,
PO Box 781609
San Antonio TX 78278

OMB
600 E. Boulevard Dept. 110
Bismarck ND 58505-0406

Dale Frink
State Engineer
ND Water Commission 900 East Boulevard
Bismarck ND 58505

State Health Department
State Capitol
Bismarck ND 58505

Janell Cole Capitol Reporter
The Forum
Inside Mail

Chief of Resource Management
Theodore Roosevelt National Park
P O Box 7
Medora ND 58645-0007

Valerie Naylor
Theodore Roosevelt Nat'l Park
PO Box 7
Medora ND 58645

M Zschomler
U S Fish & Wildlife
3425 Miriam Ave
Bismarck ND 58501-7926

Steve Williams
U S Forest Service
240 W Century Ave
Bismarck ND 58501-1494

District Chief
U S Geological Survey
821 E Interstate Ave
Bismarck ND 58501

District Engineer
US Army Engineer District Omaha
106 S 15th St
Omaha NE 68102-1618

Keith Tiggelaar
Williston Basin Interstate Pplne Co
P O Box 5601
Bismarck ND 58506-5601

ndaero@nd.gov
Melinda Weninger
Aeronautics Commission
PO Box 5020
Bismarck ND 58502-5020

jmittleider@nd.gov
John Mittleider
Department of Commerce
600 East Blvd
Bismarck ND 58505

brbjella@flecklaw.com
Brian R. Bjella
Fleck Mather & Strutz, Ltd.
PO Box 2798
Bismarck ND 58502-2798

tgrove@greenergy.com
Terry Grove
Great River Energy
P O Box 800
Elk River MN 55330-0800

sanditabor@lignite.com
Sandi Tabor
Lignite Energy Council
PO Box 2277
Bismarck ND 58502-2277

phillip.franklin@minot.af.mil
Lt. Col. Phil Franklin
Minot Air Force Base 91st Missile Wing
300 Minuteman Drive, Ste 101
Minot AFB ND 58705-5016

fziegler@nd.gov
Francis Ziegler, P.E.
ND Department of Transportation
State Highway Building
Bismarck ND 58505

mdaley@nd.gov
Maren Daley
ND Job Service
P.O. Box 5507 INSIDE MAIL
Bismarck ND 58506-5507

carla.deutsch@thomson.com
Carla Deutsch
Netscan

dprchal@nd.gov
Doug Prchal
North Dakota Parks & Rec
1600 E Century Ave, Ste. 3 INSIDE MAIL
Bismarck ND 58503-0649

apbismarck@ap.org
Phyllis Mensing
Associated Press
PO Box 1018
Bismarck ND 58502-1018

jwmorris@flecklaw.com
John Morrison
Fleck Mather & Strutz, Ltd.
PO Box 2798
Bismarck ND 58502-2798

dsaggau@GREnergy.com
Davic Saggau
Great River Energy
P O Box 800
Elk River MN 55330-0800

nlange@iwla.org
Nancy Lange
Izaak Walton League of America
1619 Dayton Ave Ste 202
St Paul MN 55104

dloer@minnkota.com
David W. Loer
Minnkota Power Cooperative, Inc
Box 13200
Grand Forks ND 58208-3200

jpaczkowski@state.nd.us
John Paczkowski
N D Water Commission
900 E Boulevard
Bismarck ND 58505

tsteinwa@nd.gov
MR TERRY STEINWAND
ND GAME & FISH DEPT
INSIDE MAIL

julie.tessier@thomson.com
Julie Tessier
Netscan

jim.melchior@coteau.com
Jim Melchior
North American Coal Corp
2000 Schafer St Ste D
Bismarck ND 58501-1204

beth.jensen@transcanada.com
Beth Jensen
Northern Border Pipeline Company
PO Box 3330
Omaha NE 68103-0330

john.irby@bismarcktribune.com
John Irby, Editor
The Bismarck Tribune
PO Box 5516
Bismarck ND 58502-5516

news@wdaz.com

WDAZ-TV
PO Box 12639
Grand Forks ND 58208-2639

kjvannin@usgs.gov
K Vannin
U S Geological Survey

keith.tiggelaar@wbip.com
Keith Tiggelaar
Williston Basin Interstate Pplne Co
P O Box 5601
Bismarck ND 58506-5601

STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION

**Enbridge Pipelines (North Dakota) LLC
Stanley Pump Station Upgrades
Siting Application**

Case No. PU-08-812

**ORDER GRANTING
CERTIFICATE OF CORRIDOR COMPATIBILITY AND ROUTE PERMIT**

December 5, 2008

Enbridge Pipelines (North Dakota) LLC (Enbridge) owns and operates an existing crude petroleum pipeline extending from near Alexander, North Dakota, to Clearbrook, Minnesota.

On October 8, 2008, Enbridge Pipelines (North Dakota) LLC (Enbridge) filed a consolidated letter of intent for upgrades to the Stanley Station located in Mountrail County, North Dakota. All construction will take place on land already owned by Enbridge, but will extend beyond the current station boundaries.

In its August 23, 2006 Order, Case No. PU-06-317, the Commission issued to Enbridge a Certificate of Site Compatibility for Transmission Facility Corridor No. 93 and a Permit for the Construction of a Transmission Facility No. 103 granting authority to upgrade the Stanley Station. An environmental assessment and cultural resource survey were provided in that proceeding.

In its June 4, 2008 Order, Case No. PU-07-791, the Commission issued to Enbridge a First Amended Certificate of Corridor Compatibility Number 93 and a First Amended Route Permit Number 103 granting authority for further upgrades at the Stanley Station. An environmental assessment and cultural resource review were provided in that proceeding.

In this proceeding, the Stanley Station upgrades involve installation of two new 200 horsepower booster pumps, two new 300 horsepower variable frequency drives, Supervisory Control and Data Acquisition system upgrades, and the replacement of 6 inch and 10 inch station piping with 12 inch and 16 inch station piping.

The cultural resource survey material demonstrates there will be minimal adverse effects by the proposed construction in the forty acre station site.

By its September 8, 2008, letter, the North Dakota State Historic Preservation Officer (SHPO) affirmed a "No Historic Properties Affected" determination regarding the Stanley station upgrades.

By its December 21, 2007, letter, the North Dakota Game and Fish Department indicated its belief, based on the information it was provided, that the project will have no significant adverse effects on wildlife or wildlife habitat, including endangered species.

On October 22, 2008, the Commission acknowledged the Enbridge letter of intent, assessed a filing fee of \$30,000, waived the one-year waiting period between filing a letter of intent and an application.

Enbridge asserts that these pipeline facilities will produce minimal adverse effects and requests that the Commission (1) waive provisions of law and rule that require filing of separate applications, separate hearings and certain time schedules; (2) not hold a public hearing, but instead publish a notice of opportunity for hearing; (3) find that the proposed facilities are of such design, location and purpose that it will produce minimal adverse effects; and (4) issue the appropriate amended corridor certificates and amended route permits.

On October 22, 2008 the Commission issued a Notice of Filing and Notice of Opportunity for Hearing. The notice provided until December 3, 2008 for comments or requests for hearing.

The issues to be considered in this proceeding are:

1. Will the location, construction, and operation of the proposed pipeline facilities produce minimal adverse effects on the environment and upon the welfare of the citizens of North Dakota?
2. Are the proposed pipeline facilities compatible with the environmental preservation and the efficient use of resources?
3. Will the proposed pipeline facilities locations minimize adverse human and environmental impact while ensuring continuing system reliability and integrity and ensuring that energy needs are met and fulfilled in an orderly and timely fashion?
4. Are the proposed pipeline facilities of such length, design, location, or purpose that they will produce minimal adverse effects so that procedures and time schedules may be waived?
5. Does a demonstrable emergency exist, which requires immediate construction so that adherence to procedures and time schedules would jeopardize the utility's system?

6. Is it appropriate for the Commission to waive any procedures and time schedules as requested in the application?

Enbridge's application included *Environmental Guidelines for Construction* providing environment guidelines and mitigation measures when planning and constructing new pipelines and facilities; and *Spill Prevention, Containment, and Control Plan* describing planning, spill prevention and control measures to minimize impacts resulting from spills of fuels, petroleum products, or other regulated substances as a result of construction.

On December 2, 2008 Enbridge filed an affidavit of Brent Horton, Manager of Regional Services and Development Enbridge Pipelines (North Dakota) LLC, in support of the application.

The location, construction, and operation of the pump stations with upgrades will produce minimal adverse effects on the environment and upon the welfare of the citizens of North Dakota.

The proposed project is compatible with the environmental preservation and the efficient use of resources.

The proposed project minimizes adverse human and environmental impact while ensuring continuing system reliability and integrity and ensuring that energy needs are met and fulfilled in an orderly and timely fashion.

The proposed project is of such length, design, location, or purpose that it will produce minimal adverse effects so that procedures and time schedules may be waived.

It is appropriate to waive procedures and time schedules as requested in the application.

The Commission Orders:

1. Enbridge is issued Second Amended Certificate of Corridor Compatibility Number 93 and Amended Route Permit Number 103 granting authority to upgrade the Stanley Station.
2. Second Amended Certificate of Corridor Compatibility Number 93 and Second Amended Route Permit Number 103 are effective for the life of the pipeline, but are subject to modification by order of the Commission if deemed necessary to further protect the public or the environment.
3. Enbridge must obtain approval from the Commission prior to any changes in the pipeline route or structural locations.

4. Enbridge shall comply with all the rules and regulations of all other agencies having jurisdiction over any phase of the proposed project, and prior to construction of any particular pumping station, shall obtain all other necessary licenses and permits for construction of the station, and shall provide copies to the Commission prior to construction of the station.
5. Enbridge shall obtain written waivers from affected landowners for location of the pipeline within 500 feet of a residence, school, or place of business prior to any construction in those areas.
6. A preconstruction conference shall be held prior to the commencement of any construction. The conference shall include an Enbridge representative, Enbridge's construction supervisor, and Commission staff, to ensure that Enbridge fully understands the conditions set forth in this order.
7. Enbridge shall inform the Commission of the date construction will start just prior to the commencement of construction; report to the Commission on the date construction is started; and, once construction has started, shall keep the Commission updated on construction activities on a weekly basis.
8. Enbridge shall construct and operate the pipeline facilities in the manner described in its application, as revised at the hearing or in late filed exhibits and supplemental materials, and in accordance with all applicable safety requirements.
9. Enbridge shall promptly report to the Commission the presence in the permit area of any critical habitat of threatened or endangered species, or of bald or golden eagles which Enbridge becomes aware of and that were not previously reported to the Commission.
10. Crossings of graded roads shall be bored unless the responsible governing agency specifically permits Enbridge to open cut the road.
11. All pre-existing roads and lanes used during construction must be restored to a condition that will accommodate their previous use, and areas used as temporary roads or working areas during construction must be restored to their original condition.
12. If any cultural resource, paleontological resource, archeological resource, historical resource, or gravesite is discovered during construction of the facility, earth disturbing activities in the immediate vicinity of the discovery must be halted. The resource must be marked, preserved and protected from any further disturbance until a professional examination can be made in consultation with the SHPO. A report of such examination must be filed with the SHPO and the Commission. Clearance to proceed must be given by the SHPO and the Commission.
13. During construction, at least 12 inches of topsoil, where available (or topsoil to the depth of cultivation, whichever is greater), over and along areas where facilities will

be placed must be stripped and segregated from subsoil. Any area on which excavated subsoil will be placed must first be stripped of topsoil. After backfilling with subsoil is completed, any excess subsoil must be placed over the excavation area, blending the grade into existing topography. Topsoil must not be placed within the footprint of the pump station, and must be placed over areas containing topsoil.

14. Construction must be suspended during periods when weather conditions are such that construction activities would cause irreparable harm to the environment, unless adequate measures approved by the Commission are taken.

15. Reclamation and clean-up along the right-of-way must be continuous and coordinated with ongoing construction.

16. Reclamation, fertilization and reseeding must be done by Enbridge according to the Natural Resource Conservation Service unless otherwise specified by the landowner and approved by the Commission.


17. Enbridge's obligation for reclamation and maintenance of the right-of-way shall continue throughout the life of the pipeline.

18. Enbridge shall construct and operate the pipeline in the manner described in its application, and in accordance with all applicable safety requirements.

19. Enbridge shall comply with the Commission's Tree and Shrub Mitigation Specifications attached to this order.

20. Enbridge shall provide the Commission with a hard copy and electronic copy of the design specifications for the construction of the Stanley Station showing the location of the project facilities as built, and an electronic version of the as-built design specifications that can be imported into ESRI GIS mapping software, and shall provide this information within 3 months of the completion of the construction.


PUBLIC SERVICE COMMISSION



Tony Clark
Commissioner



Susan E. Wejald
President



Kevin Cramer
Commissioner

Case No. PU-08-812

Tree and Shrub Mitigation Specifications

Inventory

1. Trees and shrubs anticipated to be cleared, including those that are considered invasive species or noxious weeds (*e.g.*, *Caragana arborescens*, *Elaeagnus angustifolia*, *Rhamnus cathartica*, *Tamarix chinensis*, *T. parviflora*, *T. ramosissima*, *Ulmus pumila*), shall be inventoried before cutting. The inventory shall record the location, number, and species of trees and shrubs.
2. In windbreaks, shelterbelts and other planted areas, trees or shrubs anticipated to be cleared, regardless of size, shall be inventoried for replacement.
3. In native growth areas, trees anticipated to be cleared that are 1 inch diameter at breast height ("dbh") or greater shall be inventoried for replacement.
4. In native growth areas, shrubs anticipated to be cleared in the permanent right-of-way shall be inventoried for replacement.
5. In native growth areas outside the permanent right-of-way, shrubs shall be cut flush with the surface of the ground, taking care to leave the naturally occurring seed bank and root stock intact. If soil disturbance is necessary, the native topsoil shall be preserved and replaced after construction. Shrubs shall be allowed to regenerate naturally where native topsoil is preserved and replaced. Where native topsoil is not preserved and replaced, shrubs anticipated to be cleared shall be inventoried for replacement.
6. In native growth areas, trees and shrubs may be inventoried by actual count or by sampling method that will properly represent the woody

vegetation population. A sampling plan developed by the company, filed with the North Dakota Public Service Commission (NDPSC) and approved prior to the start of construction shall define the sampling method to be used for trees, for tall shrubs and for low shrubs. The data from the sample plots shall be extrapolated to the total acreage of the wooded area to be cleared to determine the species and quantity of trees and shrubs to be replaced.

Clearing for Construction

7. Trees and shrubs shall be selectively cleared, leaving mature trees and shrubs intact where practical.
8. The width of clear cuts through windbreaks, shelterbelts and all other wooded areas shall be limited to 50 feet or less unless otherwise approved by the NDPSC.
9. If the area of trees or shrubs actually cleared differs from the area inventoried, the difference in number of trees and shrubs to be replaced shall be noted on the inventory.

Replacement

10. Prior to tree/shrub replacement, documentation identifying the number and variety of trees removed as well as the mitigation plan for the proposed number, variety, type, location and date of replacement plantings shall be filed with the NSPSC for approval.
11. Tree replacement shall be on a 2 to 1 basis with 2-year-old saplings. Shrub replacement shall be on a 2 to 1 basis with stem cuttings.
12. Trees and shrubs shall be replaced by the same species or similar species suitable for North Dakota growing conditions as recommended by the North Dakota Forest Service.

13. Tree and shrub replacement shall not be conducted within a 20 to 30 foot wide path over the pipeline to facilitate visual inspections of the right-of-way in accordance with U.S. Department of Transportation safety regulations.
14. Landowners shall be given the option of having replacement trees/shrubs planted off the right-of-way on the landowner's property or waiving that requirement in writing and allowing those replacement trees/shrubs to be planted at alternative locations.
15. At the conclusion of the project, documentation identifying the actual number, variety, type, location and date of the replacement plantings shall be filed with the NDPSC.
16. Tree/shrub replacements shall be inspected once a year for three years, on about the anniversary of the plantings, and, on or shortly before October 1 of each year, a report shall be submitted to the NDPSC documenting the condition of replacement planting and any woodlands work completed. If after three years from the anniversary of the plantings the survival rate is less than 75%, the NDPSC may order additional planting(s).

**PUBLIC SERVICE COMMISSION
STATE OF NORTH DAKOTA**

**Second Amended
Certificate of Corridor Compatibility Number 93**

This is to certify that the Commission has designated a transmission facility corridor for Enbridge Pipelines (North Dakota) LLC to construct and operate the Beaver Lodge Station and the Stanley Station with associated facilities and pipeline interconnections in Williams and Mountrail Counties, North Dakota.

The transmission facility corridor is designated by the Commission's August 23, 2006 Order in Case No. PU-06-317 for Beaver Lodge and Stanley Station upgrades; is amended by the Commission's June 4, 2008 Order in Case No. PU-07-791 for Beaver Lodge and Stanley Station upgrades; and is amended by the Commission's December 5, 2008 Order in Case No. PU-08-812 for Stanley Station upgrades.

This certificate is subject to the conditions and limitations noted in those orders.

Bismarck, North Dakota, December 5, 2008.

ATTEST:

PUBLIC SERVICE COMMISSION


Executive Secretary


Commissioner

**PUBLIC SERVICE COMMISSION
STATE OF NORTH DAKOTA**

**Second Amended
Route Permit Number 103**

This is to certify that the Commission has designated a transmission facility route for Enbridge Pipelines (North Dakota) LLC to construct and operate the Beaver Lodge Station and the Stanley Station with associated facilities and pipeline interconnections in Williams and Mountrail Counties, North Dakota.

The transmission facility route is designated by the Commission's August 23, 2006 Order in Case No. PU-06-317 for Beaver Lodge and Stanley Station upgrades; is amended by the Commission's June 4, 2008 Order in Case No. PU-07-791 for Beaver Lodge and Stanley Station upgrades; and is amended by the Commission's December 5, 2008 Order in Case No. PU-08-812 for Stanley Station upgrades.

This permit is subject to the conditions and limitations noted in those orders.

Bismarck, North Dakota, December 5, 2008.

ATTEST:

PUBLIC SERVICE COMMISSION


Executive Secretary


Commissioner