

Section 1.4 of the Pipeline Specific Operations Manual states:

The MAOP is 720 psig limited by the tie-in to WBI's pipeline and the hydrostatic pressure test performed on August 12, 2008. The line is constructed of 0.28-inch wall A53 grade B pipe and has a 46/52 tensile strength. Pressure is controlled by the Robinson Lake Plant reliefs and shutdown controls. The plant reliefs are set at 720 psig or lower. Typical operating pressure is 620 psig. (See *Figure 3: Simplified Pipeline Schematic*)