



Fargo office: 4334 18th Avenue S.W.
Suite 200, P.O. Box 9156
Fargo, ND
58106-9156
Fax: 701-232-4108

Fergus Falls office: 215 S. Cascade Street
P.O. Box 496
Fergus Falls, MN
56538-0496
Fax: 218-998-3165

1-866-410-8780 • www.ottertail.com

June 29, 2009

**Reply to Fergus Falls office
Direct: 218-998-7152**

Mr. Darrell Nitschke
Director of Administration / Executive Secretary
North Dakota Public Service Commission
State Capitol
600 East Boulevard, Department 408
Bismarck, ND 58505-0480

***Via E-Filing
and UPS Overnight Mail***

RE: Compliance Report Under N.D.C.C. § 49-02-34

and

Pursuant to Ordering Clause 13 of August 27, 2008 Order in Otter Tail Corporation Advance Determination of Prudence Application Case No. PU-06-481 and Montana-Dakota Utilities Co., a Division of MDU Resources Group, Inc. Advance Determination of Prudence Application Case No. PU-06-482

Dear Mr. Nitschke:

Enclosed for filing are one original and seven copies of a Renewable and Recycled Energy Objective Compliance Report.

This report is filed pursuant to N.D. Cent. Code § 49-02-34 and Ordering Clause 13 of the Commission's August 27, 2008 Order granting the applications of Otter Tail Corporation and Montana-Dakota Utilities Co. for an advance determination of prudence for the proposed Big Stone II generating facility and associated transmission facilities, Case Nos. PU-06-481 and PU-06-482.

Thank you for your attention to this matter. If you require additional information, please feel free to contact me.

Sincerely,

Mark B. Bring
Associate General Counsel
MBB:nlo

Enclosures

**Renewable and Recycled Energy Objective
Compliance Report
to the
North Dakota Public Service Commission**

**Report RP09-2
Otter Tail Power Company
Resource Planning Department
June 30, 2009**

PREFACE

This document is the report of Otter Tail Corporation, d/b/a Otter Tail Power Company, to the North Dakota Public Service Commission on the Company's efforts and status on compliance with the North Dakota Renewable and Recycled Energy Objective contained in Statutes §49-02-24 through §49-02-26 and §49-02-28 through §49-02-34. This report is required annually commencing on June 30, 2009 and continuing through June 30, 2016.

Questions and comments regarding the information and data contained herein should be addressed to Kerry Kaseman at 218-739-8693 or kkaseman@otpc.com.

TABLE OF CONTENTS

Preface	2
Table of Contents.....	3
Introduction	4
Jurisdictional Requirements	4
Minnesota	5
North Dakota	5
South Dakota	6
Midwest Renewable Energy Tracking System.....	6
Renewable and Recycled Energy Resources.....	8
North Dakota Renewable and Recycled Energy	8
Forecast of Future REO/RES Compliance	9
Barriers to REO/RES Compliance	11
Interconnection Queue.....	11
Transmission Delivery.....	11
LMP Prices	12
Developer Knowledge	12
Economic and Financing Issues	12
ND Sourced Renewable and Recycled Energy.....	13
Summary.....	14
Appendix A – Renewable and Recycled Energy Resources	16

INTRODUCTION

Pursuant to North Dakota Century Code §49-02-34, Otter Tail Corporation, d/b/a Otter Tail Power Company (Otter Tail or Company), makes this information filing electronically to the North Dakota Public Service Commission. This filing is the Company's first annual report on efforts to meet the state renewable and recycled energy objective that 10% of all electricity sold at retail be obtained from renewable and recycled energy sources by 2015.¹

This report is also being submitted pursuant to Order Clause 13 of Case Number PU-06-481 and PU-06-482 before the North Dakota Public Service Commission. In addition to ordering Otter Tail to file the report required by North Dakota Century Code § 49-02-34, Order Clause 13 requires this report to include information on renewable and recycled energy purchased specifically within the state of North Dakota. The additional requirements in Order Clause 13 are contained in the report beginning on page 17 under the title "ND SOURCED RENEWABLE AND RECYCLED ENERGY."

As the following pages of this report demonstrate, Otter Tail is well on the way to implementing renewable resources as part of its diverse resource portfolio and expects to be in full compliance of any and all renewable energy objectives and standards within all three state jurisdictions in which Otter Tail serves.

JURISDICTIONAL REQUIREMENTS

Otter Tail serves retail load in Minnesota, North Dakota, and South Dakota. All three state jurisdictions have some sort of renewable energy objective (REO) or renewable energy standard (RES). Discussion of compliance efforts with any single jurisdiction also requires a discussion of the other two jurisdictions so that a complete understanding of the Company's compliance efforts can be obtained. The following sections describe the requirements in each of the state jurisdictions.

¹ North Dakota Century Code §49-02-28.

Minnesota

Otter Tail is required to make a good faith effort to comply with the state REO through 2011.

Beginning with 2012 the requirement switches to an RES. The state requirements² increase in a step-wise fashion, consisting of:

- 2005 – 1% of retail sales
- 2010 – 7% of retail sales
- 2012 – 12% of retail sales
- 2016 – 17% of retail sales
- 2020 – 20% of retail sales
- 2025 – 25% of retail sales.

Eligible energy technologies for compliance include solar, wind, hydroelectric with a capacity of less than 100 MW, hydrogen,³ or biomass. Biomass includes landfill gas, anaerobic digestion, and mixed municipal solid waste or refuse-derived-fuel from mixed municipal solid waste as a primary fuel. Electricity generated by the combustion of biomass through co-firing with other fuels counts up to the percentage amount of biomass fuel relative to total fuel, only if the generating facility was constructed in compliance with new source performance standards promulgated under the federal Clean Air Act or if the facility employs the maximum achievable or best available control technology for that type of facility.

North Dakota

The state REO is 10% of retail sales by the year 2015, and includes both renewable energy and recycled energy. The calculation contains a provision to reduce the amount of retail sales by any hydroelectric energy that cannot be counted toward the REO.⁴ Renewable electricity and recycled energy includes electricity generated from solar, wind, biomass,⁵ geothermal, hydrogen,⁶ hydroelectric (must be from a facility with an in-service date of no earlier than

² These REO and RES requirements only apply to utilities without nuclear generating assets. Utilities with nuclear generating assets have a more aggressive standard as detailed in Minn. Stat. §216B.1691.

³ Provided that after January 1, 2010 the hydrogen must be generated from the other eligible energy technologies listed.

⁴ North Dakota Century Code §49-02-30.

⁵ Including agricultural crops and wastes and residues, wood and wood wastes and residues, animal wastes, and landfill gas.

⁶ Provided that the hydrogen is generated from a source listed in this section of North Dakota Century Code §49-02-25.

January 1, 2007 or from efficiency improvements to a facility existing as of August 1, 2007), and recycled energy systems producing electricity from currently unused waste heat resulting from combustion or other processes into electricity and which do not use an additional combustion process. Recycled energy does not include any system whose primary purpose is the generation of electricity.

South Dakota

The state REO is 10% of retail sales by the year 2015, and includes renewable, recycled, and conserved energy.⁷ The calculation contains a provision to reduce the amount of retail sales by any hydroelectric energy from a facility with an in-service date prior to July 1, 2008.⁸

Renewable and recycled energy include electricity generated from solar, wind, biomass,⁹ geothermal, hydrogen,¹⁰ hydroelectric (statutes seem to imply it must be from a facility with an in-service date of no earlier than July 1, 2008), and recycled energy systems producing electricity from currently unused waste heat resulting from combustion or other processes into electricity and which do not use an additional combustion process. Recycled energy does not include any system whose primary purpose is the generation of electricity. In the case of conserved energy, the objective will be measured by methods established by rules promulgated by the commission pursuant to chapter 1-26.

MIDWEST RENEWABLE ENERGY TRACKING SYSTEM

Otter Tail has registered almost all renewable energy resources within the Midwest Renewable Energy Tracking System (M-RETS). There is a number of small customer owned units, generally less than 50 kW each, which the Company has not registered. The customers self-serve a portion of their own load with Otter Tail receiving the remaining surplus energy. Otter Tail pays the cost of both initial and annual fees to register a facility in M-RETS and the cost per renewable energy credit (REC) can become quite high on these small units. For 2008, the

⁷ South Dakota Codified Laws §49-34A-101.

⁸ South Dakota Codified Laws §49-34A-103.

⁹ Includes agricultural crops and wastes and residues, wood and wood wastes and residues, animal and other degradable organic wastes, and landfill gas.

¹⁰ Provided that the hydrogen is generated from a source listed in this section of South Dakota Codified Laws §49-34A-94.

amount of unregistered renewable energy was about 301 MWh, only about 0.10% of the over 308,000 MWh of registered renewable energy.

Otter Tail has developed an account structure within M-RETS to help segregate RECs by type and usage. For customer-owned facilities that self-serve customer load, all of the generation is reported within M-RETS. Otter Tail then transfers RECs associated with the energy used to self-serve load into an account in the customer's name, for their use as they deem appropriate. The RECs associated with energy purchased by Otter Tail will remain in the Otter Tail account.

The Otter Tail M-RETS accounts include a retirement account by state jurisdiction by year. Thus it will be easy to verify the amount of RECs retired annually for compliance with each state's requirements. RECs associated with **TailWinds**, the Company's green pricing program, are retired into separate state jurisdiction accounts to ensure proper accounting for the green pricing tracker balance.

Retired RECs will be tracked on a calendar basis. The M-RETS system became operational in the last half of 2007. While Otter Tail began recording renewable energy within M-RETS late in 2007, the Company began full use of the M-RETS system for reporting verification beginning with the first full calendar year commencing January 1, 2008.

Otter Tail has not sold or purchased any RECs separate from the renewable energy. All energy currently being used for compliance is energy generated by Otter Tail or energy purchased by Otter Tail under power purchase agreements.

Otter Tail did sell 3,696,000 KWh of wind generation, including the RECs, during 2008. This energy came from the Ashtabula wind farm that was in start-up phase prior to the availability of the generation outlet facilities. This energy was sold to Minnkota Power Cooperative through a lower voltage tie during October and November. The generation outlet facilities became available in December, at which point Otter Tail began taking energy from the wind farm.

RENEWABLE AND RECYCLED ENERGY RESOURCES

The breakdown of existing and potential future renewable energy resources for Otter Tail, to the extent known, at the time of this report are shown in Appendix A. The data provided includes the name of the facility, kW rating, vintage, technology and energy source, whether owned or through a PPA, and state eligibility. For customer-owned facilities, the customer name is not provided in order to protect customer information. The information provided includes future resources which may or may not be constructed, but for which development work has commenced. There are additional renewable energy facilities which are under discussion, but these have not been included in the data since they are still in preliminary stages of feasibility studies.

NORTH DAKOTA RENEWABLE AND RECYCLED ENERGY

The following data is for the January 1, 2008 – December 31, 2008 time period. The data assumes that renewable energy is allocated across the Otter Tail system based on retail sales kWh. The exceptions to this allocation methodology are that *TailWinds* energy is based on the amount of wind energy sold under the green pricing program in North Dakota. Pursuant to North Dakota Century Code §49-02-30, the hydroelectric energy shown in the table below does not count toward compliance, but can be subtracted from retail sales before calculating the percentage of compliance.

North Dakota Renewable and Recycled Energy MWh January 1, 2008 – December 31, 2008			
Resource	Total kWh	ND Percentage	ND kWh
Borderline Wind	1,345,000	38.19%	513,656
FPL Energy ND Wind II	60,610,000	38.19%	23,146,959
Customer D1	1,142,000	38.19%	436,130
FPLE Langdon	69,559,000	38.19%	26,564,582
OTP Langdon	133,640,000	38.19%	51,037,116
Ashtabula Wind	16,654,000	38.19%	6,360,163
Big Stone Plant Biomass	868,000	38.19%	331,489
North Dakota <i>TailWinds</i>	667,200	100.0%	667,200
Customer A	38,700	38.19%	14,780

Customer C	3,440	38.19%	1,314
Customer E	224,360	38.19%	85,683
Customer F	14,177	38.19%	5,414
Customer G	3,380	38.19%	1,291
Customer H	12,851	38.19%	4,908
Customer J	2,524	38.19%	964
Customer K	274	38.19%	105
Customer L	1,379	38.19%	527
Customer T	350	38.19%	134
OTP Owned Hydro	23,260,100	38.19%	8,883,032
Manitoba Hydro	209,600,000	38.19%	80,046,240 ¹¹
WAPA Hydro	29,972,800	38.19%	11,446,612 ¹²

North Dakota Renewable and Recycled Energy Compliance	
January 1, 2008 – December 31, 2008	
North Dakota Retail Sales	1,609,913,879 kWh
Less Hydro Energy Adjustment	-100,375,885 kWh
Net ND Retail Sales for REO Compliance	1,509,537,994 kWh
North Dakota Renewable Energy	109,172,412 kWh
ND REO Compliance Percentage	7.23%

The data does show that Otter Tail is already more than 50% of the way toward compliance with the North Dakota statute. The level of compliance will increase in 2009 as the 48 MW Ashtabula Wind Farm experiences a full year of operation and again in 2010 as the 49.5 MW Luverne Wind Farm reaches commercial operation during the late part of 2009. It is likely that Otter Tail will exceed the North Dakota REO at some future time. At that time, the surplus RECs will likely be sold and/or banked for future use.

FORECAST OF FUTURE REO/RES COMPLIANCE

At the time of this report, Otter Tail is just beginning construction of the 49.5 MW Luverne Wind Farm. Combined with energy output from the 48 MW the Company owns at the Ashtabula Wind Farm completed in late 2008 and energy output from the 60 MW the Company


¹¹ This hydroelectric includes only energy under the firm 50 MW contract, which is specified as coming from hydro facilities. (262 days X 16 hours/day X 50 MW)

¹² The WAPA hydroelectric energy is an allocation to five Native American tribes.

owns or purchases from the Langdon Wind Farm, Otter Tail is well positioned to comply with the renewable energy objectives and standards in all three states.

The following graph shows the Company’s expected available renewable energy compared to the REO/RES requirements going out to 2020. The graph assumes that all RECs are counted in the year they are generated and are not banked for future compliance use. The graph does not include new customer-owned facilities that may be developed. Otter Tail is seeing significant customer interest in owning wind generation. The Company is obligated to purchase any renewable energy offered from customers under the federal Public Utility Regulatory Policies Act of 1978 (PURPA).

The North Dakota and South Dakota requirements are very similar and are lumped together in the graph. As demonstrated in the graph, Otter Tail expects by 2010 to have sufficient renewable energy available to comply with state REO/RES requirements until beyond 2020.



BARRIERS TO REO/RES COMPLIANCE

The most significant obstacles fall into four basic categories, including:

- Transmission
 - Interconnection queue
 - Transmission delivery service
 - LMP prices
- Developer knowledge
- Economic and financing issues

Interconnection Queue

The Midwest Independent Transmission System Operator (MISO) interconnection queue has been a major impediment to the development of any resources due to the significant backlog of requests. In late August the Federal Energy Regulatory Commission (FERC) approved revisions to the MISO interconnection queue process which Otter Tail believes will help to alleviate the backlog. It is expected that many projects that were simply attempting to reserve a spot in the queue will drop out, and future requests will more likely come from serious projects. Previously projects could submit a request and then remain in suspension for several years, tying up the queue. The ability to suspend a project in the queue is now limited to a much shorter term and only for force majeure reasons. All existing projects in the queue will need to transition to the new process, and MISO has issued a report detailing the status of each interconnection project and the required steps to complete the transition to the new process. The down side to the changes is that developers will have to be ready to make their application deposits and have other benchmarks in place in order to proceed in the new queue process.

Transmission Delivery – As a member of MISO Otter Tail must have firm delivery transmission service for any project to count as a network resource. At the present time transmission service is severely hampered by transmission constraints and the ability to get delivery service is limited. Otter Tail has benefited from the fact that almost 100% of the Company's system is located to the west of the North Dakota Export Boundary, and generation can generally be delivered to load without crossing that constraint. However, there are other wind projects being developed in the

Otter Tail service territory for other utilities that are using up the available transmission service. Otter Tail is a part of the CAPX 2020 group proposing new major high voltage transmission. If approved and constructed, the CAPX 2020 transmission additions will not alone resolve transmission constraints. CAPX 2020 is studying the situation to determine what other new transmission resources are likely to be required.

LMP Prices

The Location Marginal Price (LMP) is beginning to be impacted by the magnitude of the wind development taking place. The lack of adequate transmission for delivery service is causing wind generation to be economically stranded at times of plentiful wind and less than peak loads. Otter Tail wind resources at times receive less than full MISO market price because of inadequate transmission to move the energy where it is needed. As a result, the LMP price at the wind farm declines and can become negative at times. Otter Tail has to pay MISO to keep the wind generation operating at those times. This situation is being exacerbated as the amount of wind generation on the system increases. Consequently, a portion of the generation value is jeopardized. The only cure is to increase transmission capability. The previously mentioned transmission project efforts will help to alleviate the situation, although even more transmission will be needed.

Developer Knowledge

The larger developers know what they are doing with wind development. Otter Tail has experienced difficulty with small developers, community-based wind developers, and customers who consider building wind generation. These entities generally do not have the background and have not spent the time to learn about wind generation prior to attempting a project.

Economic and Financing Issues

The recent economic downturn is hampering the development of renewable resources. Some major wind developers have already announced intentions to scale back their development plans for the near-term future. While Otter Tail has not seen any specific project delays or cancellations in wind projects yet, such actions are expected by most wind industry publications. Small wind development may especially be impacted in their efforts to obtain project financing.

ND SOURCED RENEWABLE AND RECYCLED ENERGY

Otter Tail obtained 280,692,179 kWh of renewable energy from North Dakota sourced renewable energy facilities in 2008. This energy was obtained both from facilities at which Otter Tail purchases the energy and at facilities Otter Tail owns. Facilities from which Otter Tail purchases energy had a combined capacity rating of 41,230 kW and produced 130,398,179 kWh of energy in 2008. Facilities Otter Tail owns had a combined capacity rating of 88,500 kW and produced 150,294,000 kWh of energy in 2008.

Otter Tail purchases energy from five facilities in North Dakota: FPLE ND Wind II, Langdon Wind Energy Center, and three customer-owned wind energy facilities.

FPLE ND Wind II is a 21,000 kW rated wind energy facility located near Edgeley, North Dakota. It produced 60,610,000 kWh of energy in 2008. NextEra Energy, formerly FPL Energy, owns FPLE ND Wind II.

The Langdon Wind Energy Center is a 159,000 kW rated wind energy facility located near Langdon, ND. Otter Tail purchases energy from wind energy turbines with a capacity rating of 19,500 kW. Otter Tail purchased 69,559,000 kWh of energy in 2008.

Otter Tail purchased energy from three customer-owned wind energy facilities in 2008. The three facilities have a combined capacity rating of 730 kW. Otter Tail purchased a total 229,179 kWh of energy from these three facilities. This amount does not reflect the total production of the facilities since the customers self serve a portion of their own load and Otter Tail purchases the excess.

Otter Tail owns portions of two wind energy facilities in North Dakota, the Langdon Wind Energy Center and the Ashtabula Wind Energy Center.

The Langdon Wind Energy Center is a 159,000 kW rated wind energy facility located near Langdon, North Dakota. Otter Tail owns wind turbines with a capacity rating of 40,500 kW. Otter Tail obtained 133,640,000 kWh of energy from the portion it owns in 2008.

The Ashtabula Wind Energy Center is a 199,500 kW rated wind energy facility located in Barnes County, North Dakota. Otter Tail owns wind turbines with a capacity rating of 48,000 kW. Otter Tail obtained 16,654,000 kWh of energy from the portion it owns in 2008. This amount does not reflect a full year of operation since the portion of the facility that Otter Tail owns first reached commercial operation in October 2008 and Otter Tail first took energy from the facility in December 2008.

On May 22, 2009, Otter Tail announced contractual agreements to build and own 49,500 kW of a planned wind farm to be operated by NextEra Energy known as the Luverne Wind Farm. Otter Tail's portion of the wind farm will be built in Steele County and is anticipated to be operational by late 2009. Construction started in June 2009. The entire Luverne Wind Farm has a project size of 169,500 kW.

SUMMARY

Otter Tail has stepped forward with its development of renewable resources for a variety of reasons and is completing new renewable energy facilities ahead of REO/RES requirements. The most recent Company integrated resource plan called for 160 MW of new wind generation. With the Luverne project, Otter Tail will have completed that amount of wind generation addition to the system. Part of the reason for accelerated implementation is economics, as the cost of wind generation is escalating at a rate as fast or faster than any other generating technology. Also, the federal PTC is not likely to be available for the long term, so Otter Tail is taking advantage by moving forward early. The PTC reduces the cost of wind generation by about 33%.

The Company has also taken advantage of significant wind development incentives in North Dakota. Currently those incentives also have a sunset provision, so early implementation of wind generation has accessed those incentives.

With the current renewable resources in existence and under construction, additional resources for REO/RES compliance will likely not be needed until some time after 2020. This forecast does not include counting the many small customer owned units currently being installed. There are many uncertainties going forward with all forecasts, including load growth, conservation efforts, and customer-owned renewable resources.

Otter Tail expects its next integrated resource plan, which is expected to be completed during the second half of 2009, to provide updated information regarding the long-term view of REO/RES compliance.

Dated this 29 day of June 2009.

OTTER TAIL CORPORATION, DBA
OTTER TAIL POWER COMPANY

By: Kerry Kaseman
Kerry Kaseman, Sr. Credit Administrator

Appendix A – Renewable and Recycled Energy Resources

Existing Renewable and Recycled Generating Facilities							
Name	State	kW Rating	Vintage	Technology	Power Source	Owned/PPA	State Eligibility
Customer A	MN	225	1997	Wind	Wind	PPA	MN, ND, SD
Customer B	SD	90	2002	Wind	Wind	PPA	TailWinds ¹³
Hendricks	MN	900	2001	Wind	Wind	PPA	TailWinds ¹³
Borderline	MN	900	2003	Wind	Wind	PPA	MN, ND, SD
FPLE ND Wind II	ND	21,000	2003	Wind	Wind	PPA	MN, ND, SD
Customer C	ND	50	1985	Wind	Wind	PPA	MN, ND, SD
FPLE Langdon	ND	19,500	2007	Wind	Wind	PPA	MN, ND, SD
OTP Langdon	ND	40,500	2008	Wind	Wind	Owned	MN, ND, SD
Ashtabula Wind	ND	48,000	2008	Wind	Wind	Owned	MN, ND, SD
Customer D1	MN	1,650	2005	Wind	Wind	PPA	MN, ND, SD
Customer E	ND	660	2008	Wind	Wind	PPA	MN, ND, SD
Customer F	MN	39.5	2008	Wind	Wind	PPA	MN, ND, SD
Customer G	MN	39.5	2008	Wind	Wind	PPA	MN, ND, SD
Customer H	MN	39.5	2008	Wind	Wind	PPA	MN, ND, SD
Customer I	MN	35	2007	Wind	Wind	PPA	MN, ND, SD
Customer J	MN	1.8	2008	Wind	Wind	PPA	MN, ND, SD
Customer K	MN	1.8	2008	Wind	Wind	PPA	MN, ND, SD
Customer L	ND	20	2008	Wind	Wind	PPA	MN, ND, SD
Customer T	MN	3	2008	Photovoltaic	Sun	PPA	MN, ND, SD

¹³ At this time TailWinds energy counts in ND and SD, but not MN. TailWinds is the Company's green pricing tariff and the energy is counted only as customers purchase the energy, not as it is generated.

Big Stone Plant	SD	245,784	1975	Steam	Biomass	Owned	ND, SD ¹⁴
Bemidji Hydro	MN	740	1907	Hydro	Water	Owned	MN
Taplin Gorge	MN	560	1925	Hydro	Water	Owned	MN
Hoot Lake	MN	1,000	1914	Hydro	Water	Owned	MN
Pisgah	MN	520	1918	Hydro	Water	Owned	MN
Wright	MN	400	1922	Hydro	Water	Owned	MN
Dayton Hollow	MN	980	1909	Hydro	Water	Owned	MN
WAPA Allocation	Several	5,566	Various	Hydro	Water	PPA	None
Manitoba Hydro	Manitoba	50,000	Various	Hydro	Water	PPA	None

Appendix A – Renewable and Recycled Energy Resources

Planned and Expected Future Renewable and Recycled Generating Facilities							
Name	State	kW Rating	Vintage	Technology	Power Source	Owned/PPA	State Eligibility
Luverne Wind	ND	49,500	2009	Wind	Wind	Owned	MN, ND, SD
Customer D2	MN	1,500	2009	Wind	Wind	PPA	MN, ND, SD
Customer D3	MN	1,500	2009	Wind	Wind	PPA	MN, ND, SD
Customer M	MN	20	2009	Wind	Wind	PPA	MN, ND, SD
Customer N	MN	250	2009	Wind	Wind	PPA	MN, ND, SD
Customer O	MN	1,500	2009	Wind	Wind	PPA	MN, ND, SD
Customer P	MN	7,000-8,000	2010	Binary Cycle	Waste Heat	PPA	ND, SD
Customer Q	MN	4,500	2010	Steam	MSW	PPA	MN
Customer R	MN	25	2009	Wind	Wind	PPA	MN, ND, SD
Customer S	MN	2.4	Unknown	Wind	Wind	PPA	MN, ND, SD

¹⁴ Only the biomass portion of the fuel is counted. For the January 1, 2008 – December 31, 2008 time period only about .04% of the fuel was biomass.