

Exam Date:06/16/2011

Edgeley Bean Receiving, LLC

Page: 1

Examiner: 1

310 8th Ave W

Edgeley , ND

County:

Phone: 701-709-0237

CCC Number:

Location/Container Numbers/Comments	Section	Capacity
PART A - ADDITIONAL SPACE TO BE INCLUDED UNDER LICENSE		
214	A	60,931
001	B	60,931
	Total:	121,862
PART B - SPACE TO BE DELETED UNDER LICENSE		
<NO BINS DELETED>		
	Total:	0
PART C - ALL SPACE TO BE INCLUDED UNDER LICENSE		
	A	238,000
	B	61,000
	Total:	299,000
PART D - TOTAL CAPACITY BY FUNCTIONAL UNIT		
Edgeley 1177	A B	299,000
	Total:	299,000

Exam Date:06/16/2011

Edgeley Bean Receiving, LLC
310 8th Ave W
Edgeley , ND
County:

Page: 1

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	-------------------------------	--------	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: Edgeley

Section: A

A	001	Irregular	work floor		71.000	9.398	9.398	49.00	0.00	0.00	49.000	0.000	49.0	71.0	5.20	3,660
A	002	Irregular	work floor		47.300	7.671	7.671	33.00	0.00	0.00	33.000	0.000	33.0	47.3	4.00	1,623
A	003	Irregular	work floor		71.000	9.398	9.398	46.00	0.00	0.00	46.000	0.000	46.0	71.0	5.20	3,436
A	004	Irregular	work floor		25.200	5.599	5.599	34.00	0.00	0.00	34.000	0.000	34.0	25.2	2.50	878
A	005	Irregular	work floor		71.000	9.398	9.398	49.00	0.00	0.00	49.000	0.000	49.0	71.0	5.20	3,660
A	006	Irregular	work floor		36.500	6.738	6.738	34.00	0.00	0.00	34.000	0.000	34.0	36.5	3.00	1,278
A	007	Irregular	work floor		71.000	9.398	9.398	49.00	0.00	0.00	49.000	0.000	49.0	71.0	5.20	3,660
A	008	Irregular	work floor		36.500	6.738	6.738	34.00	0.00	0.00	34.000	0.000	34.0	36.5	3.00	1,278
A	010	Irregular	work floor		46.200	7.581	7.581	34.00	0.00	0.00	34.000	0.000	34.0	46.2	4.00	1,634
A	011	Irregular	work floor		71.000	9.398	9.398	49.00	0.00	0.00	49.000	0.000	49.0	71.0	5.20	3,660
A	012	Irregular	work floor		46.200	7.581	7.581	34.00	0.00	0.00	34.000	0.000	34.0	46.2	4.00	1,634
A	013	Irregular	work floor		71.000	9.398	9.398	49.00	0.00	0.00	49.000	0.000	49.0	71.0	5.20	3,660
A	015	Irregular	work floor		32.000	6.309	6.309	34.00	0.00	0.00	34.000	0.000	34.0	32.0	2.50	1,115
A	016	Irregular	work floor		71.000	9.398	9.398	49.00	0.00	0.00	49.000	0.000	49.0	71.0	5.20	3,660
A	017	Irregular	work floor		71.000	9.398	9.398	49.00	0.00	0.00	49.000	0.000	49.0	71.0	5.20	3,660
A	101 T	Irregular	work floor		123.70	12.41	12.41	37.00	0.00	0.00	37.000	0.000	37.0	123.7	6.50	4,875
A	101 B	Irregular	work floor		101.70	11.25	11.25	9.000	0.00	0.00	9.000	0.000	9.0	101.7	6.00	970
A	102 T	Irregular	work floor		123.70	12.41	12.41	37.00	0.00	0.20	36.800	0.000	36.8	123.7	6.50	4,848
A	102 B	Irregular	work floor		101.70	11.25	11.25	9.000	0.00	0.55	8.450	0.000	8.5	101.7	6.00	916
A	103 T	Irregular	work floor		105.30	11.45	11.45	37.00	0.00	0.00	37.000	0.000	37.0	105.3	6.20	4,138
A	103 B	Irregular	work floor		86.400	10.37	10.37	10.00	0.00	0.00	10.000	0.000	10.0	86.4	5.80	914

Exam Date:06/16/2011

Edgeley Bean Receiving, LLC
310 8th Ave W
Edgeley, ND
County:

Page: 2

Examiner: 1

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width									

Facility: Edgeley

Section: A

	A	104 T	Irregular	work floor	105.30	11.45	11.45	37.00	0.00	0.00	37.000	0.000	37.0	105.3	6.20	4,138
	A	104 B	Irregular	work floor	86.400	10.37	10.37	10.00	0.00	0.00	10.000	0.000	10.0	86.4	5.80	914
	A	105 T	Irregular	work floor	125.90	12.52	12.52	37.00	0.00	0.00	37.000	0.000	37.0	125.9	6.50	4,961
	A	105 B	Irregular	work floor	103.50	11.35	11.35	10.00	0.00	0.00	10.000	0.000	10.0	103.5	6.00	1,097
	A	106 T	Irregular	work floor	125.90	12.52	12.52	37.00	0.00	0.00	37.000	0.000	37.0	125.9	6.50	4,961
	A	106 B	Irregular	work floor	103.50	11.35	11.35	10.00	0.00	0.00	10.000	0.000	10.0	103.5	6.00	1,097
	A	201	Peaked	top of sidewall	16.000	0.000	0.000	25.00	2.00	0.00	27.000	1.000	28.0	161.6	5.80	4,787
	A	202	Peaked	top of sidewall	16.000	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	161.6	5.80	3,933
	A	203	Peaked	top of sidewall	16.000	0.000	0.000	25.00	2.00	0.00	27.000	1.000	28.0	161.6	5.80	4,787
	A	204	Peaked	top of sidewall	29.300	0.000	0.000	40.00	0.00	0.00	40.000	1.800	41.8	542.0	8.80	24,650
	A	205	Peaked	top of sidewall	16.000	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	161.6	5.80	3,933
	A	206	Peaked	top of sidewall	10.000	0.000	0.000	10.00	2.00	0.00	12.000	0.600	12.6	63.1	4.80	833
	A	207	Peaked	top of sidewall	16.000	0.000	0.000	25.00	2.00	0.00	27.000	1.000	28.0	161.6	5.80	4,787
	A	208	Peaked	top of sidewall	14.800	0.000	0.000	15.00	2.20	0.00	17.200	0.900	18.1	138.3	5.50	2,641
	A	209	Peaked	top of sidewall	12.000	0.000	0.000	12.00	1.75	0.00	13.750	0.700	14.5	90.9	5.00	1,384
	A	210	Peaked	top of sidewall	30.000	0.000	0.000	33.50	0.00	0.00	33.500	1.800	35.3	568.2	9.00	21,862
	A	211	Peaked	top of sidewall	30.000	0.000	0.000	33.50	0.00	0.00	33.500	1.800	35.3	568.2	9.00	21,862
	A	212	Peaked	top of sidewall	18.000	0.000	0.000	17.70	1.75	0.00	19.450	1.100	20.6	204.6	6.00	4,468
	A	213	Peaked	top of sidewall	18.000	0.000	0.000	17.70	1.75	0.00	19.450	1.100	20.6	204.6	6.00	4,468
Added	A	214	Peaked	top of sidewall	47.800	0.000	0.000	35.50	0.00	0.00	35.500	2.900	38.4	1442.5	10.0	60,931

Exam Date:06/16/2011

Edgeley Bean Receiving, LLC
 310 8th Ave W
 Edgeley , ND
 County:

Examiner: 1

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.) Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	---	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Bin count: 41

Facility: Edgeley Section: A Total: 237,651

To Even: 238,000

Section: B

Added	B	001	Peaked	top of sidewall	47.800	0.000	0.000	35.50	0.00	0.00	35.500	2.900	38.4	1442.5	10.0	60,931
-------	---	-----	--------	-----------------	--------	-------	-------	-------	------	------	--------	-------	------	--------	------	--------

Bin count: 1

Facility: Edgeley Section: B Total: 60,931

To Even: 61,000

Overall Licensed Bin Capacity for:

Edgeley Bean Receiving, LLC

Bin count: 42

Licensed Capacity:
 (Includes pack)

298,582 Bu.

Licensed Capacity (to even):
 (includes pack and section totals are
 rounded up to next highest 1000)

299,000 Bu.

