

**BASIN ELECTRIC
POWER COOPERATIVE**

1717 EAST INTERSTATE AVENUE
BISMARCK, NORTH DAKOTA 58503
PHONE: 701-223-0441 FAX: 701-557-5336



August 22, 2013

Darrell Nitschke
Executive Director
North Dakota Public Service Commission
600 East Boulevard; Dept 408
Bismarck, ND 58505-0480



Re: Case No. PU-11-696
Basin Electric Power Cooperative
AVS-Neset 345-kV Transmission Project
Siting Application

Dear Mr. Nitschke:

Enclosed for filing please find an electronic CD, an original and ten (10) copies of Basin Electric Power Cooperative's map books for the Route and Structures Applications. In addition you will find an original and ten (10) copies of the Mercer County Conditional Use Permit and the Noise Analysis for the Tande and Gumbo Creek Substations. The Conditional Use Permit and Noise Analysis have been submitted electronically directly to the docket.

Sincerely,

A handwritten signature in cursive script that reads "Cris Miller".

Cris Miller
Senior Environmental Project Administrator

cm/sr
Enclosures

cc: Casey Jacobson w/o
Duey Marthaller w/o

RECEIVED AUG 21 2013

**MERCER COUNTY BOARD OF COMMISSIONERS
STANTON, NORTH DAKOTA**

**CERTIFICATE OF APPROVAL OF A CONDITIONAL USE
ZONING CASE 13-08-02**

ISSUED TO: Basin Electric Power Cooperative
1717 East Interstate Ave
Bismarck ND 58503


CONDITIONAL USE: 345-Kilovolt Transmission Line

LEGAL DESCRIPTION: Subject route, Sections 7,8,14,15,16,17, &23
T145N R88W. Sections 7,8,9,10,11 &12
T145N R89W. Sections 7,8,9,10,11 &12
T145N R90W of the 5th P.M. Mercer
County, ND

PLANNING COMMISSION: Recommended approval August 15th, 2013

REMARKS: Approved on condition of Public Service
Commission approval

Issued this 21st day of August 2013, by the Board of Mercer County
Commissioners.



Frank Bitterman, Chairman



Shana Brost, County Auditor

Memorandum



Date: August 19, 2013
To: Cris Miller, Basin Electric Power Cooperative
From: Gabriel Weger, Burns & McDonnell
Subject: Gumbo Creek Substation Preliminary Noise Analysis

Burns & McDonnell has analyzed the preliminary, expected sound contribution from the proposed Gumbo Creek Substation, located near Killdeer, North Dakota for Basin Electric Power Cooperative. The model analyzed potential sound levels at the six nearest residences due to the installation of two 200-MVA transformers at Basin's Gumbo Creek Substation.

Department of Housing and Urban Development (HUD) Criteria

The substation will be located in Dunn County, which does not have any applicable noise ordinances. The state of North Dakota has a noise statute based on nuisance, but provides no decibel levels that must be achieved. Therefore, this project will be compared to HUD guideline noise levels for residential areas. HUD developed formal requirements related specifically to noise in 1971 (23 CFR 772). The noise regulations set forth the exterior noise standards seen in Table 1 for new housing construction assisted or supported by HUD. These noise levels are based on an L_{dn} noise level. L_{dn} is the day/night sound level, in which the average, steady sound levels (L_{eq}) are time weighted, with a 10-dB penalty applied during nighttime hours (i.e., if hourly L_{eq} sound levels are predicted to be 45 dBA, then the nighttime sound levels are artificially inflated to 55 dBA for the calculation of L_{dn}). Table 1 also lists the appropriate noise attenuation required by the HUD regulations for housing construction that is assisted by HUD.

Table 1
HUD Site Acceptability Standards

Noise Level, L_{dn} (dBA)	Acceptability	Attenuation Level Required
Not exceeding 65	Acceptable	None
65 to 75	Normally not acceptable	5 dB attenuation above the attenuation provide by standard construction required in 65 to 75 L_{dn} zone, 10 dB attenuation in 70 to 75 L_{dn} zone
Exceeding 75	Unacceptable	N/A

Based on the HUD guidance for new construction, an L_{dn} of 65 dBA will be considered acceptable for the residences near the substation. For the purposes of this memo, the predicted noise levels from the transformers at the substation were compared to the HUD standards.

August 19, 2013

Page 3

would then be added to the noise from the gas wells and other ambient sources in the area to establish the overall noise expected at the residences.

Table 3
Expected Sound Levels

Receiver	Sound Pressure Level (dBA)	
	L_{eq}	L_{dn}
Residence 1	38.6	45.0
Residence 2	32.9	39.3
Residence 3	30.3	36.7
Residence 4	32.4	38.8
Residence 5	34.7	41.1
Residence 6	29.0	35.4

HUD requirements state that L_{dn} sound levels cannot exceed 65 dBA at any residence. The substation is planned for a rural area with the closest residence being over 1 kilometer away. The highest-predicted L_{dn} impact at the nearby residences is 45.0 dBA. Therefore, it is not expected that operation of the Gumbo Creek Substation will cause sound levels that exceed the HUD requirements. To graphically represent the expected sound impacts of the proposed substation, Figure 3 provides an L_{dn} sound-level isopleth in 5-dBA contour increments.

Gabriel Weger

Attachments:

- Figure 1
- Figure 2
- Figure 3



● Residence
□ Substation Boundary




Figure 2
Gumbo Creek
Residence Locations

Memorandum



Date: February 18, 2013
To: Cris Miller, Basin Electric Power Cooperative
From: Gabriel Weger, Burns & McDonnell
Subject: Tande Substation Preliminary Noise Analysis

Burns & McDonnell has analyzed the preliminary, expected sound contribution from the proposed Tande Substation, located near Tioga, North Dakota for Basin Electric Power Cooperative. The model analyzed the sound levels expected at the three nearest residences due to the two 600 MVA transformers at Basin's Tande Substation.

Department of Housing and Urban Development (HUD) Criteria

The substation will be located in Dunn County, which does not have any applicable noise ordinances. The state of North Dakota has a noise statute based on nuisance, but provides no decibel levels that must be achieved. Therefore, this project will be compared to HUD guideline noise levels for residential areas. HUD developed formal requirements related specifically to noise in 1971 (23 CFR 772). The noise regulations set forth the exterior noise standards seen in Table 1 for new housing construction assisted or supported by HUD. These noise levels are based on an L_{dn} noise level. L_{dn} is the day/night sound level, in which the average, steady sound levels (L_{eq}) are time weighted, with a 10-dB penalty applied during nighttime hours (i.e., if L_{eq} sound levels are 45 dBA, then the nighttime sound levels are artificially inflated to 55 dBA for the calculation of L_{dn}). Table 1 also lists the appropriate noise attenuation required by the HUD regulations for housing construction that is assisted by HUD.

Table 1
HUD Site Acceptability Standards

Noise Level, L_{dn} (dBA)	Acceptability	Attenuation Level Required
Not exceeding 65	Acceptable	None
65 to 75	Normally not acceptable	5 dB attenuation above the attenuation provide by standard construction required in 65 to 75 L_{dn} zone, 10 dB attenuation in 70 to 75 L_{dn} zone
Exceeding 75	Unacceptable	N/A

Based on the HUD guidance for new construction, an L_{dn} of 65 dBA will be considered acceptable for the residences near the substation. For the purposes of this memo, the predicted noise levels from the transformers at the substation were compared to the HUD standards.

Memorandum *(continued)*



February 18, 2013

Page 3

HUD requirements state that L_{dn} sound levels cannot exceed 65 dBA at any residence. The highest-predicted L_{dn} impact at the nearby residences is 49.2 dBA. Therefore, it is not expected that operation of the Tande Substation will cause sound levels that exceed the HUD requirements. To graphically represent the expected sound impacts of the proposed substation, Figure 1 in Attachment 1 provides an L_{dn} sound-level isopleth in 5-dBA contour increments.

Gabriel Weger

Attachment 1: Tande Substation L_{dn} Contours