

Exam Date:07/30/2012

Dakota Quality Grain Cooperative
 PO Box 128
 Parshall, ND
 County:
 Phone: 701-862-3113
 CCC Number:

Page: 1

Examiner: 1

Location/Container Numbers/Comments	Section	Capacity
PART A - ADDITIONAL SPACE TO BE INCLUDED UNDER LICENSE		
301	A	146,406
302	A	146,406
303	A	146,406
304	A	146,406
202	F	81,092
203	F	110,378
204	F	149,766
		Total: 926,860

PART B - SPACE TO BE DELETED UNDER LICENSE

001	H	762
003	H	2,219
004	H	2,219
007	H	2,219
008	H	2,219
009	H	861
010	H	861
011	H	861
012	H	861
013	H	2,219
014	H	2,219
016	H	2,219
017	H	2,219
018	H	323
020	H	762
101	H	2,405
102	H	2,686
103	H	983
104	H	2,523
106	H	1,681
107	H	1,095
108	H	2,523
109	H	2,686
110	H	2,405
111	H	835
112	H	2,048
113	H	1,571
114	H	752
115	H	2,048
201	H	1,858
202	H	1,858
203	H	1,858
204	H	1,858

Location/Container Numbers/Comments	Section	Capacity
205	H	828
206	H	828
207	H	1,858
208	H	1,858
209	H	693
210	H	749
211	H	1,858
212	H	1,858
213	H	1,593
Total:		68,839

PART C - ALL SPACE TO BE INCLUDED UNDER LICENSE

A	1,127,000	
B	795,000	
C	68,000	
D	300,000	
F	944,000	
G	45,000	
I	25,000	
J	488,000	
K	66,000	
L	26,000	
M	692,000	
Total:		4,576,000

PART D - TOTAL CAPACITY BY FUNCTIONAL UNIT

New Town 842	F G I	1,014,000
Parshall 839	A B C D	2,290,000
Ross 840	J K L M	1,272,000
Total:		4,576,000

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 1

Examiner: 1

PO Box 128
Parshall, ND
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	-------------------------------	--------	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: New Town

Section: F

F	002A		Square	work floor	0.000	9.800	5.700	86.00	0.00	0.00	86.000	0.000	86.0	44.9	3.50	3,996
F	002B		Square	work floor	0.000	5.800	5.000	86.00	0.00	0.00	86.000	0.000	86.0	23.3	2.00	2,044
F	003A		Irregular	work floor	35.400	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	35.4	3.00	3,135
F	003B		Irregular	work floor	35.400	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	35.4	3.00	3,135
F	004		Irregular	work floor	48.600	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	48.6	4.20	4,356
F	005		Round	work floor	13.000	0.000	0.000	110.0	0.00	0.00	110.00	0.000	110.0	106.7	5.20	12,347
F	006		Irregular	work floor	22.500	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	22.5	2.00	1,974
F	007		Irregular	work floor	25.300	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	25.3	2.50	2,230
F	008		Square	work floor	0.000	5.600	5.000	86.00	0.00	0.00	86.000	0.000	86.0	22.5	2.00	1,974
F	009		Irregular	work floor	25.300	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	25.3	2.50	2,230
F	011		Irregular	work floor	22.500	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	22.5	2.00	1,974
F	012		Round	work floor	13.000	0.000	0.000	110.0	0.00	0.00	110.00	0.000	110.0	106.7	5.20	12,347
F	013		Square	work floor	0.000	9.800	5.700	86.00	0.00	0.00	86.000	0.000	86.0	44.9	3.50	3,996
F	014		Irregular	work floor	9.000	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	9.0	2.00	789
F	015A		Irregular	work floor-each bin	9.000	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	9.0	2.00	789
F	015B		Irregular	work floor-each bin	9.000	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	9.0	2.00	789
F	015C		Irregular	work floor-each bin	9.000	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	9.0	2.00	789
F	016		Square	work floor	0.000	5.600	5.000	86.00	0.00	0.00	86.000	0.000	86.0	22.5	2.00	1,974
F	017		Irregular	work floor	35.400	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	35.4	3.00	3,135
F	018		Square	work floor	0.000	9.800	5.700	86.00	0.00	0.00	86.000	0.000	86.0	44.9	3.50	3,996
F	019		Round	work floor	13.000	0.000	0.000	110.0	0.00	0.00	110.00	0.000	110.0	106.7	5.20	12,347
F	020		Irregular	work floor	21.700	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	21.7	2.00	1,903

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 2

Examiner: 1

PO Box 128

Parshall , ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	-------------------------------	--------	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: New Town

Section: F

F	021A	Square	work floor		0.000	6.300	5.000	86.00	0.00	0.00	86.000	0.000	86.0	25.3	2.50	2,230
F	021B	Irregular	work floor		22.400	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	22.4	2.00	1,965
F	022	Irregular	work floor		23.300	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	23.3	2.00	2,044
F	023	Irregular	work floor		22.400	0.000	0.000	86.00	0.00	0.00	86.000	0.000	86.0	22.4	2.00	1,965
F	024	Round	work floor		13.000	0.000	0.000	110.0	0.00	0.00	110.00	0.000	110.0	106.7	5.20	12,347
F	025	Square	work floor		0.000	6.300	2.300	86.00	0.00	0.00	86.000	0.000	86.0	11.6	2.00	1,018
F	026	Peaked	top of sidewall		15.000	0.000	0.000	25.00	2.20	0.00	27.200	0.900	28.1	142.1	5.50	4,213
F	027	Peaked	top of sidewall		15.000	0.000	0.000	25.00	2.20	0.00	27.200	0.900	28.1	142.1	5.50	4,213
F	028	Peaked	work floor		15.000	0.000	0.000	25.00	2.20	0.00	27.200	0.900	28.1	142.1	5.50	4,213
F	029	Peaked	work floor		15.000	0.000	0.000	25.00	2.20	0.00	27.200	0.900	28.1	142.1	5.50	4,213
F	030	Peaked	work floor		15.000	0.000	0.000	25.00	2.20	0.00	27.200	0.900	28.1	142.1	5.50	4,213
F	031	Peaked	work floor		16.000	0.000	0.000	12.00	2.00	0.00	14.000	1.000	15.0	161.6	5.80	2,565
F	032	Peaked	work floor		16.000	0.000	0.000	12.00	2.00	0.00	14.000	1.000	15.0	161.6	5.80	2,565
F	033	Peaked	work floor		16.000	0.000	0.000	12.00	2.00	0.00	14.000	1.000	15.0	161.6	5.80	2,565
F	034	Peaked	work floor		16.000	0.000	0.000	12.00	2.00	0.00	14.000	1.000	15.0	161.6	5.80	2,565
F	101	Peaked	work floor		36.000	0.000	0.000	47.70	0.00	0.00	47.700	2.200	49.9	818.2	10.0	44,911
F	102	Peaked	work floor		36.000	0.000	0.000	47.70	0.00	0.00	47.700	2.200	49.9	818.2	10.0	44,911
F	103	Peaked	work floor		36.000	0.000	0.000	47.70	0.00	0.00	47.700	2.200	49.9	818.2	10.0	44,911
F	104	Peaked	work floor		36.000	0.000	0.000	47.70	0.00	0.00	47.700	2.200	49.9	818.2	10.0	44,911
F	105	Peaked	work floor		36.000	0.000	0.000	47.70	0.00	0.00	47.700	2.200	49.9	818.2	10.0	44,911
F	106	Peaked	work floor		36.000	0.000	0.000	47.70	0.00	0.00	47.700	2.200	49.9	818.2	10.0	44,911
F	107	Peaked	work floor		36.000	0.000	0.000	40.00	0.00	0.00	40.000	2.200	42.2	818.2	10.0	37,981

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 3

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.) Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	---	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: New Town

Section: F

	F	108	Peaked	work floor	36.000	0.000	0.000	40.00	0.00	0.00	40.000	2.200	42.2	818.2	10.0	37,981
	F	109	Peaked	work floor	36.000	0.000	0.000	40.00	0.00	0.00	40.000	2.200	42.2	818.2	10.0	37,981
	F	201	Round	bttm manhole	38.700	0.000	0.000	80.80	0.00	0.00	80.800	0.000	80.8	945.6	10.0	84,044
Added	F	202	Round	bttm manhole	36.000	0.000	0.000	90.10	0.00	0.00	90.100	0.000	90.1	818.2	10.0	81,092
Added	F	203	Round	bttm manhole	42.000	0.000	0.000	90.10	0.00	0.00	90.100	0.000	90.1	1113.7	10.0	110,378
Added	F	204	Round	bttm manhole	48.000	0.000	0.000	93.60	0.00	0.00	93.600	0.000	93.6	1454.6	10.0	149,766

Bin count: 50

Facility: New Town Section: F Total: 943,832To Even: 944,000

Section: G

	G	004	Peaked	work floor	22.400	0.000	0.000	31.50	0.00	0.00	31.500	1.300	32.8	316.8	7.20	11,139
	G	005	Peaked	work floor	22.400	0.000	0.000	31.50	0.00	0.00	31.500	1.300	32.8	316.8	7.20	11,139
	G	006	Peaked	work floor	22.400	0.000	0.000	31.50	0.00	0.00	31.500	1.300	32.8	316.8	7.20	11,139
	G	007	Peaked	work floor	22.400	0.000	0.000	31.50	0.00	0.00	31.500	1.300	32.8	316.8	7.20	11,139

Bin count: 4

Facility: New Town Section: G Total: 44,556To Even: 45,000

Section: I

	I	001	Peaked	top of sidewall - round or	23.500	0.000	0.000	20.00	0.00	0.00	20.000	1.400	21.4	348.7	7.50	8,022
	I	002	Peaked	round or peaked ??	23.500	0.000	0.000	20.00	0.00	0.00	20.000	1.400	21.4	348.7	7.50	8,022
	I	003	Peaked	round or peaked ??	23.500	0.000	0.000	20.00	0.00	0.00	20.000	1.400	21.4	348.7	7.50	8,022

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 4

Examiner: 1

PO Box 128
Parshall, ND
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	-------------------------------	--------	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Bin count: 3

Facility: New Town Section: I Total: 24,066

To Even: 25,000

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 5

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.) Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	---	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: Parshall

Section: A

A	001	Square	work floor		0.000	8.000	3.800	60.00	0.00	0.00	60.000	0.000	60.0	24.4	2.50	1,501
A	002	Square	work floor		0.000	9.000	8.000	70.00	0.00	0.00	70.000	0.000	70.0	57.9	4.80	4,248
A	003	Square	work floor		0.000	9.000	4.000	70.00	0.00	0.00	70.000	0.000	70.0	28.9	2.50	2,074
A	004	Square	work floor		0.000	8.200	4.000	55.00	0.00	0.00	55.000	0.000	55.0	26.4	2.50	1,488
A	005	Square	work floor		0.000	8.200	4.000	55.00	0.00	0.00	55.000	0.000	55.0	26.4	2.50	1,488
A	006	Square	work floor		0.000	9.000	4.000	60.00	0.00	0.00	60.000	0.000	60.0	28.9	2.50	1,777
A	007	Square	work floor		0.000	8.200	4.000	47.00	0.00	0.00	47.000	0.000	47.0	26.4	2.50	1,272
A	008	Square	work floor		0.000	9.000	4.000	60.00	0.00	0.00	60.000	0.000	60.0	28.9	2.50	1,777
A	009	Square	work floor		0.000	9.000	4.000	60.00	0.00	0.00	60.000	0.000	60.0	28.9	2.50	1,777
A	010	Square	work floor		0.000	8.000	4.800	52.00	0.00	0.00	52.000	0.000	52.0	30.9	2.50	1,647
A	011	Square	work floor		0.000	9.000	8.000	70.00	0.00	0.00	70.000	0.000	70.0	57.9	4.80	4,248
A	012	Square	work floor		0.000	8.200	4.000	47.00	0.00	0.00	47.000	0.000	47.0	26.4	2.50	1,272
A	013	Square	work floor		0.000	6.000	3.800	52.00	0.00	0.00	52.000	0.000	52.0	18.3	2.00	971
A	014	Square	work floor		0.000	9.000	8.000	70.00	0.00	0.00	70.000	0.000	70.0	57.9	4.80	4,248
A	015	Square	work floor		0.000	8.200	4.000	47.00	0.00	0.00	47.000	0.000	47.0	26.4	2.50	1,272
A	016	Square	work floor		0.000	9.000	4.000	55.00	0.00	0.00	55.000	0.000	55.0	28.9	2.50	1,630
A	017	Square	work floor		0.000	8.200	4.000	47.00	0.00	0.00	47.000	0.000	47.0	26.4	2.50	1,272
A	018	Square	work floor		0.000	9.000	4.000	55.00	0.00	0.00	55.000	0.000	55.0	28.9	2.50	1,630
A	019	Square	work floor		0.000	9.000	4.000	55.00	0.00	0.00	55.000	0.000	55.0	28.9	2.50	1,630
A	020	Square	work floor		0.000	8.200	4.000	55.00	0.00	0.00	55.000	0.000	55.0	26.4	2.50	1,488
A	021	Square	work floor		0.000	9.000	4.000	55.00	0.00	0.00	55.000	0.000	55.0	28.9	2.50	1,630
A	022	Square	work floor		0.000	8.200	4.000	55.00	0.00	0.00	55.000	0.000	55.0	26.4	2.50	1,488

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 6

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width									

Facility: Parshall

Section: A

A	023	Square	work floor		0.000	9.000	8.000	70.00	0.00	0.00	70.000	0.000	70.0	57.9	4.80	4,248
A	024	Square	work floor		0.000	8.000	4.800	60.00	0.00	0.00	60.000	0.000	60.0	30.9	2.50	1,900
A	101	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	102	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	103	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	104	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	105	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	106	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	107	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	108	Round	work floor		16.300	0.000	0.000	93.00	0.00	0.00	93.000	0.000	93.0	167.7	5.80	16,501
A	109	Irregular	work floor - interstice		12.000	0.000	0.000	92.00	0.00	0.00	92.000	0.000	92.0	12.0	2.00	1,126
A	110	Irregular	work floor - interstice		62.000	0.000	0.000	92.00	0.00	0.00	92.000	0.000	92.0	62.0	4.80	5,978
A	111	Irregular	work floor - interstice		24.000	0.000	0.000	92.00	0.00	0.00	92.000	0.000	92.0	24.0	2.00	2,252
A	112	Irregular	work floor - interstice		62.000	0.000	0.000	92.00	0.00	0.00	92.000	0.000	92.0	62.0	4.80	5,978
A	113	Irregular	work floor - interstice		24.000	0.000	0.000	92.00	0.00	0.00	92.000	0.000	92.0	24.0	2.00	2,252
A	114	Irregular	work floor - interstice		62.000	0.000	0.000	92.00	0.00	0.00	92.000	0.000	92.0	62.0	4.80	5,978
A	115	Irregular	work floor - interstice		50.000	0.000	0.000	92.00	0.00	0.00	92.000	0.000	92.0	50.0	4.20	4,793
A	201	Peaked	top of sidewall		30.000	0.000	0.000	66.70	0.00	0.00	66.700	1.800	68.5	568.2	9.00	42,425
A	202	Peaked	top of sidewall		33.000	0.000	0.000	66.70	0.00	0.00	66.700	2.000	68.7	687.5	9.50	51,718
A	203	Peaked	top of sidewall		36.000	0.000	0.000	64.00	0.00	0.00	64.000	2.200	66.2	818.2	10.0	59,582
A	204	Peaked	top of sidewall		42.000	0.000	0.000	64.00	0.00	0.00	64.000	2.500	66.5	1113.7	10.0	81,467
A	205	Peaked	top of sidewall		45.000	0.000	0.000	66.70	0.00	0.00	66.700	2.700	69.4	1278.5	10.0	97,601

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 7

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width									

Facility: Parshall

Section: A

Added	A	301	Peaked	top of sidewall	48.000	0.000	0.000	88.10	0.00	0.00	88.100	3.400	91.5	1454.6	10.0	146,406
Added	A	302	Peaked	top of sidewall	48.000	0.000	0.000	88.10	0.00	0.00	88.100	3.400	91.5	1454.6	10.0	146,406
Added	A	303	Peaked	top of sidewall	48.000	0.000	0.000	88.10	0.00	0.00	88.100	3.400	91.5	1454.6	10.0	146,406
Added	A	304	Peaked	top of sidewall	48.000	0.000	0.000	88.10	0.00	0.00	88.100	3.400	91.5	1454.6	10.0	146,406

Bin count: 48

Facility: Parshall Section: A Total: **1,126,758**To Even: **1,127,000**

Section: B

B	000 East	Round	btm inspection hole	32.500	0.000	0.000	80.00	0.00	0.00	80.000	0.000	80.0	666.9	9.50	58,420
B	000 West	Round	btm inspection hole	32.500	0.000	0.000	80.00	0.00	0.00	80.000	0.000	80.0	666.9	9.50	58,420
B	002	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	003	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	004	Irregular	work floor	73.000	0.000	0.000	75.00	0.00	0.00	75.000	0.000	75.0	73.0	5.20	5,760
B	005	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	006	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	007	Irregular	work floor - interstice	84.000	0.000	0.000	75.00	0.00	0.00	75.000	0.000	75.0	84.0	5.80	6,665
B	008	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	009	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	010	Irregular	work floor - irregular	32.000	0.000	0.000	38.00	0.00	0.00	38.000	0.000	38.0	32.0	2.50	1,246
B	011	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	012	Square	work floor	0.000	7.300	3.800	54.00	0.00	0.00	54.000	0.000	54.0	22.3	2.00	1,228
B	013	Irregular	work floor - irregular	84.000	0.000	0.000	75.00	0.00	0.00	75.000	0.000	75.0	84.0	5.80	6,665

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 8

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width									

Facility: Parshall

Section: B

B	014 T	Square	work floor	0.000	6.400	3.000	38.00	0.00	0.00	38.000	0.000	38.0	15.4	2.00	597
B	014 B	Irregular	work floor -top 38'	47.000	0.000	0.000	34.00	0.00	0.00	34.000	0.000	34.0	47.0	4.00	1,662
B	015	Square	work floor	0.000	3.500	3.500	54.00	0.00	0.00	54.000	0.000	54.0	9.8	2.00	540
B	016	Irregular	work floor - irregular	73.000	0.000	0.000	75.00	0.00	0.00	75.000	0.000	75.0	73.0	5.20	5,760
B	017	Square	work floor	0.000	3.500	3.500	54.00	0.00	0.00	54.000	0.000	54.0	9.8	2.00	540
B	018	Square	work floor	0.000	3.500	3.500	54.00	0.00	0.00	54.000	0.000	54.0	9.8	2.00	540
B	020	Square	work floor	0.000	3.500	3.500	54.00	0.00	0.00	54.000	0.000	54.0	9.8	2.00	540
B	101	Round	top of slab	26.100	0.000	0.000	125.0	0.00	0.00	125.00	0.000	125.0	430.1	8.20	58,172
B	102	Round	top of slab	26.100	0.000	0.000	125.0	0.00	0.00	125.00	0.000	125.0	430.1	8.20	58,172
B	201	Round	top of slab	38.200	0.000	0.000	110.6	0.00	0.00	110.60	0.000	110.6	921.3	10.0	112,086
B	202	Round	top of slab	38.200	0.000	0.000	110.6	0.00	0.00	110.60	0.000	110.6	921.3	10.0	112,086
B	203	Round	top of slab	38.200	0.000	0.000	109.9	0.00	0.00	109.90	0.000	109.9	921.3	10.0	111,376
B	204	Round	top of slab	38.200	0.000	0.000	109.9	0.00	0.00	109.90	0.000	109.9	921.3	10.0	111,376
B	205	Irregular	top of slab	224.80	0.000	0.000	108.6	0.00	0.00	108.60	0.000	108.6	224.8	7.00	26,122
B	206	Irregular	top of slab	107.60	0.000	0.000	108.6	0.00	0.00	108.60	0.000	108.6	107.6	6.20	12,409
B	207	Irregular	top of slab	107.60	0.000	0.000	108.6	0.00	0.00	108.60	0.000	108.6	107.6	6.20	12,409
B	208	Irregular	top of slab	139.00	13.15	13.15	108.6	0.00	0.00	108.60	0.000	108.6	139.0	6.50	16,076
B	209	Irregular	top of slab	126.60	0.000	0.000	53.00	0.00	0.00	53.000	0.000	53.0	126.6	6.50	7,146

Bin count: 32

Facility: Parshall Section: B Total: 794,609

To Even: 795,000

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 9

Examiner: 1

PO Box 128
Parshall, ND
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.) Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	---	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: Parshall

Section: C

C	001	Peaked	top of slab		14.500	0.000	0.000	18.00	2.50	0.00	20.500	0.900	21.4	132.7	5.50	2,996
C	002	Peaked	top of slab		14.500	0.000	0.000	18.00	2.50	0.00	20.500	0.900	21.4	132.7	5.50	2,996
C	003	Peaked	top of slab		14.500	0.000	0.000	18.00	2.50	0.00	20.500	0.900	21.4	132.7	5.50	2,996
C	004	Peaked	top of slab		14.500	0.000	0.000	18.00	2.50	0.00	20.500	0.900	21.4	132.7	5.50	2,996
C	005	Peaked	top of slab		14.500	0.000	0.000	18.00	2.50	0.00	20.500	0.900	21.4	132.7	5.50	2,996
C	006	Peaked	top of slab		14.500	0.000	0.000	18.00	2.50	0.00	20.500	0.900	21.4	132.7	5.50	2,996
C	007	Peaked	top of sidewall		14.000	0.000	0.000	12.00	1.70	0.00	13.700	0.800	14.5	123.7	5.50	1,893
C	008	Peaked	top of sidewall		14.000	0.000	0.000	12.00	1.70	0.00	13.700	0.800	14.5	123.7	5.50	1,893
C	009	Peaked	top of slab		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	010	Peaked	top of slab		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	011	Peaked	top of slab		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	012	Peaked	top of slab		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	013	Peaked	top of slab		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	014	Peaked	top of slab		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	015	Peaked	top of slab		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	016	Peaked	top of sidewall		16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
C	017	Peaked	top of sidewall		15.900	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	159.6	5.80	3,884
C	018	Peaked	top of sidewall		15.900	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	159.6	5.80	3,884
C	019	Peaked	top of sidewall		15.900	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	159.6	5.80	3,884
C	020	Peaked	top of sidewall		15.900	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	159.6	5.80	3,884
C	021	Peaked	top of sidewall		15.900	0.000	0.000	20.00	2.00	0.00	22.000	1.000	23.0	159.6	5.80	3,884

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 10

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.) Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack	
Bin count:		21													Facility: Parshall Section: C Total:	67,166
														To Even:	68,000	

Section: D

D	101	Flat	top of sidewall catwalk 27.0'	0.000	80.90	70.00	20.30	0.00	0.00	20.300	0.000	20.3	4552.3	10.0	101,653	
D	102	Flat	top of sidewall catwalk 27.0'	27.000	148.0	70.00	10.20	0.00	0.00	10.200	11.40	21.6	8328.0	10.0	197,874	
Bin count:		2													Facility: Parshall Section: D Total:	299,527
														To Even:	300,000	

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 11

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack	
					Length	Width										
<u>Facility: Ross</u>																
<u>Section: J</u>																
J	001		Square	work floor	0.000	11.00	3.500	51.00	0.00	0.00	51.000	0.000	51.0	30.9	2.50	1,615
J	003		Square	work floor	0.000	11.00	7.300	68.00	0.00	0.00	68.000	0.000	68.0	64.5	5.00	4,605
J	004		Square	work floor	0.000	11.00	5.500	68.00	0.00	0.00	68.000	0.000	68.0	48.6	4.20	3,444
J	005		Square	work floor	0.000	11.50	11.00	65.00	0.00	0.00	65.000	0.000	65.0	101.7	6.00	7,008
J	006		Square	work floor	0.000	12.30	7.300	52.00	0.00	0.00	52.000	0.000	52.0	72.2	5.20	3,949
J	008		Square	work floor	0.000	12.30	11.50	50.00	0.00	0.00	50.000	0.000	50.0	113.7	6.20	6,037
J	009		Square	work floor	0.000	12.30	5.500	52.00	0.00	0.00	52.000	0.000	52.0	54.4	4.50	2,956
J	010		Square	work floor	0.000	11.00	7.300	68.00	0.00	0.00	68.000	0.000	68.0	64.5	5.00	4,605
J	011		Square	work floor	0.000	11.50	11.00	65.00	0.00	0.00	65.000	0.000	65.0	101.7	6.00	7,008
J	012		Square	work floor	0.000	11.00	5.500	68.00	0.00	0.00	68.000	0.000	68.0	48.6	4.20	3,444
J	013		Square	work floor climb under scale	0.000	11.00	6.700	20.00	0.00	0.00	20.000	0.000	20.0	59.2	4.80	1,241
J	014		Square	work floor climb under scale	0.000	11.00	6.700	20.00	0.00	0.00	20.000	0.000	20.0	59.2	4.80	1,241
J	015		Square	work floor	0.000	11.00	7.300	68.00	0.00	0.00	68.000	0.000	68.0	64.5	5.00	4,605
J	016		Square	work floor	0.000	11.00	5.500	68.00	0.00	0.00	68.000	0.000	68.0	48.6	4.20	3,444
J	017		Square	work floor	0.000	11.50	11.00	65.00	0.00	0.00	65.000	0.000	65.0	101.7	6.00	7,008
J	018		Square	work floor	0.000	12.30	11.50	50.00	0.00	0.00	50.000	0.000	50.0	113.7	6.20	6,037
J	019		Square	work floor	0.000	12.30	5.500	52.00	0.00	0.00	52.000	0.000	52.0	54.4	4.50	2,956
J	020		Square	work floor	0.000	12.30	7.300	52.00	0.00	0.00	52.000	0.000	52.0	72.2	5.20	3,949
J	021		Square	work floor	0.000	11.00	5.500	68.00	0.00	0.00	68.000	0.000	68.0	48.6	4.20	3,444
J	022		Square	work floor	0.000	11.50	11.00	65.00	0.00	0.00	65.000	0.000	65.0	101.7	6.00	7,008
J	023 T		Square	work floor	0.000	7.300	5.800	18.00	0.00	0.00	18.000	0.000	18.0	34.0	2.50	627
J	023 B		Square	work floor - top 18'	0.000	11.00	7.300	50.00	0.00	0.00	50.000	0.000	50.0	64.5	5.00	3,386

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 12

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	-------------------------------	--------	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: Ross

Section: J

J	024	Square	work floor		0.000	7.300	5.000	18.00	0.00	0.00	18.000	0.000	18.0	29.3	2.50	540
J	025 T	Square	work floor		0.000	5.000	3.500	25.00	0.00	0.00	25.000	0.000	25.0	14.1	2.00	360
J	025 B	Square	work floor - top 25'		0.000	11.00	3.500	26.00	0.00	0.00	26.000	0.000	26.0	30.9	2.50	823
J	026	Square	work floor		0.000	5.500	3.500	22.00	0.00	0.00	22.000	0.000	22.0	15.5	2.00	348
J	027	Square	work floor		0.000	12.30	6.700	52.00	0.00	0.00	52.000	0.000	52.0	66.2	5.00	3,614
J	028	Square	work floor		0.000	12.30	6.700	52.00	0.00	0.00	52.000	0.000	52.0	66.2	5.00	3,614
J	201 T	Square	work floor		0.000	17.00	15.00	61.00	0.00	0.00	61.000	0.000	61.0	205.0	7.00	13,380
J	201 B	Square	work floor- top 61'		0.000	14.90	13.60	8.000	0.00	0.00	8.000	0.000	8.0	162.9	7.00	1,394
J	202 T	Square	work floor		0.000	17.00	15.40	61.00	0.00	0.00	61.000	0.000	61.0	210.5	7.00	13,740
J	202 B	Square	work floor -top 61'		0.000	15.30	13.60	8.000	0.00	0.00	8.000	0.000	8.0	167.3	7.00	1,432
J	203 T	Square	work floor		0.000	17.00	15.40	61.00	0.00	0.00	61.000	0.000	61.0	210.5	7.00	13,740
J	203 B	Square	work floor - top 61'		0.000	15.30	13.60	8.000	0.00	0.00	8.000	0.000	8.0	167.3	7.00	1,432
J	204 T	Square	work floor		0.000	17.00	15.40	61.00	0.00	0.00	61.000	0.000	61.0	210.5	7.00	13,740
J	204 B	Square	work floor -top 61'		0.000	15.30	13.60	8.000	0.00	0.00	8.000	0.000	8.0	167.3	7.00	1,432
J	205 T	Square	work floor		0.000	17.00	15.00	61.00	0.00	0.00	61.000	0.000	61.0	205.0	7.00	13,380
J	205 B	Square	work floor - top 61'		0.000	14.90	13.60	8.000	0.00	0.00	8.000	0.000	8.0	162.9	7.00	1,394
J	206 T	Square	work floor		0.000	17.00	15.00	61.00	0.00	0.00	61.000	0.000	61.0	205.0	7.00	13,380
J	206 B	Square	work floor - top 61'		0.000	14.90	13.60	8.000	0.00	0.00	8.000	0.000	8.0	162.9	7.00	1,394
J	207 T	Square	work floor		0.000	17.00	15.40	61.00	0.00	0.00	61.000	0.000	61.0	210.5	7.00	13,740
J	207 B	Square	work floor - top 61'		0.000	15.30	13.60	8.000	0.00	0.00	8.000	0.000	8.0	167.3	7.00	1,432
J	208 T	Square	work floor		0.000	17.00	15.40	61.00	0.00	0.00	61.000	0.000	61.0	210.5	7.00	13,740
J	208 B	Square	work floor - top 61'		0.000	15.30	13.60	8.000	0.00	0.00	8.000	0.000	8.0	167.3	7.00	1,432

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 13

Examiner: 1

PO Box 128

Parshall, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.) Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	---	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: Ross

Section: J

J	209 T	Square	work floor		0.000	17.00	15.40	61.00	0.00	0.00	61.000	0.000	61.0	210.5	7.00	13,740
J	209 B	Square	work floor -top 61'		0.000	15.30	13.60	8.000	0.00	0.00	8.000	0.000	8.0	167.3	7.00	1,432
J	210 T	Square	work floor		0.000	17.00	15.00	61.00	0.00	0.00	61.000	0.000	61.0	205.0	7.00	13,380
J	210 B	Square	work floor - top 61'		0.000	14.90	13.60	8.000	0.00	0.00	8.000	0.000	8.0	162.9	7.00	1,394
J	301	Peaked	top of sidewall Peaked ??		35.900	0.000	0.000	64.50	0.00	0.00	64.500	2.200	66.7	813.7	10.0	59,701
J	302	Peaked	top of sidewall Peaked ??		35.900	0.000	0.000	64.50	0.00	0.00	64.500	2.200	66.7	813.7	10.0	59,701
J	303	Peaked	top of sidewall Peaked ??		35.900	0.000	0.000	64.50	0.00	0.00	64.500	2.200	66.7	813.7	10.0	59,701
J	304	Peaked	top of sidewall Peaked ??		35.900	0.000	0.000	64.50	0.00	0.00	64.500	2.200	66.7	813.7	10.0	59,701

Bin count: 52

Facility: Ross Section: J Total: **487,848**To Even: **488,000**

Section: K

K	001	Square	work floor		0.000	11.50	3.700	48.00	0.00	0.00	48.000	0.000	48.0	34.2	3.00	1,691
K	003	Square	work floor		0.000	13.30	11.50	68.00	0.00	0.00	68.000	0.000	68.0	123.0	6.50	8,908
K	004	Square	work floor		0.000	13.30	11.00	68.00	0.00	0.00	68.000	0.000	68.0	117.6	6.20	8,493
K	006	Square	work floor		0.000	13.30	11.50	68.00	0.00	0.00	68.000	0.000	68.0	123.0	6.50	8,908
K	007	Square	work floor		0.000	11.00	6.300	50.00	0.00	0.00	50.000	0.000	50.0	55.7	4.80	2,919
K	008	Square	work floor		0.000	11.50	6.300	48.00	0.00	0.00	48.000	0.000	48.0	58.2	4.80	2,928
K	009	Square	work floor		0.000	11.00	6.300	50.00	0.00	0.00	50.000	0.000	50.0	55.7	4.80	2,919
K	011	Square	work floor		0.000	13.30	11.50	68.00	0.00	0.00	68.000	0.000	68.0	123.0	6.50	8,908
K	012 T	Square	work floor		0.000	11.50	6.300	12.00	0.00	0.00	12.000	0.000	12.0	58.2	4.80	732
K	012 B	Square	work floor		0.000	11.50	6.300	36.00	0.00	0.00	36.000	0.000	36.0	58.2	4.80	2,196

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 14

Examiner: 1

PO Box 128
Parshall, ND
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width									

Facility: Ross

Section: K

K	013	Square	work floor	0.000	11.00	6.400	50.00	0.00	0.00	50.000	0.000	50.0	56.6	4.80	2,966
K	014	Square	work floor	0.000	11.00	6.400	50.00	0.00	0.00	50.000	0.000	50.0	56.6	4.80	2,966
K	015	Square	work floor	0.000	7.000	3.700	48.00	0.00	0.00	48.000	0.000	48.0	20.8	2.00	1,018
K	016	Square	work floor	0.000	13.30	11.50	68.00	0.00	0.00	68.000	0.000	68.0	123.0	6.50	8,908
K	017	Square	work floor	0.000	5.000	4.500	30.00	0.00	0.00	30.000	0.000	30.0	18.1	2.00	554
K	018	Square	work floor	0.000	4.500	3.700	30.00	0.00	0.00	30.000	0.000	30.0	13.4	2.00	410

Bin count: 16

Facility: Ross Section: K Total: **65,424**To Even: **66,000**

Section: L

L	H001	Peaked	work floor	14.500	0.000	0.000	25.00	2.00	0.00	27.000	0.900	27.9	132.7	5.50	3,906
L	H002	Peaked	work floor	14.500	0.000	0.000	25.00	2.00	0.00	27.000	0.900	27.9	132.7	5.50	3,906
L	H003	Peaked	work floor	14.500	0.000	0.000	25.00	2.00	0.00	27.000	0.900	27.9	132.7	5.50	3,906
L	H004	Peaked	work floor	16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
L	H005	Peaked	work floor	16.000	0.000	0.000	16.00	2.00	0.00	18.000	1.000	19.0	161.6	5.80	3,248
L	H006	Peaked	work floor	13.500	0.000	0.000	12.00	1.80	0.00	13.800	0.800	14.6	115.1	5.20	1,767
L	H007	Peaked	work floor	13.500	0.000	0.000	12.00	1.80	0.00	13.800	0.800	14.6	115.1	5.20	1,767
L	H008	Peaked	work floor	13.500	0.000	0.000	12.00	1.80	0.00	13.800	0.800	14.6	115.1	5.20	1,767
L	H009	Peaked	work floor	13.500	0.000	0.000	12.00	1.80	0.00	13.800	0.800	14.6	115.1	5.20	1,767

Bin count: 9

Facility: Ross Section: L Total: **25,282**To Even: **26,000**

Exam Date:07/30/2012

Dakota Quality Grain Cooperative

Page: 15

Examiner: 1

PO Box 128
Parshall, ND
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.) Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	---	-------	--------------	----------------------	----------------------	--------------------	--------------------	------------------------	------------------------	---------------	------------------------------

Facility: Ross

Section: M

M	001	Square	top of slab		88.800	10.40	10.70	85.00	4.30	0.70	88.600	0.000	88.6	89.5	5.80	8,390
M	002	Square	top of slab		88.800	10.40	10.70	85.00	4.30	0.70	88.600	0.000	88.6	89.5	5.80	8,390
M	003	Square	top of slab		102.50	12.00	10.70	85.00	4.30	0.60	88.700	0.000	88.7	103.2	6.00	9,703
M	004	Square	top of slab		102.50	12.00	10.70	85.00	4.30	0.60	88.700	0.000	88.7	103.2	6.00	9,703
M	005	Square	top of slab		102.50	12.00	10.70	85.00	4.30	0.60	88.700	0.000	88.7	103.2	6.00	9,703
M	006	Square	top of slab		102.50	12.00	10.70	85.00	4.30	0.60	88.700	0.000	88.7	103.2	6.00	9,703
M	008	Round	top of slab		22.000	0.000	0.000	123.0	0.00	0.00	123.00	0.000	123.0	305.6	7.20	40,295
M	009	Round	top of slab		22.000	0.000	0.000	39.00	2.70	0.00	41.700	0.000	41.7	305.6	7.20	13,662
M	010	Irregular	top of slab		54.800	8.257	8.257	122.5	0.00	0.00	122.50	0.000	122.5	54.8	4.50	7,015
M	011	Irregular	top of slab		124.10	12.43	12.43	122.0	0.00	0.00	122.00	0.000	122.0	124.1	6.50	16,124
M	012	Irregular	top of slab		124.10	12.43	12.43	122.0	0.00	0.00	122.00	0.000	122.0	124.1	6.50	16,124
M	013	Irregular	top of slab		124.10	12.43	12.43	122.0	0.00	0.00	122.00	0.000	122.0	124.1	6.50	16,124
M	014	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792
M	015	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792
M	016	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792
M	017	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792
M	018	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792
M	019	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792
M	020	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792
M	021	Round	top of slab		28.000	0.000	0.000	122.5	0.00	0.00	122.50	0.000	122.5	495.0	8.50	65,792

Bin count: 20

Facility: Ross Section: M Total: 691,272

To Even: 692,000

Overall Licensed Bin Capacity for:

Dakota Quality Grain Cooperative

Bin count: 257

Licensed Capacity:

(includes pack)

4,570,340 Bu.

Licensed Capacity (to even):

(includes pack and section totals are rounded up to next highest 1000)

4,576,000 Bu.
