

**TEST REPORT**

Invoice Number **14603**

Operator No. <b>1388</b>	Date <b>2-19-13</b>	Date Last Tested (P&S Only)	Check All That Apply	
Name of Business <b>Environmental Materials Inc.</b>			<input type="checkbox"/> Self-Certification <input type="checkbox"/> Non-Commercial <input type="checkbox"/> Equipment Repair <input checked="" type="checkbox"/> New Installation <input type="checkbox"/> Routine Service <input type="checkbox"/> Annual <input type="checkbox"/> Semi-Annual <input type="checkbox"/> Rejected Equipment   Tag # (Attach) _____ <input type="checkbox"/> Service Contract?   Expires _____	
Location of Device <b>Killdeer</b>			Variance Posted	
Mailing Address <b>357 102X Ave</b>			Date of Variance <b>N/A</b>	
City <b>Killdeer</b>	State <b>ND</b>	Zip Code <b>58640</b>	PSC Device Code	
County <b>Dunn</b>	Telephone Number <b>406-697-3585</b>		Quantity (of like devices)	

Make(s) <b>Avery Weigh-Tronix</b>	Regulating Element(s) <b>Electronic</b>	Serial Number(s) <b>8745</b>	Lever System <b>NO</b>	
No. of Sections <b>3</b>	<input type="checkbox"/> Monorail/Track <input type="checkbox"/> MTD <input type="checkbox"/> Hopper <input type="checkbox"/> Livestock <input checked="" type="checkbox"/> Platform <input type="checkbox"/> Axle Load <input type="checkbox"/> Aux. Beam <input type="checkbox"/> MT <input type="checkbox"/> Hanging <input type="checkbox"/> Counter Scale <input type="checkbox"/> Dormant/Deck <input type="checkbox"/> Other	Multiple	Pit Depth <b>N/A</b>	
Capacity & Min. Grad. <b>120,000lb Cap X 20lb Grad</b>		Class <b>III L</b>	Size of Platform <b>70'</b>	Approaches (Length/Condition) <b>10' level with scale / concrete</b>
Printer Model <b>TM-U295</b>	Printer Serial Number <b>J9KFO91964</b>	Wind <b>3mph SW</b>	Temperature <b>39°</b>	Device Location <b>Killdeer Facility</b>
SR (Sensitivity Response) OR Discrimination Test ZERO LOAD = _____ lb.   LOADED = _____ lb.		Motion Detection Range = _____ lb.	AZSM (auto zero) Range = <b>60</b> lb.	

Device/ Load Position	Amount of Test Equipment Used	Actual Readings		Device/ Load Position	Amount of Test Equipment Used	Actual Readings	
		As Found	As Left			As Found	As Left
1	20,000 lb	20,000 lb	20,000 lb				
2	20,000 lb	20,000 lb	20,000 lb				
3	20,000 lb	20,000 lb	20,000 lb				
4	20,000 lb	20,000 lb	20,000 lb				
5	20,000 lb	20,000 lb	20,000 lb				
6	20,000 lb	20,000 lb	20,000 lb				
7	20,000 lb	20,000 lb	20,000 lb				
8	20,000 lb	20,000 lb	20,000 lb				

STRAIN LOAD TEST	Section #	Section #	Section #	Section #
Empty Truck Weight	16,040	16,040	16,040	16,040
Total Test Weight Added	20,000	20,000	20,000	20,000
Truck Plus Weights	36,040	36,040	36,040	36,040
Error on Added Test Weights	0	0	0	0

I hereby declare the statements made here are correct:

Are there any other jurisdictional devices at this location that require testing?  Yes    No

HAS SECURITY SEAL AND STICKER BEEN APPLIED?  YES    NO

Approved    Rejected   Service Agency (Print)  
**Rocky Mtn. Scale Works**

Inspector/Permit Holder Signature  
**Dylan Moses**   Permit No.  
**1724**

Owner/Operator Signature  
**Harry Reynolds**

**REMARKS & ADJUSTMENTS MADE**

1 Copy to Public Service Commission, 600 E. Boulevard Avenue, Bismarck, ND 58505 / 1 Copy to Owner/Operator