

Exam Date:09/16/2013

Dakota Midland Grain, LLC

Page: 1

Examiner: 1

PO Box 188

Voltaire, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).			Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width										
	B	001	Square	bottom of slab	0.000	20.00	16.00	40.00	2.50	0.25	42.250	0.000	42.3	257.2	7.00	11,642
	B	002	Square	bottom of slab	0.000	14.00	9.700	92.20	2.70	0.35	94.550	0.000	94.6	109.2	6.20	10,970
	B	003	Square	bottom of slab	0.000	14.00	9.700	92.20	2.70	0.35	94.550	0.000	94.6	109.2	6.20	10,970
	B	004	Square	bottom of slab	0.000	14.00	9.700	92.20	2.70	0.35	94.550	0.000	94.6	109.2	6.20	10,970
	B	005	Square	bottom of slab	0.000	14.00	9.700	92.20	2.70	0.35	94.550	0.000	94.6	109.2	6.20	10,970
	B	006	Irregular-R	bottom of slab	34.800	7.424	0.000	84.20	2.20	0.00	86.400	0.000	86.4	34.8	4.50	3,142
	B	007	Irregular-R	bottom of slab	73.100	10.76	0.000	137.0	0.00	0.00	137.00	0.000	137.0	73.1	4.80	10,496
	B	008	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
	B	009	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
	B	010	Interstice	bottom of slab	32.400	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	181.1	5.80	26,250
	B	011	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
	B	012	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
	B	013	Interstice	bottom of slab	32.400	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	181.1	5.80	26,250
	B	014	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
	B	015	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
	B	016	Interstice	bottom of slab	32.400	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	181.1	5.80	26,250
	B	017	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
	B	018	Round	bottom of slab	34.000	0.000	0.000	137.0	0.00	0.00	137.00	0.000	137.0	729.8	9.80	109,781
Added	B	019	Round	bottom of slab	36.000	0.000	0.000	130.5	0.00	0.60	129.90	0.000	129.9	818.2	10.0	116,912
Added	B	020	Round	bottom of slab	36.000	0.000	0.000	130.5	0.00	0.60	129.90	0.000	129.9	818.2	10.0	116,912
Added	B	021	Interstice	bottom of slab	32.700	0.000	0.000	125.8	2.60	0.00	128.40	0.000	128.4	184.5	5.80	25,064
Added	B	022	Round	bottom of slab	36.000	0.000	0.000	130.5	0.00	0.60	129.90	0.000	129.9	818.2	10.0	116,912
Added	B	023	Round	bottom of slab	36.000	0.000	0.000	130.5	0.00	0.60	129.90	0.000	129.9	818.2	10.0	116,912

**Section: B**

Exam Date:09/16/2013

Dakota Midland Grain, LLC

Page: 2

Examiner: 1

PO Box 188  
Voltaire, ND  
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack	
					Length	Width										
Added	B	024	Interstice	bottom of slab	32.700	0.000	0.000	125.8	2.60	0.00	128.40	0.000	128.4	184.5	5.80	25,064
Added	B	025	Round	bottom of slab	36.000	0.000	0.000	130.5	0.00	0.60	129.90	0.000	129.9	818.2	10.0	116,912
Added	B	026	Round	bottom of slab	36.000	0.000	0.000	130.5	0.00	0.60	129.90	0.000	129.9	818.2	10.0	116,912
Added	B	027	Round	bottom of slab	76.000	0.000	0.000	133.5	0.00	0.00	133.50	0.000	133.5	3646.7	10.0	535,517
Added	B	027 A	Irregular	bottom of slab	38.900	6.956	6.956	125.8	3.80	0.00	129.60	0.000	129.6	38.9	3.00	5,192

Bin count: 28

Facility: Surrey Section: B Total: 2,318,467To Even: 2,319,000**Section: C**

C	002	Square	work floor	0.000	9.100	4.100	51.00	0.00	0.00	51.000	0.000	51.0	30.0	2.50	1,568
C	004 T	Square	work floor	0.000	9.100	8.700	54.00	0.00	0.00	54.000	0.000	54.0	63.6	5.00	3,606
C	004 B	Square	work floor- top 54'	0.000	9.100	13.10	15.00	0.00	0.00	15.000	0.000	15.0	95.8	6.00	1,523
C	005	Square	work floor	0.000	13.10	6.000	51.00	0.00	0.00	51.000	0.000	51.0	63.2	5.00	3,384
C	006	Square	work floor	0.000	7.800	6.000	52.00	0.00	0.00	52.000	0.000	52.0	37.6	3.00	2,014
C	008	Square	work floor	0.000	13.10	6.000	51.00	0.00	0.00	51.000	0.000	51.0	63.2	5.00	3,384
C	009	Square	work floor	0.000	13.10	9.000	69.00	0.00	0.00	69.000	0.000	69.0	94.8	6.00	6,933
C	010	Square	work floor	0.000	7.800	6.000	52.00	0.00	0.00	52.000	0.000	52.0	37.6	3.00	2,014
C	011	Square	work floor	0.000	9.000	7.800	52.00	0.00	0.00	52.000	0.000	52.0	56.4	4.80	3,074
C	014 T	Irregular	work floor 9x7.3 with obstruct	17.600	0.000	0.000	15.00	0.00	0.00	15.000	0.000	15.0	17.6	2.00	269
C	014 B	Square	work floor - top 15'	0.000	9.000	7.300	37.00	0.00	0.00	37.000	0.000	37.0	52.8	4.50	2,042
C	016	Square	work floor	0.000	9.000	13.10	69.00	0.00	0.00	69.000	0.000	69.0	94.8	6.00	6,933
C	017	Square	work floor	0.000	7.300	6.000	52.00	0.00	0.00	52.000	0.000	52.0	35.2	3.00	1,885
C	018	Square	work floor	0.000	13.10	12.20	70.00	0.00	0.00	70.000	0.000	70.0	128.5	6.50	9,580

Exam Date:09/16/2013

Dakota Midland Grain, LLC

Page: 3

Examiner: 1

PO Box 188

Voltaire, ND

County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)		Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack	
					Length	Width										
	C	020	Square	work floor	0.000	7.300	6.000	52.00	0.00	0.00	52.000	0.000	52.0	35.2	3.00	1,885
	C	021	Square	work floor	0.000	13.10	9.100	69.00	0.00	0.00	69.000	0.000	69.0	95.8	6.00	7,007
	C	023	Square	work floor	0.000	9.100	3.800	50.00	0.00	0.00	50.000	0.000	50.0	27.8	2.50	1,425
	C	101 T	Square	work floor	0.000	12.50	9.500	33.50	0.00	0.00	33.500	0.000	33.5	95.5	6.00	3,391
	C	101 B	Square	work floor - top 33.5'	0.000	9.500	9.200	7.500	0.00	0.00	7.500	0.000	7.5	70.3	5.20	554
	C	102	Square	work floor	0.000	12.40	9.500	41.00	0.00	0.00	41.000	0.000	41.0	94.7	6.00	4,116
	C	103 T	Square	work floor	0.000	12.50	9.700	33.50	0.00	0.00	33.500	0.000	33.5	97.5	6.00	3,462
	C	103 B	Square	work floor -top 33.5'	0.000	9.700	9.200	7.500	0.00	0.00	7.500	0.000	7.5	71.7	5.20	566
	C	104	Square	work floor	0.000	12.40	9.700	41.00	0.00	0.00	41.000	0.000	41.0	96.7	6.00	4,203
	C	105 T	Square	work floor	0.000	12.50	9.700	33.50	0.00	0.00	33.500	0.000	33.5	97.5	6.00	3,462
	C	105 B	Square	work floor -top 33.5'	0.000	9.700	9.200	7.500	0.00	0.00	7.500	0.000	7.5	71.7	5.20	566
	C	106	Square	work floor	0.000	12.40	9.700	41.00	0.00	0.00	41.000	0.000	41.0	96.7	6.00	4,203
	C	107 T	Square	work floor	0.000	12.50	9.700	33.50	0.00	0.00	33.500	0.000	33.5	97.5	6.00	3,462
	C	107 B	Square	work floor - top 33.5'	0.000	9.700	9.200	7.500	0.00	0.00	7.500	0.000	7.5	71.7	5.20	566
	C	108	Square	work floor	0.000	12.40	9.700	41.00	0.00	0.00	41.000	0.000	41.0	96.7	6.00	4,203
	C	109 T	Square	work floor	0.000	12.50	9.500	33.50	0.00	0.00	33.500	0.000	33.5	95.5	6.00	3,391
	C	109 B	Square	work floor - top 33.5'	0.000	9.500	9.200	6.500	0.00	0.00	6.500	0.000	6.5	70.3	5.20	481
	C	110	Square	work floor	0.000	12.40	9.500	40.00	0.00	0.00	40.000	0.000	40.0	94.7	6.00	4,015
	C	201	Peaked	top of sidewall	26.900	0.000	0.000	40.00	0.00	0.00	40.000	1.600	41.6	456.9	8.50	20,623
	C	301	Peaked	top of sidewall	32.900	0.000	0.000	64.70	0.00	0.00	64.700	2.000	66.7	683.4	9.50	49,913
	C	302	Peaked	top of sidewall	32.900	0.000	0.000	64.70	0.00	0.00	64.700	2.000	66.7	683.4	9.50	49,913

Bin count: 35

Facility: Norwich Section: C Total: 219,616

To Even: 220,000

Exam Date:09/16/2013

Dakota Midland Grain, LLC

Page: 4

Examiner: 1

PO Box 188  
Voltaire, ND  
County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).			Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
					Length	Width										
O	001		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	002		Square	roof over bin	0.000	10.00	5.000	55.00	0.00	0.00	55.000	0.000	55.0	40.2	3.00	2,277
O	003		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	004		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	006		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	008		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	009		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	010		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	011		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	012		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	013		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	014		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	016		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	017		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	018		Square	roof over bin	0.000	10.00	10.00	49.30	0.00	0.00	49.300	0.000	49.3	80.4	5.50	4,182
O	101		Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655
O	102		Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655
O	103		Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655
O	104		Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655
O	105		Peaked	top of sidewall	18.000	0.000	0.000	44.00	3.00	0.00	47.000	1.100	48.1	204.6	6.00	10,431
O	106		Peaked	top of sidewall	18.000	0.000	0.000	44.00	3.00	0.00	47.000	1.100	48.1	204.6	6.00	10,431
O	107		Peaked	top of sidewall	18.000	0.000	0.000	44.00	3.00	0.00	47.000	1.100	48.1	204.6	6.00	10,431
O	108		Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655

**Section: O**

Exam Date:09/16/2013

Dakota Midland Grain, LLC  
 PO Box 188  
 Voltaire, ND  
 County:

Page: 5

Examiner: 1

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg.)	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
<b>Section: O</b>																
O		109	Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655
O		110	Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655
O		111	Peaked	top of sidewall	32.900	0.000	0.000	69.70	0.00	0.00	69.700	2.000	71.7	683.4	9.50	53,655
O		201	Peaked	top of sidewall	62.400	0.000	0.000	59.20	0.00	0.00	59.200	4.400	63.6	2458.3	10.0	171,983
O		202	Peaked	top of sidewall	62.400	0.000	0.000	59.20	0.00	0.00	59.200	4.400	63.6	2458.3	10.0	171,983
O		203	Peaked	top of sidewall	62.400	0.000	0.000	59.20	0.00	0.00	59.200	4.400	63.6	2458.3	10.0	171,983

Bin count: 29

Facility: Voltaire Section: O Total: 1,037,307

To Even: 1,038,000

**Section: Y**

Added	Y	bunker	Temporary	top of sidewall	26.000	200.0	100.0	3.000	0.00	0.00	3.000	26.00	29.0	16077.2	10.0	512,863
-------	---	--------	-----------	-----------------	--------	-------	-------	-------	------	------	-------	-------	------	---------	------	---------

Bin count: 1

Facility: Voltaire Section: Y Total: 512,863

To Even: 513,000

**Overall Licensed Bin Capacity for:**

Dakota Midland Grain, LLC

Bin count: 93

**Licensed Capacity:**  
(includes pack)

4,088,253 Bu.

**Licensed Capacity (to even):**  
(includes pack and section totals are rounded up to next highest 1000)

4,090,000 Bu.