



Public Service Commission  
State of North Dakota

COMMISSIONERS

Brian P. Kalk  
Randy Christmann  
Julie Fedorchak

Executive Secretary  
Darrell Nitschke

600 East Boulevard, Dept. 408  
Bismarck, North Dakota 58505-0480  
Web: www.psc.nd.gov  
E-mail: ndpsc@nd.gov  
Phone: 701-328-2400  
ND Toll Free: 1-877-245-6685  
Fax: 701-328-2410  
TDD: 800-366-6888 or 711

STATE OF NORTH DAKOTA  
PUBLIC SERVICE COMMISSION

Ideal Oilfield Disposal, LLC  
Variance Permit  
Application

Case No. WM-13-653

TEMPORARY VARIANCE PERMIT APPROVAL

Expires: Midnight on November 30, 2013 or Upon the Permanent Truck Scale  
Being Placed in Service (whichever occurs first)

Issued To:

Ideal Oilfield Disposal, LLC  
3711 4<sup>th</sup> Ave NE  
Watford City ND 58854

Scale Location:

Special Waste Landfill  
13195 26<sup>th</sup> St NW  
Arnegard ND 58835

Scale Information:

Rice Lake, ATV Series, Serial Number 4VC7, 200,000 lbs, 100,000 lb Concentrated Load  
Capacity 11' x 70' Truck Scale

Request To:

Temporarily operate a portable pitless scale for commercial use.

Temporary Variance Permit Conditions:


- The scale will not be used beyond its 200,000 lb capacity;
- During the temporary variance period, the scale must maintain acceptance tolerance;
- Once every three months from the date of being placed into service by a registered service company, the scale must be retested and adjusted by a registered service company. The three-month test reports must be submitted to the Commission;
- The test reports must include both the "as found" and "as left" readings;
- The scale must be operated according to all applicable North Dakota Laws and Rules; and
- The enclosed Temporary Variance Permit must be posted near the scale in a place conspicuous to the public.

We must also notify you that a portable pitless scale that is in a location for **6 months or more** must meet approach requirements found in North Dakota Administrative Code Section 69-10-02-09 and NIST Handbook 44 UR.2.6.1 as follows:

- on the entrance and exit ends of the vehicle scale there shall be a straight approach as follows:
  - the width at least the width of the platform,
  - the length of twelve feet or a distance equal to one-third of deck length, whichever is greater, beginning in a level plane with the surface of the scale deck, and
  - the first twelve feet of the straight approach from the scale must be of metal or concrete to insure that this portion remains smooth and level and in the same plane as the platform. Metal grating must be of sufficient strength to withstand all loads equal to the concentrated load capacity of the scale. Any slope of the remaining portion of the straight approach away from the scale deck may not exceed one-third inch [8.47 millimeters] per foot [30.48 centimeters].
  - any slope in any remaining portion of approaches beyond the straight approach shall ensure ease of vehicle access, ease for testing purposes, and drainage away from the scale.

If you have any further questions, or require additional information, please feel free to contact me at (701) 328-4077.

Dated July 18, 2013



Patrick Fahn, Director  
Compliance and Competitive Markets Division

PUBLIC SERVICE COMMISSION

STATE OF NORTH DAKOTA

TEMPORARY VARIANCE PERMIT

**Expires: Midnight on November 30, 2013 or Upon the Permanent Truck Scale Being Placed in Service (whichever occurs first)**

**Issued To:**

Ideal Oilfield Disposal, LLC  
3711 4<sup>th</sup> Ave NE  
Watford City ND 58854

**Scale Location:**

Special Waste Landfill  
13195 26<sup>th</sup> St NW  
Arnegard ND 58835

**Scale Information:**

Rice Lake, ATV Series, Serial Number 4VC7, 200,000 lbs, 100,000 lb Concentrated Load Capacity 11' x 70' Truck Scale

This Permit allows the above referenced **portable pitless scale to be operated for commercial use.**


This Permit is conditioned upon Ideal Oilfield Disposal, LLC adhering to the terms of the July 18, 2013 Temporary Variance Permit Approval.

Dated July 22, 2013



Patrick Fahn, Director  
Compliance and Competitive Markets Division

North Dakota

nd.gov Official Portal for  
North Dakota State Government

# SECRETARY OF STATE

## NORTH DAKOTA

[Home](#) | [Business Records Search](#)

### IDEAL OILFIELD DISPOSAL, LLC

#### Corporation Details

**System ID:** 30509300**Phone:** (701) 799-4766**Type:** LIMITED LIABILITY COMPANY**Status:** Active & Good Standing**Original File Date:** 12/28/2011**Effective Date:** 12/28/2011**State of Origin:** North Dakota

#### Nature of Business

SPECIAL WATER LANDFILL DISPOSAL

#### Principal Office

210 11TH ST N APT 104 FARGO, ND 58102-4668

#### Registered Agent

**PAT ZAVORAL**

210 11TH ST N APT 104

FARGO, ND 58102-4668

Established Date: Dec 28, 2011

#### Generate an Annual Report To File

To Generate a Annual Report form to be filed with the Secretary of State, select the appropriate year of the report you intend to file. This report does not contain details of a report previously filed with the Secretary of State. The annual report years reflected are an indication of the various report forms available in this site and is not an indication that an entity needs to file reports for all years. Missing years indicate that the forms for the missing year have not yet been deployed to the website, or have already been removed, and can be obtained by contacting the Secretary of State.

[2012](#) (generates a forms-fillable pdf in a new pop-up window)

[Return to Search Results](#)

[Contact Us](#)[Disclaimer](#)[Privacy Policy](#)

We use Secure Sockets Layer (SSL) encryption technology to ensure your information is secure