



PRAIRIE SCALE SYSTEMS, INC.

P.O. Box 69
Horace, ND 58047-0069
701-281-9591

MC-100655

Operator No.	Date	Date Last Tested	Check All That Apply						
	11/19/2013		Self-Certification	Non-Commercial					
Billing Name: Nuverra Environmental Treatment Center(Power Fuels)			Equipment Repair	New Installation X					
Billing Address:			Routine Service X	Annual X	Semi-Annual				
PO Box: Street Address: 3711 4th Ave NE Watford City ND 58854			Rejected Equipment	Tag # (Attached)					
Scale Location/Name: Special Waste Landfill RLWS PT			Service Contract?	Expires					
Mailing Address: PO Box: Street Address: 13195 26th ST NW			Variance Posted	Date of Variance					
City	State	Zip Code	No						
Arnegard	ND	58835							
County	Telephone Number		PSC Device Code	Quantity					
McKenzie	1-701-580-5490		3V4	1					
Make	Regulating Elements	Serial Number		Lever System					
RLWS Suvivor	720i-2A	1632500090		Ele. 8 Cell					
No. Sections	Monorail/Track	MTD	Hopper	Livestock	Platform	Axle Load	Multiple		
2	Aux. Beam	MT X	Hanging	Counter	Scale	Dormant/Deck	Other		
						Pit Depth			
						1:1			
						4'			
Capacity & Min. Grad.		Class	Size of Platform	Approaches					
160,000 X 20 lbs.		IIIL	10' X 80'	35' Contrete / Good (New)					
Printer Model	Printer Serial Number		Wind	Temperature	Device Location				
TM-U 295	J9KF069638		0-7	35 deg. F.	Outside				
SR (Sensitivity Response) OR Discrimination Test			Motion Detection		AZSM (auto zero)				
ZERO LOAD		LOADED	Range= 60		Range= 60				
Device/ Load Position	Amount of Test Equipment Used	Serial Number or Test Number	Actual Readings		Device/ Load Position	Amount of Test Equipment Used	Serial Number or Test Number	Actual Readings	
			As Found	As Left				As Found	As Left
Corner Test					Section Test				
1	10,000 lbs.		+20	0	1	20,000 lbs.		0	0
2	"		0	0	2	"		+20	0
3	"		-20	0	3	"		0	0
4	"		-20/-40	0	4	20,000 lbs.		-20	0
5	"		+20	0					
6	"		+20	0			BC=0@0		
7	"		+20	0					
8	10,000 LBS.		-20	0					
		BC=0@0							

STRAIN LOAD TEST	Section # 1	Section # 2	Section # 0	Section # 0
Empty Truck Weight	40,660	40,660		
Total Test Weight Added	20,000	20,000		
Truck Plus Weights	60,640	60,640		
Error on Added Test Weights	-20	-20		

I hereby declare the statements made here are correct:

Are there any jurisdictional devices at this location that require testing?	Yes	Remarks and Adjustments Made Placed into service the new truck scale at the landfill site. Wired, calibrated, tested and adjusted the new scale to bring it into acceptance tolerances. Removed the temporary truck scale.
HAS SECURITY SEAL AND STICKER BEEN APPLIED?	Yes	
Approved	Service Agency PSS	
Inspector/Permit Holder Signature	Permit No. 1514	
Owner - Operator Signature		