



Public Service Commission State of North Dakota

COMMISSIONERS

Julie Fedorchak
Randy Christmann
Brian P. Kalk

Executive Secretary
Darrell Nitschke

600 East Boulevard, Dept. 408
Bismarck, North Dakota 58505-0480
Web: www.psc.nd.gov
E-mail: ndpsc@nd.gov
Phone: 701-328-2400
ND Toll Free: 1-877-245-6685
Fax: 701-328-2410
TDD: 800-366-6888 or 711

TEMPORARY VARIANCE PERMIT APPROVAL EXTENSION

Expires: Midnight on August 31, 2016

**CHS Inc.
Variance Permit - Langdon
Application**

Case No. WM-13-809

Issued To:

CHS Inc.
515 W Montrose Ave
Milton ND 58260

Scale Location:

CHS Langdon East Terminal
10617 92nd St NE
Langdon, North Dakota

Truck Scale Information:

RLWS Survivor OTR Model EZ11712-SC-100-OTR, SN 56E2, 100,000 lb. CLC, 12' x 117'
and
RLWS Survivor OTR Model EZ11712-SC-100-OTR, SN 56DN, 100,000 lb. CLC, 12' x 117'

Request To:

Operate in commerce a scale with a floating slab foundation.

Temporary Variance Permit Conditions:


- The foundation of the scale must be constructed on soil that has a uniform natural or engineered soil bearing of at least 1,500 pounds per square foot.
- A base of uniform, compacted, permeable aggregate, at least 24 inches deep must be installed. The concrete slab foundation must be poured on top of this base.
- The scale weighing element or elements must be supported on a monolithic, reinforced 12" thick concrete slab and must conform to the scale manufacturer's installation and reinforcing requirements.
- The top surface of the foundation slab must be installed above the surrounding grade level so that water will flow away from the foundation and away from the permeable aggregate base that supports the foundation.
- The scale will not be used beyond its 100,000 lb. CLC capacity.

CHS Inc.
Page 2

- During the temporary variance period, the scale must maintain acceptance tolerance.
- The scale must be retested and adjusted, if applicable, by a registered service company in January 2016 and July 2016.
- The service company test reports must be submitted to the Commission.
- The service company test reports must include both the "as found" and "as left" readings.
- The scale must be operated according to all applicable North Dakota Laws and Rules.
- Enclosed is a Temporary Variance Permit for each scale that must be posted near the scale referenced by the Permit and in a place conspicuous to the public.
- Failure to comply with the variance permit conditions may result in revocation.

If you have any further questions, or require additional information, please feel free to contact me at (701) 328-4020.

Dated August 26, 2015



Joshua Gallion, Director
Weights and Measures Division



Public Service Commission

TEMPORARY VARIANCE PERMIT

Issued To:

CHS Inc.
515 W Montrose Ave
Milton ND 58260

Permit No. 491

Expiration Date: August 31, 2016

Scale Location:

CHS Langdon East Terminal
10617 92nd St NE
Langdon, North Dakota

Scale Information:

RLWS Survivor OTR Model EZ11712-SC-100-OTR, SN 56E2, 100,000 lb. CLC, 12' x 117'

This Permit allows the above referenced **scale with a floating slab foundation to be operated in commerce.**

This Permit is conditioned upon CHS adhering to the terms of the August 26, 2015 Temporary Variance Permit Approval Extension.

Dated August 26, 2015

A handwritten signature in green ink, appearing to read "Joshua Gallion", is written over the typed name and title.

Joshua Gallion, Director
Weights and Measures Division



Public Service Commission

TEMPORARY VARIANCE PERMIT

Issued To:

CHS Inc.
515 W Montrose Ave
Milton ND 58260

Permit No. 492

Expiration Date: August 31, 2016

Scale Location:

CHS Langdon East Terminal
10617 92nd St NE
Langdon, North Dakota

Scale Information:

RLWS Survivor OTR Model EZ11712-SC-100-OTR, SN 56DN, 100,000 lb. CLC, 12' x 117'

This Permit allows the above referenced **scale with a floating slab foundation to be operated in commerce.**

This Permit is conditioned upon CHS adhering to the terms of the August 26, 2015 Temporary Variance Permit Approval Extension.

Dated August 26, 2015

A handwritten signature in green ink, appearing to read "J Gallion", is written over a circular stamp or seal.

Joshua Gallion, Director
Weights and Measures Division