



PRAIRIE SCALE SYSTEMS, INC.

P.O. Box 69
Horace, ND 58047-0069
701-281-9591

CR-100395

Operator No.	Date	Date Last Tested	Check All That Apply						
	07/01/2014		Self-Certification	Non-Commercial					
Billing Name: CHS INC. Feed Facility			Equipment Repair	New Installation X					
Billing Address:			Routine Service	Annual	Semi-Annual				
PO Box: 187 Street Address: Edgeley ND 58433			Rejected Equipment	Tag # (Attached)					
Scale Location/Name: EDGELEY RLWS OTR			Service Contract?	Expires					
Mailing Address: PO Box: 187 Street Address: 8170 HWY #13			Variance Posted			Date of Variance			
City	State	Zip Code	Yes			05/07/2014			
Edgely	ND	58433	PSC Device Code			Quantity			
County	Telephone Number		3V2			1			
Lamoure	701-493-2271								
Make	Regulating Elements		Serial Number			Lever System			
RLWS OTR S/N: 5RMP	RLWS 920i-2A		1665400144			EL. 4 Cell			
No. Sections	Monorail/Track MTD Hopper Livestock Platform Axle Load					Multiple	Pit Depth		
2	Aux. Beam MT X Hanging Counter Scale Dormant/Deck Other					1:1	3'		
Capacity & Min. Grad.			Class	Size of Platform		Approaches			
80,000 x 20 lbs			IIIL	10' x 15'6"		East- OK - West 14"			
Printer Model		Printer Serial Number		Wind	Temperature	Device Location			
Epson TM-U295		J9KF102067		5-10	60 deg. F.	Outside			
SR (Sensitivity Response) OR Discrimination Test				Motion Detection		AZSM (auto zero)			
ZERO LOAD		NA	LOADED		NA	Range= 3d		Range= 3d	
Device/ Load Position	Amount of Test Equipment Used	Serial Number or Test Number	Actual Readings		Device/ Load Position	Amount of Test Equipment Used	Serial Number or Test Number	Actual Readings	
			As Found	As Left				As Found	As Left
Corner Test					Section Test				
1	10,000 lbs		0		1	20,000 lbs			0
2	"		0		2	20,000 lbs			0
3	"		0						
4	10,000 lbs		0			BC=0			
	BC=0								

STRAIN LOAD TEST	Section # 1	Section # 0	Section # 0	Section # 0
Empty Truck Weight	15,820			
Total Test Weight Added	20,000			
Truck Plus Weights	35,820			
Error on Added Test Weights	0			

I hereby declare the statements made here are correct:

Are there any jurisdictional devices at this location that require testing? **Yes**

HAS SECURITY SEAL AND STICKER BEEN APPLIED? **Yes**

Approved

Inspector/Permit Holder Signature: *Cody Rammick*

Owner - Operator Signature: *Wayne S. Cook*

Service Agency: **PSS**

Permit No.: **1718**

Remarks and Adjustments Made

Prairie Scales had recently installed new RLWS OTR truck scale (S/N: 5RMP), wired scale as needed, programmed scale into a new RLWS 920i dual channel indicator. Calibrated scale and made adjustments as needed. Scale has a temporary variance permit issued May 7th, 2014. Case No. WM-14-221.

1) Less pit clearance (36") than required (48") from the finished floorline of the scale to the bottom of the "I" beam of the scale bridge. (Extension scale only)

2) Less inside clearance (1-2') than required (5') between scale deck and doorsill.

Variance posted next to indicator in open site.