

Exam Date: 12/01/2015

Central Plains Ag Services, LLC
 10810 7th Street SE
 Hannaford, ND
 County:
 Phone: 701-769-2665
 CCC Number:

Page: 1

Examiner: 1

Location/Container Numbers/Comments	Section	Capacity
-------------------------------------	---------	----------

PART A - ADDITIONAL SPACE TO BE INCLUDED UNDER LICENSE

001	B	90,243
002	B	90,243
003	B	90,243
004	B	90,243
005	B	90,243
006	B	90,243
007	B	90,243
008	B	90,243
009	B	90,243
010	B	90,243
011	B	90,243
012	B	90,243
013	B	138,010
014	B	138,010
		Total: 1,358,936

PART B - SPACE TO BE DELETED UNDER LICENSE

025	C	2,159
018	A	583,369
019	A	803,117
		Total: 1,388,645

PART C - ALL SPACE TO BE INCLUDED UNDER LICENSE

A	3,614,000	
B	1,359,000	
C	686,000	
		Total: 5,659,000

PART D - TOTAL CAPACITY BY FUNCTIONAL UNIT

Courtenay	1215	C	686,000
Hannaford	2225	A B	4,973,000
			Total: 5,659,000

Exam Date: 12/01/2015
 Examiner: 1

Central Plains Ag Services, LLC
 10810 7th Street SE
 Hannaford, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg):	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Section: A

A		001	Irregular	top of slab	255.60	17.83	17.83	38.40	2.50	0.00	40.900	0.000	40.9	255.6	7.00	11,186
A		002	Irregular	top of slab	74.860	9.650	9.650	96.70	1.80	0.00	98.500	0.000	98.5	74.8	5.50	7,780
A		003	Irregular	top of slab	74.860	9.650	9.650	96.70	1.80	0.00	98.500	0.000	98.5	74.8	5.50	7,780
A		004	Irregular	top of slab	74.860	9.650	9.650	96.70	1.80	0.00	98.500	0.000	98.5	74.8	5.50	7,780
A		005	Irregular	top of slab	74.860	9.650	9.650	96.70	1.80	0.00	98.500	0.000	98.5	74.8	5.50	7,780
A		006	Irregular	top of slab	46.900	7.638	7.638	98.00	3.00	0.00	101.00	0.000	101.0	46.9	4.00	4,926
A		007	Irregular	top of slab	70.710	9.379	9.379	136.6	1.10	0.00	137.70	0.000	137.7	70.7	5.20	10,243
A		008	Round	top of slab	36.000	0.000	0.000	137.0	3.00	0.50	139.50	0.000	139.5	818.2	10.0	125,553
A		009	Round	top of slab	36.000	0.000	0.000	137.0	3.00	0.50	139.50	0.000	139.5	818.2	10.0	125,553
A		010	Irregular	top of slab	206.35	16.02	16.02	131.0	3.00	0.00	134.00	0.000	134.0	206.3	7.00	29,587
A		011	Round	top of slab	36.000	0.000	0.000	137.0	3.00	0.50	139.50	0.000	139.5	818.2	10.0	125,553
A		012	Round	top of slab	36.000	0.000	0.000	137.0	3.00	0.50	139.50	0.000	139.5	818.2	10.0	125,553
A		013	Irregular	top of slab	206.35	16.02	16.02	131.0	3.00	0.00	134.00	0.000	134.0	206.3	7.00	29,587
A		014	Round	top of slab	36.000	0.000	0.000	137.0	3.00	0.50	139.50	0.000	139.5	818.2	10.0	125,553
A		015	Round	top of slab	36.000	0.000	0.000	137.0	3.00	0.50	139.50	0.000	139.5	818.2	10.0	125,553
A		016	Irregular	top of slab	51.850	8.031	8.031	137.0	1.00	0.00	138.00	0.000	138.0	51.8	4.50	7,477
A		017	Round	top of slab	76.000	0.000	0.000	140.0	0.00	0.10	139.90	0.000	139.9	3646.7	10.0	561,190
A		Bunker	Peaked	top of sidewall	304.00	0.000	0.000	5.250	0.00	0.00	5.250	21.30	26.6	58346.7	10.0	1,707,224
A		ground	Temporary	top of sidewall	25.000	400.0	116.0	0.100	0.00	0.00	0.100	11.30	11.4	37299.0	10.0	467,730

Bin count: 19 Facility: Hannaford Section: A Total: 3,613,588

To Even: 3,614,000

Exam Date: 12/01/2015
 Examiner: 1

Central Plains Ag Services, LLC
 10810 7th Street SE
 Hannaford, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Opst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Section: B

Added	B	001	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	002	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	003	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	004	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	005	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	006	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	007	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	008	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	009	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	010	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	011	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	012	Peaked	top of sidewall	48.000	0.000	0.000	53.00	0.00	0.00	53.000	3.400	56.4	1454.6	10.0	90,243
Added	B	013	Peaked	top of sidewall	60.000	0.000	0.000	51.00	0.00	0.00	51.000	4.200	55.2	2272.9	10.0	138,010
Added	B	014	Peaked	top of sidewall	60.000	0.000	0.000	51.00	0.00	0.00	51.000	4.200	55.2	2272.9	10.0	138,010

Bin count: 14

Facility: Hannaford Section: B Total: **1,358,936**

To Even: **1,359,000**

Section: C

C	001	Irregular	work floor	32.400	6.349	6.349	51.00	0.00	0.00	51.000	0.000	51.0	32.4	2.50	1,693
C	004	Irregular	work floor	25.600	5.643	5.643	33.00	0.00	0.00	33.000	0.000	33.0	25.6	2.50	866
C	005 T	Irregular	work floor	31.400	6.250	6.250	33.00	0.00	0.00	33.000	0.000	33.0	31.4	2.50	1,062
C	005 B	Irregular	work floor - top 33'	57.900	8.487	8.487	22.00	0.00	0.00	22.000	0.000	22.0	57.9	4.80	1,335
C	006 T	Irregular	work floor	57.900	8.487	8.487	55.00	0.00	0.00	55.000	0.000	55.0	57.9	4.80	3,338

Exam Date: 12/01/2015
 Examiner: 1

Central Plains Ag Services, LLC
 10810 7th Street SE
 Hannaford, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Section: C

C	006 B	Irregular	work floor-top 55'		115.80	12.00	12.00	15.50	0.00	0.00	15.500	0.000	15.5	115.8	6.20	1,906
C	007	Irregular	work floor		31.500	6.260	6.260	51.00	0.00	0.00	51.000	0.000	51.0	31.5	2.50	1,647
C	008	Irregular	work floor		29.700	6.078	6.078	51.00	0.00	0.00	51.000	0.000	51.0	29.7	2.50	1,553
C	009	Irregular	work floor		32.600	6.368	6.368	51.00	0.00	0.00	51.000	0.000	51.0	32.6	2.50	1,705
C	010	Irregular	work floor		46.300	7.589	7.589	51.00	0.00	0.00	51.000	0.000	51.0	46.3	4.00	2,455
C	011	Irregular	work floor		30.800	6.190	6.190	51.00	0.00	0.00	51.000	0.000	51.0	30.8	2.50	1,610
C	012	Irregular	work floor		115.80	12.00	12.00	70.50	0.00	0.00	70.500	0.000	70.5	115.8	6.20	8,670
C	013	Irregular	work floor		63.700	8.902	8.902	49.00	0.00	0.00	49.000	0.000	49.0	63.7	5.00	3,277
C	014	Irregular	work floor		69.500	9.298	9.298	49.00	0.00	0.00	49.000	0.000	49.0	69.5	5.20	3,583
C	016	Irregular	work floor		115.80	12.00	12.00	70.50	0.00	0.00	70.500	0.000	70.5	115.8	6.20	8,670
C	017 T	Irregular	work floor		7.000	2.951	2.951	16.00	0.00	0.00	16.000	0.000	16.0	7.0	2.00	114
C	017 B	Irregular	work floor-top 16'		33.600	6.465	6.465	35.00	0.00	0.00	35.000	0.000	35.0	33.6	2.50	1,205
C	018	Irregular	work floor		32.600	6.368	6.368	51.00	0.00	0.00	51.000	0.000	51.0	32.6	2.50	1,705
C	020	Irregular	work floor		31.500	6.260	6.260	51.00	0.00	0.00	51.000	0.000	51.0	31.5	2.50	1,647
C	021 T	Irregular	work floor		57.900	8.487	8.487	55.00	0.00	0.00	55.000	0.000	55.0	57.9	4.80	3,338
C	021 B	Irregular	work floor-top 55'		115.80	12.00	12.00	15.50	0.00	0.00	15.500	0.000	15.5	115.8	6.20	1,906
C	022	Irregular	work floor		57.900	8.487	8.487	55.00	0.00	0.00	55.000	0.000	55.0	57.9	4.80	3,338
C	023	Irregular	work floor		46.300	7.589	7.589	51.00	0.00	0.00	51.000	0.000	51.0	46.3	4.00	2,455
C	024	Irregular	work floor		35.700	6.664	6.664	48.00	0.00	0.00	48.000	0.000	48.0	35.7	3.00	1,765
C	101 T	Irregular	work floor		115.40	11.98	11.98	61.00	0.00	0.00	61.000	0.000	61.0	115.4	6.20	7,475
C	101 B	Irregular	work floor-top 61'		142.60	13.32	13.32	6.000	0.00	0.00	6.000	0.000	6.0	142.6	6.80	914
C	102 T	Irregular	work floor		122.50	12.35	12.35	61.00	0.00	0.00	61.000	0.000	61.0	122.5	6.50	7,959
C	102 B	Irregular	work floor-top 61'		145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Section: C

C		103	Irregular	work floor-	99.900	11.15	11.15	59.00	0.00	0.00	59.000	0.000	59.0	99.9	6.00	6,248
C		104	Irregular	work floor-	105.20	11.44	11.44	59.00	0.00	0.00	59.000	0.000	59.0	105.2	6.20	6,592
C		105 T	Irregular	work floor-	115.40	11.98	11.98	61.00	0.00	0.00	61.000	0.000	61.0	115.4	6.20	7,475
C		105 B	Irregular	work floor-top 61'	142.60	13.32	13.32	6.000	0.00	0.00	6.000	0.000	6.0	142.6	6.80	914
C		106 T	Irregular	work floor-	122.50	12.35	12.35	61.00	0.00	0.00	61.000	0.000	61.0	122.5	6.50	7,959
C		106 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		107 T	Irregular	work floor	117.40	12.09	12.09	61.00	0.00	0.00	61.000	0.000	61.0	117.4	6.20	7,605
C		107 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		108 T	Irregular	work floor-	122.50	12.35	12.35	61.00	0.00	0.00	61.000	0.000	61.0	122.5	6.50	7,959
C		108 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		109	Irregular	work floor-	101.70	11.25	11.25	59.00	0.00	0.00	59.000	0.000	59.0	101.7	6.00	6,360
C		110	Irregular	work floor-	104.30	11.39	11.39	59.00	0.00	0.00	59.000	0.000	59.0	104.3	6.00	6,523
C		111 T	Irregular	work floor-	117.40	12.09	12.09	61.00	0.00	0.00	61.000	0.000	61.0	117.4	6.20	7,605
C		111 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		112 T	Irregular	work floor-	122.50	12.35	12.35	61.00	0.00	0.00	61.000	0.000	61.0	122.5	6.50	7,959
C		112 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		113 T	Irregular	work floor-	118.40	12.14	12.14	61.00	0.00	0.00	61.000	0.000	61.0	118.4	6.20	7,670
C		113 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		114 T	Irregular	work floor-	118.40	12.14	12.14	61.00	0.00	0.00	61.000	0.000	61.0	118.4	6.20	7,670
C		114 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		115	Irregular	work floor-	102.60	11.30	11.30	59.00	0.00	0.00	59.000	0.000	59.0	102.6	6.00	6,416
C		116 T	Irregular	work floor-	122.50	12.35	12.35	61.00	0.00	0.00	61.000	0.000	61.0	122.5	6.50	7,959
C		116 B	Irregular	work floor-top 61'	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930

Exam Date: 12/01/2015
 Examiner: 1

Central Plains Ag Services, LLC
 10810 7th Street SE
 Hannaford, ND
 County:

Status	Section	Bin Number	Bin Type	Base Point	Diameter or Bu/Ft (Irreg).	Length	Width	Side wall	Add for Hopper	Ded. for Obst.	Effective Depth	Add for Peak	Depth for Capac.	Bushels per Foot	Base Pack%	Bushel Capacity with Pack
--------	---------	------------	----------	------------	----------------------------	--------	-------	-----------	----------------	----------------	-----------------	--------------	------------------	------------------	------------	---------------------------

Section: C

C		117	Irregular	work floor-	104.30	11.39	11.39	59.00	0.00	0.00	59.000	0.000	59.0	104.3	6.00	6,523
C		118 T	Irregular	work floor-	122.50	12.35	12.35	61.00	0.00	0.00	61.000	0.000	61.0	122.5	6.50	7,959
C		118 B	Irregular	work floor-top 6'1"	145.10	13.44	13.44	6.000	0.00	0.00	6.000	0.000	6.0	145.1	6.80	930
C		119	Irregular	work floor-	101.70	11.25	11.25	59.00	0.00	0.00	59.000	0.000	59.0	101.7	6.00	6,360
C		120 T	Irregular	work floor-	117.40	12.09	12.09	13.00	0.00	0.00	13.000	0.000	13.0	117.4	6.20	1,621
C		120 M	Irregular	work floor-top 13'	117.40	12.09	12.09	11.00	0.00	0.00	11.000	0.000	11.0	117.4	6.20	1,371
C		120 B	Irregular	work floor-top 13'-middle 11'	142.60	13.32	13.32	6.000	0.00	0.00	6.000	0.000	6.0	142.6	6.80	914
C		121 T	Irregular	work floor-	118.40	12.14	12.14	61.00	0.00	0.00	61.000	0.000	61.0	118.4	6.20	7,670
C		121 B	Irregular	work floor-top 6'1"	142.60	13.32	13.32	6.000	0.00	0.00	6.000	0.000	6.0	142.6	6.80	914
C		200	Quonset	low point roof 18.5'	0.000	179.0	52.20	9.800	0.00	0.00	9.800	0.000	9.8	7330.6	10.0	79,024
C		201	Peaked	top of sidewall	16.000	0.000	0.000	15.00	2.50	0.00	17.500	1.000	18.5	161.6	5.80	3,163
C		202	Peaked	top of sidewall	16.000	0.000	0.000	15.00	2.50	0.00	17.500	1.000	18.5	161.6	5.80	3,163
C		Ground	Temporary	top of sidewall	16.200	296.0	104.0	7.500	0.00	0.00	7.500	7.500	15.0	22880.1	10.0	377,522

Bin count: 64
 Facility: Courtenay Section: C Total: 685,609
 To Even: 686,000

Overall Licensed Bin Capacity for:
 Central Plains Ag Services, LLC
 Bin count: 97

Licensed Capacity: _____
 (includes pack)

Licensed Capacity (to even): 5,659,000 Bu.
 (includes pack and section totals are rounded up to next highest 1000)

