



Public Service Commission
State of North Dakota

COMMISSIONERS

Julie Fedorchak
Randy Christmann
Brian P. Kalk

Executive Secretary
Darrell Nitschke

600 East Boulevard, Dept. 408
Bismarck, North Dakota 58505-0480
Web: www.psc.nd.gov
E-mail: ndpsc@nd.gov
Phone: 701-328-2400
ND Toll Free: 1-877-245-6685
Fax: 701-328-2410
TDD: 800-366-6888 or 711

TEMPORARY VARIANCE PERMIT APPROVAL

Expires: Midnight on June 30, 2017, or Upon the Permanent Truck Scale Being Placed in Service (whichever occurs first)

**Red River Oilfield Services, Inc.
Variance Permit
Application**

Case No. WM-16-751

Issued To:
Red River Oilfield Services, Inc.
1202 E. Broadway
Williston, ND 58801

Scale Location:
Stony Creek Rail Yard
13314 50th Rd. NW
Williston, ND 58801

Scale Information:
Weightronix Model W/T E1310, Serial Number 140615144, 120,000 lb. capacity, 11' x 75' Truck Scale

Variance Permit Request Received November 22, 2016:

To operate a portable pitless scale in commerce.

Temporary Variance Permit Conditions:


- The scale will not be used beyond its 120,000 lb. capacity;
- The scale must meet approach requirements found in North Dakota Administrative Code Section 69-10-02-09 and NIST Handbook 44 UR.2.6.1 as follows:
 - on the entrance and exit ends of the vehicle scale there shall be a straight approach as follows:
 - the width at least the width of the platform,
 - the length of twelve feet or a distance equal to one-third of deck length, whichever is greater, beginning in a level plane with the surface of the scale deck, and
 - the first twelve feet of the straight approach from the scale must be of metal or concrete to insure that this portion remains smooth and level and in the same plane as the platform. Metal grating must be of sufficient strength to withstand all loads equal to the concentrated load capacity of the scale. Any slope of the remaining portion of the straight approach away from the scale deck may not exceed one-third inch [8.47 millimeters] per foot [30.48 centimeters].

Red River Oilfield Services, Inc.
Temporary Variance Permit Approval

- any slope in any remaining portion of approaches beyond the straight approach shall ensure ease of vehicle access, ease for testing purposes, and drainage away from the scale.
- Once every three months from the date of being placed into service by a registered service company, the scale must be retested and adjusted by a registered service company. The three-month test reports must be submitted to the Commission;
- The placing in service, the required testing every three months, and the necessary adjustments may not be performed by SP Specialty Products, Inc.
- During the temporary variance period, the scale must maintain acceptance tolerance;
- The service company test reports must include both the "as found" and "as left" readings;
- The scale must be operated according to all applicable North Dakota Laws and Rules;
- If this scale is moved to a new location during the temporary variance permit period, Red River Oilfield Services, Inc. must have the scale placed back into service and all requirements listed above must be followed; and
- Enclosed is a Temporary Variance Permit that must be posted near the scale referenced by the Permit and in a place clearly visible to the public.

If you have any further questions, or require additional information, please feel free to contact me at (701) 328-4020.

Dated November 23, 2016



Joshua Gallion, Director
Weights and Measures Division



Public Service Commission

TEMPORARY VARIANCE PERMIT

Expires: Midnight on June 30, 2017, or Upon the Permanent Truck Scale Being Placed in Service (whichever occurs first)

Issued To:

Permit No. 514

Red River Oilfield Services, Inc.
1202 E. Broadway
Williston, ND 58801

Scale Location:

Stony Creek Rail Yard
13314 50th Rd. NW
Williston, ND 58801

Scale Information:

Weightronix Model W/T E1310, Serial Number 140615144, 120,000 lb. capacity, 11' x 75'
Truck Scale

This Permit allows the above referenced **portable pitless scale to be operated in commerce.**

This Permit is conditioned upon Red River Oilfield Services, Inc. adhering to the conditions of the November 23, 2016 Temporary Variance Permit Approval.

Dated November 23, 2016

A handwritten signature in black ink, appearing to read "Joshua Gallion", is written over a large, circular, stylized flourish or seal.

Joshua Gallion, Director
Weights and Measures Division