

R1728

Successful Reclamation of Lands Disturbed by Oil and Gas Development and Infrastructure Construction

Kevin Sedivec, Rangeland Management Specialist,
NDSU Extension Service

Carl Piper, Seed and Restoration Specialist,
Piper Land Resource Services, LLC

Jeff Printz, Rangeland Management Specialist,
Natural Resources Conservation Service

Abbey Wick, Soil Health Specialist,
NDSU Extension Service

Aaron Daigh, Soil Scientist,
NDSU School of Natural Resource Sciences

Ryan Limb, Range Scientist,
NDSU School of Natural Resource Sciences



NDSU EXTENSION SERVICE
North Dakota State University, Fargo
August 2014



Table of Contents

Development of Reclamation Plan	3
Land Preparation	5
Pipeline and Narrow Disturbance	
Small Disturbance Areas Such as Pads, Access Roads and Other Construction Disturbance Areas	
Seed Mixtures and Rates for Rangeland	8
Pipeline, Access Roads and Other Narrow Disturbance Upland Site Grass Seed Mixtures	
Pipeline, Access Roads and Other Narrow Disturbance Upland Forb Seed Options (select three) to Seed With the Grass Seed Mixture	
Pipeline, Access Roads and Other Narrow Disturbance Wet Meadow, Saline and/or Sodic Site Seed Mixtures	
Small Disturbance Site Upland Forb Seed Options (select three) to Seed With the Grass Seed Mixture (well pads, staging areas, tower sites, pumping stations and other construction disturbance)	
Small Disturbance Site Upland Grass Seed Mixtures (well pads, staging areas, tower sites, pumping stations and other construction disturbance)	
Small Disturbance Site Wet Meadow, Saline and/or Sodic Site Seed Mixtures (well pads, staging areas, tower sites, pumping stations and other construction disturbance)	
Varieties/Cultivars/ECOVARS	
Conservation Reserve Program (CRP)	12
Hay Land Reclamation	
Tame Pasture Reclamation	
Right of Way	12
Seeding Dates	
Erosion Control	13
Weed Control	15
Determining the Success of the Reclamation Project	15

This publication is designed to describe activities for the successful reclamation of North Dakota lands following disturbances associated with oil and gas production, and infrastructure construction. This includes topsoil/subsoil removal and replacement, well and pad development, pipeline and road construction, residential development and other activities related to the oil boom.

This publication only will address reclamation of non-contaminated soils. Contaminated soils may include lands compromised by oil spills (hydrocarbons) and brine spills.

We will introduce the critical components of a successful reclamation, provide recommended seed mixtures and seeding rates when reclaiming range and pasture land, and provide options to reduce soil erosion on disturbed rangelands, pastureland and hay lands. Although croplands are not specified directly in this publication, many of the topsoil salvage and replacement approaches, planning, preparation procedures and reclamation methods can be used as a guide to the successful reclamation of croplands.

These recommendations are designed for pipeline and small-area disturbance that may take place when developing infrastructure for oil and gas development, not for general agriculture and conservation restoration.

Development of Reclamation Plan

The goal for any reclamation project is to restore a site disturbed during the construction activities associated with oil and gas production to its pre-disturbance ecological structure and functions, as well as control erosion and sediment movement until the reclamation process is complete. The ecological structure and functions may include plant community integrity, watershed and water quality protection, wildlife habitat, retaining soil quality and productivity, and forage for livestock and wildlife.

What is important to understand is that minimizing the disturbance footprint before construction will provide a quicker return to the pre-disturbance conditions at a lower cost and with greater efficiency. A thorough, preconstruction inventory compiled by a botanist, certified professional in range management (CPRM), certified professional soil classifier or an experienced lay person with knowledge of soils, ecological sites, plant species and ecological function provides the basis for describing important functions of the land and setting clear objectives of the reclamation process.

This preconstruction inventory should include:

1. Clearly defined objectives and scope of the project. This will minimize the area that will be disturbed and reduce the construction footprint (area disturbed and severity of the disturbance).
2. Planning the reclamation and documenting the process prior to the disturbance. This document should be filed permanently for future reference.
3. Conducting a pre-disturbance/baseline inventory of the plant community, soils, topographic and landscape features. Photographs of the site provide valuable information. The **Web Soil Survey** can be used to provide an idea of the soil types found in area to be disturbed (however, a professional soil classifier will be needed to determine the actual soil types found on-site). Remember, the inventory should establish a framework for post-reclamation monitoring and evaluation.
4. Baseline inventory and documentation that includes 1) site-specific information and 2) on-site evaluation of ecosystem functions that need to be maintained or restored.



Components of existing, on-site information that need to be gathered for successful reclamation include:

1. Topsoil depth

The boundary between topsoil and subsoil material is determined based primarily on color (which indicates organic matter content), texture, pH and other properties that indicate suitable soil to support plant growth. The topsoil will contain remnant vegetative plant material and seeds that naturally occur and can help regenerate plant species that are present pre-disturbance. Topsoil is labeled at the "A horizon" in the Natural Resources Conservation Service (NRCS) **Web Soil Survey**. Determination and interpretation of soil pre-disturbance is completed by a certified professional soil classifier in North Dakota.

Clearly labeled stakes should be placed in the field indicating required depth to remove topsoil. Topsoil and subsoil must be removed in separate lifts and stockpiled in separate piles (for example, topsoil in one pile and subsoil in a separate pile) to reduce mixing soil layers when the reclamation process begins.

2. Properties of the subsoil and underlying materials

These properties should help identify any drainage issues and document water-holding capacity, allowing for the planning of erosion protection options; subsoil material has lower organic matter content than topsoil, making it typically lighter in color. It also may have a different texture than the topsoil material. Subsoil is referred to as the "B horizon" in the NRCS **Web Soil Survey**. Subsoil **never** should be placed or stored on top of topsoil. Consult your Soil Conservation District office or the Professional Soil Classifiers Associate of North Dakota for more information. Refer to North Dakota Century Code 43-36 for more information on soil classification and interpretation of soil properties.

3. Identification of vegetation and land use

Delineate land use (farmland, native rangeland, hay land, tame pasture, Conservation Reserve Program [CRP], etc.). Characterize the cover, productivity and plant community species' diversity and composition, including threatened or endangered species, watch species and sensitive species when working on federally owned lands.

4. Topography, landforms and surface water

These properties will affect post-disturbance functions to be restored and identify if a need occurs to develop storm water retention sites and erosion control techniques.

5. Wildlife habitat

Document wildlife species present through visual observation, fecal pellets, tracks, small mammal burrows or disturbances, and bird nests. Include any threatened or endangered species, watch species and sensitive species. Consult the North Dakota Game and Fish Department, U.S. Fish and Wildlife Service, U.S. Forest Service, U.S. Bureau of Land Management or any other agencies to identify species and critical habitat within or around the disturbed area. Pre-project clearances must be made with these agencies and/or corresponding agency prior to disturbance activities on public lands.

6. Archaeological and historical resources

Consult the North Dakota State Historical Preservation office for more information.

Land Preparation

The key to successful reclamation is to minimize the area of disturbance. This will reduce the cost of reclamation, allow adjoining areas to remain intact and help accelerate the recovery process.



Example of construction and reclamation of an access road during and after construction.



Pipeline and Narrow Disturbance

Take the following steps from the onset of construction to final recovery for successful reclamation in rangelands. Pipeline disturbances, particularly in croplands, can be identified decades after the disturbance, so take care to follow the appropriate reclamation guidelines.

1. Separate the topsoil from the subsoil.
 - a.) In areas where distinguishing the topsoil from subsoil is difficult, separate the top 8 inches of soil from the rest of the soil and treat it as topsoil. If you are unable to determine the depth of the topsoil, the **Web Soil Survey** (available online) is a useful tool for providing guidelines for topsoil depth. In all cases, a professional soil classifier can determine the depth of topsoil in the field.
 - b.) Do not mix topsoil and subsoil. Topsoil has biological, physical and chemical properties that are critical to recovery of the site.
 - c.) Store topsoil separately from the subsoil, either on the opposite side of the trench or with sufficient separation, to prevent the layers from mixing. Subsoil never should be mixed with the topsoil resource. Erosion control should be installed to ensure soil stays within the stockpile footprint. If stockpiles will remain longer than a growing season, seed the pile with a cover crop, or seed with perennial cover if the pile is to be retained for multiple years.
 - d.) If excavating below the subsoil or into different soil horizons, separate this soil from top- and subsoil so it can be backfilled at the base of the trench.



Top photo showing topsoil separated from subsoil. Bottom photo shows a close-up of the topsoil and subsoil separated during the excavation process.


2. Replace the soil accordingly to the order in which the layers were removed.
 - a.) Replace the subsoil first without compacting the material, but make sure it is firm enough to prevent subsidence of material post-reclamation. Water will need to be able to move through this layer, so limiting compaction is key. Subsoil never should be placed over or mixed with topsoil.
 - b.) Replace the topsoil after the subsoil has been set in the trench. Bring the disturbance to desired grade. **Do not mix the topsoil and subsoil.**
3. A firm seedbed is critical for a successful seeding. Final soil preparation for seeding should provide a firm, relatively uniform seedbed that is not compacted. Loose soil will result in seed being planted too deeply, resulting in poor vegetative stand success, while areas with compaction will result in shallow rooting and poor plant survival rates. Agricultural practices for seedbed preparation should be used prior to seeding.
4. Identify areas of potential excess erosion risk and stabilize them accordingly.
 - a.) See the erosion control section of this publication.
5. Seed an appropriate seed mix approximately ¼ inch deep.
 - a.) Use drills equipped with depth-control bands.
 - b.) Hydro seeding, broadcast and harrowing or other seeding methods may be used as necessary.
 - c.) Rake in all fence lines, meters, stand pipes and other obstructions within the disturbance areas.
 - d.) Use high-quality clean and conditioned seed that has been tested for germination (germ) and purity.
 - e.) Buy seed on a pure live seed (PLS) basis.
 - f.) Calibrate and seed on an adjusted bulk seeding rate of PLS/(germ x purity). For example, 10 pounds/acre PLS with 85 percent germ and 90 percent purity = 13.07 bulk pounds/acre.

Non-native grasses and forbs can be invasive on native prairie. Clean equipment thoroughly after seeding non-native species to avoid transferring these species to areas where they are unwanted.

Small Disturbance Areas Such as Pads, Access Roads and Other Construction Disturbance Areas

These types of reclamation projects may be the focus of later restoration, often years or decades into the future, largely due to the compaction of the soil and mixing of topsoil and subsoil resources. Additional steps need to be taken to ensure these areas have the resources necessary to be preserved for remediation at that time.

Example of a small disturbance. Development and reclamation of a well pad in western North Dakota.



1. Strip topsoil and stockpile it in separate lifts for future restoration of the pad, road or other disturbance area at the end of its useful life. All topsoil should be salvaged per the depth determined by a professional soil classifier; this is your most valuable resource for successful reclamation. Topsoil should be stored separately from subsoil and, when possible, in shallow, wide piles. Stockpiles need to be stabilized to avoid erosional losses using re-established native grasses and/or erosion mats, even if it is for a "short" time period (less than one month). Retention of topsoil and subsoil resources in stockpiles is essential because top soil is a non-renewable resource.
2. Bring all slopes, roadways, sediment retainers and ditches to appropriate grade.
3. Replace subsoil first and then topsoil. As stated previously, you will want the subsoil to be firm but not compacted to allow for water movement into and through the subsoil material. Additionally, take care when replacing the topsoil to avoid destruction of soil structure and compaction upon replacement. The use of scrapers for this process can lead to compaction, so take care when using that type of equipment.
4. Final preparation for seeding should provide a firm, relatively uniform seedbed for seeding. Loose soil will result in seed being planted too deeply, resulting in poor stand success, while compacted soil will result in restrictive layers limiting root development. Agricultural practices to prepare the seedbed should be used.
5. Identify areas of potential excess erosion risk and stabilize them accordingly.
 - a.) See the erosion control section of this publication.
6. Seed an appropriate seed mix approximately ¼ inch deep.
 - a.) Use drills equipped with depth-control bands.
 - b.) Hydro seeding, broadcast and harrowing or other seeding methods may be used as necessary.
 - c.) Use high-quality clean and conditioned seed that has been tested for purity and germination.
 - d.) Buy and install seed on a pure live seed (PLS) basis.
 - e.) Calibrate and seed on an adjusted bulk seeding rate of PLS/(germ x purity). For example, 10 pounds/acre PLS with 85 percent germ and 90 percent purity = 13.07 bulk pounds/acre.

Seed Mixtures and Rates for Rangeland

We divided the state into three major areas for seed mixtures and separated them by major roadways (Figure 1). Major highways were used to simplify decision making for pipeline operators, engineers and contractors. The boundaries were delineated on general rangeland types and precipitation relative to a region.

Each section will have a recommended native rangeland seed mixture for *upland sites* and *wet meadow, saline and/or sodic sites* to apply on pipeline disturbance. Small disturbance sites will have a recommended native rangeland seed mixture for *loamy/clayey sites, thin loamy/shallow loamy/limy sites, sandy/sands sites, and wet meadow, saline and/or sodic sites*.

For the upland sites, select a minimum of three forbs/legumes from the recommended species list to complement the recommended grass-seeding mixtures. For the *wet meadow, saline and/or sodic sites*, select at least one forb species from the list that best fits the site.




Figure 1. Location of west, central and east zones, with the boundary, to be used for recommended seeding mixtures and rates in North Dakota. The **West** is an area from the Montana border east to U.S. Highway 83, **Central** stretches from U.S. Highway 83 to North Dakota Highway 32 and the **East** lies east of North Dakota Highway 32 to the Minnesota border.

Government agencies may have more rigorous restrictions on seed cultivars, origins, seeding dates or other specifications than those listed here. Consult with the corresponding agency before designing and purchasing a seed mixture.

Applying fertilizer to native plant seeding is **not** recommended. Fertilizers enhance exotic grasses and annual weeds, reducing the success of the establishment.

Pipeline, Access Roads and Other Narrow Disturbance Upland Site Grass Seed Mixtures

Upland Mixture (loamy, clayey, sandy, sands, shallow loamy, thin loamy)

Grass Species	West*	Central*	East*
		PLS lb/ac ¹	
Western wheatgrass	2.5	2.5	2.5
Green needlegrass	2.0	1.5	1.0
Slender wheatgrass	1.5	1.5	1.0
Little bluestem	1.0	1.0	1.0
Prairie sandreed	1.0	1.0	0.5
Sideoats grama	2.0	2.0	2.0
Blue grama	0.5	0.25	0.25
Big bluestem	---	1.0	1.0
Switchgrass	---	0.25	0.5
Canada wildrye	---	1.0	1.0
Indiangrass	---	---	1.0
Total seed mixture	10.5	12.0	11.75

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².

* West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Pipeline, Access Roads and Other Narrow Disturbance Upland Forb Seed Options (select three) to Seed With the Grass Seed Mixture

Upland Mixture (loamy, clayey, sandy, sands, shallow loamy, thin loamy)

Forb and Legume Species ²	North Dakota
	PLS lb/ac ^{1,3}
Purple prairieclover	0.1
White prairieclover	0.1
Purple coneflower	0.1
Maximilian sunflower	0.1
Blanket flower	0.2
Black-eyed Susan	0.05
Stiff sunflower	0.1
Goldenrod	0.05
Lewis flax	0.1
Scarlet globemallow	0.05
Prairie coneflower	0.1

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².

² Select a minimum of three forb/legume species from the list. The seeding rate of three selected forbs/legumes at the prescribed rate will equal approximately 5 percent of the total mixture.

³ Drill calibration is critical when seeding low rates because seed may be expensive.

Pipeline, Access Roads and Other Narrow Disturbance Wet Meadow, Saline and/or Sodic Site Seed Mixtures

Wet Meadow, Saline/Sodic Mixture

Grass Species	West*	Central*	East*
		PLS lb/ac ¹	
Western wheatgrass	7.5	5.0	5.5
Slender wheatgrass	2.5	2.0	2.0
Prairie cordgrass	1.5	1.5	1.5
Inland saltgrass	0.5	0.5	0.5
Switchgrass	---	1.0	1.0
Total seed mixture	12.0	10.0	10.5
		Forb Species ² PLS lb/ac ^{1,3}	
Western yarrow		0.05	
Gardner saltbush ⁴		0.3	
Fourwing saltbush ⁴		0.45	
Lewis flax		0.1	

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².

² Select a minimum of one forb species from the list.

³ Drill calibration is critical when seeding low rates because seed may be expensive.

⁴ Gardner and fourwing saltbush should be used only on the saline/sodic sites.

* West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Small Disturbance Site Upland Grass Seed Mixtures (well pads, staging areas, tower sites, pumping stations and other construction disturbance)

Loamy and Clayey Sites

Grass Species	West*	Central*	East*
Western wheatgrass	5.0	3.0	2.0
Green needlegrass	2.5	2.0	2.0
Slender wheatgrass	1.0	1.0	1.0
Side-oats grama	2.0	2.0	2.0
Blue grama	0.5	0.25	0.25
Big bluestem	---	1.0	1.5
Switchgrass	---	0.25	0.5
Canada wildrye	---	1.0	1.0
Indiangrass	---	---	1.0
Total seed mixture	11.0	10.5	11.25

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².
^{*} West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Thin Loamy, Shallow Loamy and Limy Sites

Grass Species	West*	Central*	East*
Western wheatgrass	2.5	3.0	2.0
Green needlegrass	1.5	1.5	1.5
Slender wheatgrass	1.5	1.0	1.0
Little bluestem	1.0	1.0	1.0
Prairie sandreed	1.0	1.0	1.0
Sideoats grama	2.0	2.0	2.0
Blue grama	0.5	0.5	0.25
Big bluestem	---	1.0	1.5
Total seed mixture	10.0	11.0	10.25

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².
^{*} West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Sandy and Sands Sites

Grass Species	West*	Central*	East*
Western wheatgrass	2.5	2.5	2.0
Needle-and-thread	2.0	2.0	1.0
Canada wildrye	1.0	1.0	1.0
Little bluestem	1.0	1.0	1.0
Prairie sandreed	1.5	1.5	1.0
Sideoats grama	2.0	2.0	2.0
Blue grama	0.5	0.5	0.25
Sand/Big bluestem	---	1.5	2.0
Total seed mixture	10.5	12.0	10.25

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².
^{*} West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Small Disturbance Site Upland Forb Seed Options (select three) to Seed With the Grass Seed Mixture (well pads, staging areas, tower sites, pumping stations and other construction disturbance)

Forb and Legume Mixture (loamy, clayey, sandy, sands, shallow loamy, thin loamy, limy)

Forb and Legume Species ²	North Dakota
Purple prairieclover	0.1
White prairieclover	0.1
Purple coneflower	0.1
Maximilian sunflower	0.1
Blanket flower	0.2
Black-eyed Susan	0.05
Stiff sunflower	0.1
Goldenrod	0.05
Lewis flax	0.1
Scarlet globemallow	0.05
Prairie coneflower	0.1

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².
² Select a minimum of three forb/legume species from the list. The seeding rate of three selected forbs/legumes at the prescribed rate will equal approximately 5 percent of the total mixture.
³ Drill calibration is critical when seeding low rates because seed may be expensive.

Small Disturbance Site Wet Meadow, Saline and/or Sodic Site Seed Mixtures (well pads, staging areas, tower sites, pumping stations and other construction disturbance)

Wet Meadow, Saline and/or Sodic Sites

Plant Species ^{2,3}	West*	Central*	East*
Western wheatgrass	8.0	5.0	5.0
Slender wheatgrass	2.0	2.0	2.0
Prairie cordgrass	2.0	2.0	2.0
Inland saltgrass	1.0	1.0	1.0
Switchgrass	---	1.0	1.0
Total grass seed mixture	13.0	11.0	11.0
Western yarrow	0.05	0.05	0.05
Gardner saltbush ⁴	0.3	0.3	0.3
Fourwing saltbush ⁴	0.45	0.45	0.45
Lewis flax	0.1	0.1	0.1

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².
² Select a minimum of one forb/legume species from the list.
³ Drill calibration is critical when seeding low rates because seed may be expensive.
⁴ Gardner and fourwing saltbush should be used only on the saline/sodic sites.
^{*} West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Varieties/Cultivars/ECOVARS

Approved Named Varieties

Species	Recommended Varieties for North Dakota
	Origin of nonvarietal (common) native and introduced grass seed is limited to North Dakota, South Dakota, Nebraska, Montana, Wyoming, Minnesota and Canada

Introduced Cool-season Grasses

Meadow brome grass	Fleet, Paddock, Regar, Montana, MacBeth, Cache
Crested wheatgrass	
Standard	Nordan, RoadCrest, Summit
Fairway	Ephraim, Ruff, Parkway, Fairway, Douglas
Hybrid	HyCrest II, HyCrest, NU-ARS AC2
Intermediate wheatgrass	Reliant, Clarke, Slate, Chief, Oahe, Haymaker, Beefmaker, Manifest
Pubescent wheatgrass	Manska, Greenleaf

Native Warm- and Cool-season Grasses

Green needlegrass	Lodorm, AC Mallard, Fowler
Needle-and-thread	Common, AC Sharptail
Nuttall alkaligrass	Common
Porcupine grass	Common
Prairie junegrass	Common
Slender wheatgrass	Adanac, Pryor, Revenue, Primar, Firststrike
Western wheatgrass	Rodan, Walsh, Flintlock, Rosana, W.R.Poole, Recovery
Canada wildrye	Mandan
Big bluestem	Sunnyview, Bison, Bonilla, Bounty
Little bluestem	Badlands, Itasca
Blue grama	Bad River
Sideoats grama	Killdeer, Pierre, Butte
Indiangrass	Tomahawk
Prairie cordgrass	Red River
Prairie sandreed	Goshen, Bowman, Koch
Switchgrass	Dacotah, Forestburg, Sunburst, Summer

Species	Recommended Varieties for North Dakota
	Nonvarietal (common) native forbs and legumes will originate or be grown in North Dakota, South Dakota, Nebraska, Montana, Wyoming, Idaho, Washington, Oregon, Minnesota, Wisconsin, Iowa, Colorado and Canada

Native Legumes/Forbs

Black-eyed Susan	Common
Blanket flower	Common
Grayhead coneflower	Common
Narrow-leaved purple coneflower	Bismarck
Prairie (yellow) coneflower	Stillwater
Purple coneflower	Common
Canada goldenrod	Common
Missouri goldenrod	Common
Stiff goldenrod	Common
Lewis flax	Appar, Maple Grove
Maximilian sunflower	Medicine Creek
Purple prairieclover	Bismarck
Scarlet globemallow	Common
Stiff sunflower	Bismarck
Western yarrow	Great Northern
White prairieclover	Antelope

Introduced Legumes

Alfalfa ¹	Fall dormancy rating or winter survival index (WSI) of 3 or less ²
----------------------	---

Native Shrubs

Fourwing saltbush: Dewinged	Wytana, Snake River
Gardner saltbush	
Winterfat	Open Range
WY big sagebrush	Common

¹ A partial list of grazable-type alfalfas can be found in "Developing Alfalfa Adapted to Grazing in the Northern Great Plains," available at www.ag.ndsu.edu/archive/streeter/99report/berdahl99.htm.

² The following websites are approved for use in determining approved alfalfa varieties: www.alfalfa.org/ and www.maes.umn.edu/. Varieties should have a fall dormancy rating or winter survival index (WSI) of 3 or less. Note: Alfalfa varieties with a WSI of 2 or 3 may experience some winter kill. The origin of nonvarietal (common) alfalfa types is limited to North Dakota, South Dakota, Minnesota, Montana and Canada.

NOTE: Approved alfalfa varieties that may not be shown on these websites include Alogonquin, Anik, Blazer, Champ, Drylander, Grim, Ladak, Ladak 65, Prowler, Rambler, Rangelander, Ramsey, Ranger, Spredor 2, Teton, Travois, Vernal and Wrangler. Alfalfa varieties not listed here or shown on these websites will require documentation from the distributor or developer to determine suitability.

Conservation Reserve Program (CRP)

Seed CRP fields back to the predominant species found within the stand. Contact the local NRCS office for help with seed mixtures in your construction area. Some CRP is seeded to native species. Take care to seed all areas to appropriate species.

Hay Land Reclamation

Hay Land Sites			
Plant Species ³	West*	Central*	East*
	PLS lb/ac ¹		
Crested wheatgrass	3.0	---	---
Pubescent/Intermediate wheatgrass	4.0	3.0	---
Meadow bromegrass	---	7.0	10.0
Alfalfa ²	4.0	3.0	5.0
Total seed mixture	11.0	13.0	15.0

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².

² Use alfalfa varieties with a fall dormancy rating of 3 to 4 and a winter hardiness rating of 2 to 2.5 when reseeding pure stands of alfalfa. Recommended seeding rates are 8 pounds/acre of PLS in the west, 9 pounds/acre of PLS in the central and 10 pounds/acre of PLS in the eastern portions of North Dakota.

³ These hay land recommendations are to be used as examples. Always consult with the land owner/manager and plant what he or she prefers or needs for future use.

* West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Tame Pasture Reclamation

Hay Land Sites			
Plant Species ³	West*	Central*	East*
	PLS lb/ac ¹		
Crested wheatgrass	4.0	---	---
Pubescent/Intermediate wheatgrass	5.0	6.0	6.0
Western wheatgrass	5.0	---	---
Meadow bromegrass	---	15.0	15.0
Alfalfa ²	---	---	---
Total seed mixture	14.0	21.0	21.0

¹ PLS = Pure live seed: Seeding rates are 1.5 times the normal seeding rate based on 30 seed/ft².

² Use alfalfa varieties with a fall dormancy rating of 3 to 4 and a winter hardiness rating of 2 to 2.5 when reseeding pure stands of alfalfa. Recommended seeding rates are 8 pounds/acre of PLS in the west, 9 pounds/acre of PLS in the central and 10 pounds/acre of PLS in the eastern portions of North Dakota.

³ These tame pasture recommendations are to be used as examples. Always consult with the land owner/manager and plant what he or she prefers or needs for future use.

* West = west of U.S. Highway 83, Central = east of U.S. Highway 83 to North Dakota Highway 32, East = east of North Dakota Highway 32

Right of Way

Use specifications for Class II seed specifications in North Dakota Department of Transportation Manual Section 708.02B.

Seeding Dates

Recommended Seeding Dates	
Species Type and Season of Planting	North Dakota
Cool-season Species	
Spring	Prior to June 1 ²
Late summer ¹	Aug. 1 to Sept. 1
Late fall (dormant)	See footnote ³
Warm/Cool-season Mix	
Spring	April 20 to June 15 ²
Late summer ¹	Not recommended
Late fall (dormant)	See footnote ³

¹ Weather and soil moisture conditions permitting. If soil moisture levels and forecasted precipitation amounts are not favorable, this time period of seeding is not recommended.

² Seeding may be extended with adequate soil moisture and when favorable precipitation and temperatures are forecast.

³ Seed after Oct. 10 when ground temperatures at a depth of 4 inches are 45 F or lower and cooler air temperatures are forecast.

Erosion Control

Erosion control devices may be utilized when site reclamation occurs outside the preferred seeding dates or when the topography of the site requires additional measures to enhance the restoration process.

In all cases, topsoil and subsoil stockpiles must be protected from erosional processes (wind and water), even if the duration of stockpiling is “short” (less than one month). Such protection certainly needs to be considered for long-term resource storage.

Spray-on covers such as mulching will help create a microclimate at the seed soil interface to promote germination while controlling erosion. Additional measures such as mats, which provide additional stability, may be used in higher-gradient areas or remote areas where access is limited.


Many erosion-control devices are available, and all are unique in some way. The best way to manage erosion is to evaluate the landscape as a whole, providing the proper controls based on need. For example, stabilizing the soil with mulch or crimping may control erosion and lessen the impact of raindrops or small sheet flows on a specific area (ditch bottom or pipeline trench).

But if your disturbed site is impacted from the surrounding landscape through runoff, other controls such as temporary berms, diversions or sediment fence diverting larger sheet flows from entering the site may be required. The area being protected may not be the only area impacting the erosion potential.

The North Dakota Department of Health’s Division of Water Quality (2001) states that erosion control is mandatory on all construction projects. Phase II of the National Pollution Discharge Elimination System (NPDES) will require projects disturbing areas larger than one acre to apply for a storm water discharge permit. These criteria will force smaller contractors who normally do not have to deal with temporary erosion control measures to install these devices.

This publication is intended to give all contractors, designers and inspectors the tools needed to properly install, maintain and implement their storm water pollution prevention (SWPP) plans. The proper use of best management practices (BMPs) will protect the environment and save the user time and money lost to erosion damage.

NOTE: For further information on erosion control, see “**A Guide to Temporary Erosion-Control Measures for Contractors, Designers and Inspectors**” published by the North Dakota Department of Health’s Division of Water Quality (June 2001), 1200 Missouri Ave., P.O. Box 5520, Bismarck, ND 58506-5520; www.ndhealth.gov/wq/wastewater/pubs/bmpmanual.pdf.



Example of using multiple erosion control methods to reduce sediment movement and aid in the restoration of the seeding.

Erosion control during the reclamation process



Example of a reclamation project using erosion control techniques, before and after photos.

Final restoration with erosion control structures removed



Weed Control

Weed control is essential for reclamation success. Annual broadleaf and grass weeds will be common during the year of implementation and second year after seeding. These annual weeds should not be a concern during the first growing season; however, mowing or chemical treatment (depending on seed mixture) to control seed development may be necessary during the second growing season. If the seed mixture contains broadleaf, legume or shrub plants, chemical control would not be recommended because the chemical also will damage the seeded plants.

NOTE: For further information on weed control, see the "North Dakota Weed Control Guide" at www.ag.ndsu.edu/weeds/weed-control-guides/nd-weed-control-guide-1. This publication is available through an app (NDSU Pest Management app). For weed identification and control, see "Identification and Control of Invasive and Troublesome Weeds in North Dakota" at www.ag.ndsu.edu/publications/landing-pages/crops/identification-and-control-of-invasive-and-troublesome-weeds-in-north-dakota-w-1411.

Determining the Success of the Reclamation Project

Disturbed areas should be monitored for a period of time and compared with adjacent, similar reference areas to document that revegetation has been successful. If revegetation is successful, soil structure and function likely also have been reclaimed to a level conducive for stabilization of long-term, desirable vegetative communities.

Developing and following a long-term monitoring plan is critical so problems can be identified and controlled early. Direct monitoring and comparisons with suitable reference areas will ensure that landowner commitments, private and public, have been satisfied and that all applicable regulatory requirements are met.

Pay close attention to topsoil and subsoil replacement depths, seeding success, noxious weeds and erosion. Topsoil and subsoil replacement depths can be determined by using a soil auger and looking for color change. Darker material relative to other soil materials should be on the surface. Seedlings from the seeded plant species should be noticeable in the first growing season, but the presence of annual weeds throughout is not unusual. Seeded plants should occur throughout the site and annual weeds still will be present by the second growing season.

A typical standard for successful revegetation is when the disturbed area has reached three to five established plants of replacement vegetation per foot², as specified in the seed mixture or compared with adjacent undisturbed areas. Noxious weeds, by law, must be controlled by pulling or spraying before they spread or produce seed.

While monitoring the reclamation process, identify any areas of instability or erosion. Uncontrolled wind and water erosion can degrade a reclamation project rapidly, destroying the integrity of the land and quality of water down slope. If erosion points are found and appear to be worsening, incorporate control measures that slow and divert runoff flow.

Erosion control best management practices that may be incorporated include successful stands of vegetation, wattles, silt fences, straw bales and trenches. Wind erosion is more difficult to evaluate than water erosion; however, if best management practices are implemented for water erosion control, wind erosion control is highly likely.



NDSU EXTENSION
SERVICE



All photos used with permission from Brenda Fettingler, Marathon Oil.

The NDSU Extension Service does not endorse commercial products or companies even though reference may be made to tradenames, trademarks or service names.

NDSU encourages you to use and share this content, but please do so under the conditions of our Creative Commons license. You may copy, distribute, transmit and adapt this work as long as you give full attribution, don't use the work for commercial purposes and share your resulting work similarly. For more information, visit www.ag.ndsu.edu/agcomm/creative-commons.

For more information on this and other topics, see www.ag.ndsu.edu

County commissions, North Dakota State University and U.S. Department of Agriculture cooperating. North Dakota State University does not discriminate on the basis of age, color, disability, gender expression/identity, genetic information, marital status, national origin, public assistance status, sex, sexual orientation, status as a U.S. veteran, race or religion. Direct inquiries to the Vice President for Equity, Diversity and Global Outreach, 205 Old Main, (701) 231-7708. This publication will be made available in alternative formats for people with disabilities upon request, (701) 231-7881.