

STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION

ONEOK Rockies Midstream, L.L.C.
Cherry Creek Pipeline – McKenzie & Williams Counties
Siting Application

Case No. PU-17-483

AFFIDAVIT OF SERVICE BY CERTIFIED MAIL

STATE OF NORTH DAKOTA
COUNTY OF BURLEIGH

Geralyn R. Schmaltz deposes and says that:

she is over the age of 18 years and not a party to this action and, on the **30th day of June 2022**, she deposited in the United States Mail, at Bismarck, North Dakota, **one** envelope with certified postage, return receipt requested, fully prepaid, securely sealed and containing a photocopy of:



- **Order on Tree and Shrub Mitigation Specifications**

The envelope was addressed as follows:

Todd McKimmey
Vice-President Integrated Operations & Capital Projects
ONEOK
100 West 5th Street, 16th Floor
Tulsa, OK 74103
Cert. No. 7021 2720 0003 0049 2065

Each address shown is the respective addressee's last reasonably ascertainable post office address.

Subscribed and sworn to before me
this **30th day of June 2022**.



SEAL



Shelly A Bauske
Notary Public

STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION

ONEOK Rockies Midstream, L.L.C.
Cherry Creek Pipeline – McKenzie & Williams Counties
Siting Application

Case No. PU-17-483

ORDER ON TREE AND SHRUB MITIGATION SPECIFICATIONS

June 29, 2022

Preliminary Statement

The Commission's April 30, 2018, Findings of Fact, Conclusions of Law and Order in Case No. PU-17-483, issued Certificate of Corridor Compatibility No. 203 and Route Permit No. 213 to ONEOK Rockies Midstream, L.L.C. (ONEOK) for the 12-inch diameter natural gas liquids transmission line project.

On March 13, 2019, the Commission revised its Tree and Shrub Mitigation Specifications to update the process for mitigation reporting.

On February 16, 2022, Commission Staff sent a letter to ONEOK suggesting that ONEOK may wish to consider complying instead with the March 13, 2019, version of the Tree and Shrub Mitigation Specifications.

On March 24, 2022, ONEOK responded to the February 16, 2022, Commission Staff letter.

Discussion

The Tree and Shrub Mitigation Specifications (Specifications) attached to and made part of the Commission's April 30, 2018, Order required that two trees be planted for every one tree removed, and that two shrubs be planted for one shrub removed. The Specifications required that tree and shrub replacements be inspected annually, in September, for three years, with the first annual inspection at least one year from the anniversary date of the original plantings. The Specifications further required that a report of each annual report be submitted to the Commission by October 1 of each year, documenting the condition of plantings and any woodlands work completed as of September of each year.

During construction of the project, 25 trees/shrubs were removed.

The Commission's March 13, 2019, Specifications were conceived to be goal or purpose oriented to create sustainable plantings, appropriate for the local soil and growing conditions that will provide long-term benefits to landowners, farmers and

ranchers, the community, wildlife and the environment. In lieu of annual reporting for three years, the Commission's March 13, 2019, Specifications require one final report filed by the company after two years that details the company's tree and shrub mitigation efforts and describes how the company's mitigation achieved the purpose stated above.

ONEOK has indicated a desire to comply with the March 13, 2019, version of the Tree and Shrub Mitigation Specifications instead of the version of the Tree and Shrub Mitigation Specifications adopted by the Commission's April 30, 2018, Order.

Having considered this matter, the Commission issues the following:

Order

The Commission Orders that its April 30, 2018, Findings of Fact, Conclusions of Law and Order is amended to replace the Tree and Shrub Mitigation Specifications adopted in that Order with the March 13, 2019, version of the Tree and Shrub Mitigation Specifications, attached to and made part of this Order.

PUBLIC SERVICE COMMISSION


Randy Christmann
Commissioner


Julie Fedorchak
Chair


Sheri Haugen-Hoffart
Commissioner

**STATE OF NORTH DAKOTA
PUBLIC SERVICE COMMISSION**

**ONEOK Rockies Midstream, L.L.C.
Cherry Creek Pipeline – McKenzie & Williams Counties
Siting Application**

Case No. PU-17-483

Tree and Shrub Mitigation Specifications

Inventory

Prior to cutting or clearing trees or shrubs for construction:

- All trees one-inch or greater in diameter at breast height must be inventoried to record the location, number, and species.
- All shrubs and all coniferous trees of any diameter must be inventoried to record the location, number, and species.

Clearing

The maximum width of tree and shrub removal is 50 feet, unless otherwise approved by the Commission.

Replacement

1. Landowners must be given the option to have trees and shrubs that are removed from their property replaced on their property. The landowner may waive this option in writing. If the landowner waives this option, the company shall plant replacement trees and shrubs in an alternate location in the same region, if practical.
2. Trees and shrubs must be replaced on a minimum two-to-one basis. The company shall develop a Tree and Shrub Mitigation Plan (Plan) in consultation with landowners who are seeking replacement trees and shrubs and in accordance with USDA-NRCS-North Dakota Field Office Technical Guide: Windbreak and Woodland Tree Care and Management. The guidelines outlined in the Technical Guide shall be followed until filing of the Plan summary outlined in number 5 below.
3. The purpose of the company's Tree and Shrub Mitigation Plan is to create sustainable plantings, appropriate for the local soil and growing conditions that will provide long-term benefit to landowners, farmers and ranchers, the community, wildlife and the environment.
4. The Plan, including the proposed number, variety, type, location, and approximate date for plantings, shall be filed with and approved by the Commission.
5. Two years after completion of the plan, the company must file a summary documenting how the plan achieved the purpose outlined in number 3 above. The summary must also report the number of surviving replacement trees and shrubs.
6. The Commission will consider, on a limited basis as conditions warrant, mitigation plans that provide long-term wildlife habitat and conservation benefits but do not involve the replanting of trees and shrubs.