

McKENZIE COUNTY UTILITY APPLICATION

Permit # **BF180725KD**

Revised September 07, 2017

Permit Type: **Permanent**
 (Please circle one) Temporary

Belle Fourche Pipeline
 Utility Company Name

of **455 N Poplar St, Casper WY 82601**
 Address, City, State & Zip

Route*	Section #		Township (N)		Range (W)		For Official Use Only	
	From	To	From	To	From	To	Type of Crossing	Fee
18th St	36	4	T-149-N	T-148-N	R-100-W	R-100-W	8 inch steel	\$500.00
132nd Ave	36	31	T-149-N	T-149-N	R-100-W	R-99-W	8 inch steel	\$500.00
18th St	33	6	T-149-N	T-148-N	R-99-W	R-99-W	8 inch steel	\$500.00
12th St	4	n/a	T-147-N	n/a	R-101-W	n/a	8 inch steel	\$500.00
130 1/2 Ave	32	n/a	T-149-N	n/a	R-99-W	n/a	8 inch steel	\$500.00
Red Wing Rd	33	34	T-148-N	n/a	R-101-W	n/a	8 inch steel	\$500.00
138th Ave	24	19	T-148-N	T-148-N	R-101-W	R-100-W	8 inch steel	\$500.00
136th Ave	16 9	17	T-148-N	n/a	R-100-W	n/a	8 inch steel	\$500.00
17th St	4	9	T-148-N	n/a	R-100-W	n/a	8 inch steel	\$500.00
139th Ave	23	24	T-148-N	n/a	R-101-W	n/a	8 inch steel	\$500.00
18th St	34	n/a	T-149-N	n/a	R-99-W	n/a	8 inch steel	\$500.00
140th Ave NW	--- 26	--- 26	----- 148	-----	----- 101	-----	8 inch steel	\$500.00
13th T St NW	--- 27	--- 27	----- 148	-----	----- 101	-----	8 inch steel	\$500.00
	---	---	-----	-----	-----	-----		
	---	---	-----	-----	-----	-----		
	---	---	-----	-----	-----	-----		

Total Fee: **\$8275.00**

*Enter the County Route # or Street Name. If it is simply a section line crossing, enter "Section Line"

Attach Maps and Construction Plans

At a minimum, acceptable plans will include method of crossing existing roads or section lines and size and material used for the buried facility.

Existing 8 inch line be converted into a transmission line.

Email Address **Ken.Dockweiler@Truecos.com**

Ken Dockweiler
 Signature of Authorized Agent of Utility Company

Ken Dockweiler

Printed Name of Authorized Agent of Utility Company

7/25/18
 Date

307-237-9301

Telephone Number

PAID

If you require additional pages for your request, indicate your total number of pages.

Page of Total # Pages of

WHERE SHOULD THE APPROVED PERMIT BE SENT TO:

Belle Fourche Pipeline Company

Company Name or Agent Name

455 N Poplar St


Address

Casper, WY 82601

City, State & Zip Code

307-237-9301

Telephone Number



SEP 10 2018

Additional crossings for permit BF180725KD

Route	Section #		Township (N)		Range (W)		Crossing Type	Fee
	From	To	From	To	From	To		
Section Line	36	35	149		99		Section Line	\$25.00
Section Line	35	34	149		99		Section Line	\$25.00
Section Line	34	6	149	148	99	99	Section Line	\$25.00
Section Line	33	32	149		99		Section Line	\$25.00
Section Line	32	31	149		99		Section Line	\$25.00
Section Line	17	18	148		100		Section Line	\$25.00
Section Line	18	19	148		100		Section Line	\$25.00
Section Line	23	26	148		101		Section Line	\$25.00
Section Line	26	27	148		101		Section Line	\$25.00
Section Line	27	34	148		101		Section Line	\$25.00
Section Line	33	4	148	147	101	101	Section Line	\$25.00
Section Line	4	5	147		101		Section Line	\$25.00
Section Line	5	8	147		101		Section Line	\$25.00
CR27 ROW (.1 mi)	4		147		101		Utility in ROW @\$500/mi	\$50.00
Section line ROW (.1 mi)	4	5	147		101		Utility in ROW @\$500/mi	\$50.00
13th T St NW ROW (.1 mi)	27		148		101		Utility in ROW @\$500/mi	\$50.00
15th St NW Section line (ROW 1.9 mi)	24	19	148	148	101	100	Utility in ROW @\$500/mi	\$950.00
16th St NW ROW (.2 mi)	17	9	148		100		Utility in ROW @\$500/mi	\$100.00
135th Ave NW ROW (.5 mi)	9	4	148		100		Utility in ROW @\$500/mi	\$250.00

\$1,775.00

Utility Company, as noted on reverse hereinafter referred to as "Utility Company", having requested permission from McKenzie County, a political subdivision of the State of North Dakota, to cross an existing road, run within its right-of-way easement, or section line with a buried or overhead transmission facility designed to carry or conduct oil, gas, water, electricity, telephone or any other substance or service whatsoever, and McKenzie County having considered the request does grant consent to cross the existing road or section line, or run within its right-of-way or easement as noted on reverse, upon the terms and conditions herein stated.

Consent to cross such existing road or section line is granted on these terms and conditions:

1. Utility company must pay for all damage to the existing road caused by its activities, including but not limited to slumping in of trenches and collapse of pipe. Utility company is responsible for restoring and reclaiming any land used for temporary or permanent utilities to their original condition.
2. Utility company is responsible for any and all claims of damage, personal injury, or bodily injury that is the fault of the utility company. Furthermore, utility company agrees to indemnify and hold harmless McKenzie County for any and all claims of damage, either personal injury or property or any type of claim for damages of any nature whatsoever, whether valid or invalid, that is made against McKenzie County on account of the activities conducted by the utility company in crossing any existing road or section line.
3. When the utility company crosses an existing road or section line, or places a line parallel to the road in the right-of-way, the utility company shall be responsible to pay for all costs of moving, relocating, or reconstructing the temporary or permanent utility facility should McKenzie County deem it necessary or advisable in its sole discretion. Roads may be built on the section line or off the section line as allowed by North Dakota law. Should the utility company fail to take the necessary steps to relocate or reconstruct its permanent or temporary utility facility, the County may take steps to have the same accomplished, and the utility company agrees to reimburse the County for all expenses incurred by McKenzie County in moving, relocating, or reconstructing the utility facility so the existing roads may be repaired or reconstructed, or new roads may be built on the section line or off of the section line as allowed by North Dakota Law.
4. The buried or overhead transmission facility to be installed by the utility company in crossing any existing road shall, at a minimum, comply with the following engineering standards:
 - i) Pipe shall be cased or heavy wall pipe used.
 - ii) All overhead powerlines crossing over public streets, roads, and non-residential driveways with truck traffic must maintain a minimum height of 18ft.
 - iii) All bores under county roads must be approved by the Road and Bridge Department.
 - iv) All crossings of existing roads not trenched as in Section 5 below shall be bored to a depth of five (5) feet below original ground or ditch elevations.
 - v) All parallel borings must be a minimum of thirty (30) feet from road centerline.
 - vi) Vent pipes must be outside existing right-of-way lines.
 - vii) All disturbed ground within right-of-way must be rehabilitated by covering with black dirt and seeding with an approved mix approved by the Road and Bridge Department
 - viii) If vent pipes are not used within the (10) feet of both sides of right-of-way, the transmission facility must have markers on the right-of-way line or 33 foot line, whichever is greater, on both sides of the road.
 - ix) The Company's plan to bury a transmission facility filed with the County Engineer must show, at a minimum, in plain view and cross sectional view, the location of the crossing from a section or quarter line; section, township and range the crossing is located in; the location of vent pipes, if any, in proximity to the crossing; and the angle of crossing.
 - x) The Company's plan must be submitted to the Office of the County Engineer for review at least two (2) weeks prior to the commencement of the project.
5. Any crossing installed by trenching or plowing in may be no more than eight (8) inches in width. The Company will apply surfacing materials and compact the site, returning it as close as possible to the original compaction. The Utility Company will be responsible for all such crossings for a period of three (3) years, repairing during those three (3) years any damages to the road resulting from their activity. Any crossing which cannot be accomplished with this method must be bored. All road trenching and reconstruction shall be inspected and approved by the Road and Bridge Department.
6. Temporary utility lines that are parallel to a county maintained road must exist outside the clear zone. The clear zone on a gravel road is 10 feet from the outside edge of the shoulder of the road. The clear zone on a paved road is 14 feet from the outside edge of the shoulder of the road. Applicants are required to permit temporary lines that parallel a county maintained road, pass through culverts or cattle guards, as well as cross section lines.
7. Application fees are non-refundable. When a permit is requested the fee that is distributed by the Road and Bridge Department is considered the application fee. If the utility is not implemented, the fee **MUST** still be paid. Accounts will not be credited for unused or expired permits. Any refunds will be at the discretion of the Road and Bridge Department.


8. Utility company must comply with all terms and conditions stated herein, with particular attention to the required engineering standards. McKenzie County shall give written notice to utility company in the event it believes the utility company has failed to meet any of the terms or conditions of the permit. Utility company representative shall meet with McKenzie County engineer or his representative within three (3) days of such notice (unless a longer time is requested by McKenzie County) to discuss and review the alleged violation of terms and conditions: if utility company agrees with McKenzie County that terms and conditions have been violated, utility company shall begin work within 24 hours (or such longer time as McKenzie County might allow) to correct such violations of terms and conditions and shall work diligently until such violations are corrected. If utility company fails to begin work timely or diligently to correct such violations, utility company shall be deemed to have failed to comply with the CONDITIONAL CONSENT. Failure to comply with this CONDITIONAL CONSENT shall cause the consent to be rescinded and utility company must remove facility from right-of-way immediately or be responsible for the costs incurred by the County in removing the same. The County specifically reserves the right to remove the buried, overhead, or temporary transmission facility from right-of-way for non-compliance and reimbursement will be made to the County by utility company for doing the same. If utility company disagrees with McKenzie that it is in violation of the terms and conditions as outlined in the permit, utility company shall nevertheless comply with the demands of McKenzie; but, if it is later determined that McKenzie County was in error in its position, McKenzie County will reimburse utility company for its costs in complying with McKenzie County's demands.

For purposes of this permit "highway right-of-way" shall mean the highway right-of-way as it exists on the date of execution of this permit and shall also include that area within seventy-five feet of the center of the highway right-of-way over which the Board of McKenzie County Commission has control pursuant to North Dakota Century Code Section 24-01-42

AUTHORIZED AGENT OF THE UTILITY COMPANY

I, the undersigned, being an authorized agent of the Utility Company described in the above, do hereby agree on behalf of the Utility Company that all terms and conditions listed on the reverse will be complied with, and any assignment of this utility facility described above shall include an assignment of this liability to comply with the terms and conditions as stated herein.

Signature:



Date:

7/25/18

*** PLEASE NOTE***

Permanent utility applications are valid for one year upon approval. After one year the applicant must re-apply for the permit.

Temporary utility applications are valid for 180 days upon approval. After 180 days, the applicant must re-apply for the permit.

Belle Fourche

Legend

- Style1
- Style2
- WILSON_BOWLINE

Google Earth

© 2018 Google



4 mi

