

**STATE OF NORTH DAKOTA**  
**PUBLIC SERVICE COMMISSION**

**ONEOK Bakken Pipeline, L.L.C.**  
**16-Inch NGL Pipeline – Williams County**  
**Siting Application**

**Case No. PU-19-368**

**FINDINGS OF FACT, CONCLUSIONS OF LAW AND ORDER**

**April 1, 2020**

**Appearances**

Commissioners Brian Kroshus, Julie Fedorchak, and Randy Christmann

Casey A. Furey, Attorney at Law, Crowley Fleck PLLP, 100 West Broadway, Suite 250, Bismarck, North Dakota 58501, on behalf of ONEOK Rockies Midstream, L.L.C.

Zachary Pelham, Special Assistant Attorney General, 314 E. Thayer Ave., Bismarck, ND 58501, as Counsel for the North Dakota Public Service Commission.

Timothy Dawson, Office of Administrative Hearings, 2911 North 14<sup>th</sup> Street, Suite 303, Bismarck, North Dakota 58503, as Procedural Hearing Officer.

**Preliminary Statement**

On November 25, 2019, ONEOK Bakken Pipeline, L.L.C. (ONEOK) filed with the North Dakota Public Service Commission (Commission), a consolidated application for a certificate of corridor compatibility and a route permit concerning the location of a 16-inch natural gas liquids (NGLs) transmission pipeline, and associated facilities in Williams County, North Dakota (Project).

On December 30, 2019, the Commission provided notification of the application to the townships with retained zoning authority, cities, and counties in which any part of the proposed pipeline corridor would be located.

On December 17, 2019, December 18, 2019, and January 10, 2020, ONEOK filed information supplementing its consolidated application.

On January 22, 2020, the Commission deemed the consolidated application complete (Application) and issued a Notice of Filing and Public Hearing, scheduling a public hearing for March 6, 2020, at 9:00 a.m. Central Standard Time, at the City of

Williston Public Works and Engineering Department, 1121 5<sup>th</sup> Street East, Williston, North Dakota 58801. The Notice identified the following issues:

1. Will construction, operation, and maintenance of the facility at the proposed location produce minimal adverse effects on the environment and upon the welfare of the citizens of North Dakota?
2. Is the proposed facility compatible with the environmental preservation and the efficient use of resources?
3. Will construction, operation, and maintenance of the facility at the proposed location minimize adverse human and environmental impact while ensuring continuing system reliability and integrity and ensuring that energy needs are met and fulfilled in an orderly and timely fashion?

On March 6, 2020, the hearing was held as scheduled. Exhibits 1 through 12 were admitted at the hearing.

Having allowed all interested persons an opportunity to be heard and having heard, reviewed, and considered all testimony and evidence presented, the Commission makes its:

### **Findings of Fact**

1. ONEOK Bakken Pipeline, L.L.C. is a Delaware limited liability company. ONEOK Bakken Pipeline, L.L.C. has been authorized to do business in the State of North Dakota, as evidenced by the corporate papers filed with the Commission on February 7, 2019, in Case No. PU-13-739.

#### **Size, Type, and Preferred Location of Facility**

2. The Project consists of approximately 75 miles of 16-inch diameter steel pipeline, located in Williams County, North Dakota. The project includes four mainline block valves, one pig launcher facility, one pig launcher with receiver facility, and one pig receiver facility. The Project is capable of transporting up to 90,000 barrels of NGLs per day.
3. The Project will originate at the Hess Tioga Natural Gas Processing Plant and terminate at an interconnection near the ONEOK Stateline to Riverview NGL Pipeline.
4. The proposed facility corridor and pipeline route is identified in Exhibit B.2 of the Application.
5. The pipeline has a maximum operating pressure of 1,480 pounds per square inch.

6. The estimated cost of the Project is \$100 million dollars.
7. ONEOK anticipates a fourth quarter 2020 in-service date for the facility.

#### Study of Preferred Location

8. ONEOK conducted a Class I cultural resource literature review and a desktop analysis for wetlands, waterbodies, woodlands, and other sensitive environmental resources across a one-mile wide area centered on the pipeline route (Study Area).
9. ONEOK conducted several surveys and a habitat assessment across an approximately 300-foot-wide area generally centered on the Project route (Survey Area). ONEOK conducted a natural resources survey across the Survey Area, which included wetland and waterbody surveys, noxious weed surveys, and a general habitat assessment for state- and federally-listed species. ONEOK also conducted a tree and shrub survey, an eagle nest survey, and a biological survey.
10. ONEOK conducted a Class III cultural resource inventory across the Survey Area. The Class III reports were submitted to the North Dakota State Historic Preservation Office.
11. Section 49-22.1-13(4) of the North Dakota Century Code provides that a site shall not be designated that violates the rules of any state agency, and that compliance with an agency's rules shall be presumed if the agency fails to present its position with respect to the proposed facility at the public hearing.
12. ONEOK initiated correspondence with federal, state and local departments, agencies and entities as follows:
  - a. Federal: (i) U.S. Fish and Wildlife Service (USFWS); (ii) U.S. Army Corps of Engineers; (iii) U.S. Department of Defense; and (iv) U.S. Department of Agriculture
  - b. State: (i) North Dakota State Historic Preservation Office (NDSHPO); (ii) North Dakota Parks and Recreation Department; (iii) North Dakota Department of Trust Lands; (iv) North Dakota Department of Environmental Quality; (v) North Dakota Geological Survey (NDGS); (vi) North Dakota State Water Commission; and (vii) North Dakota Game and Fish Department (NDGFD);
  - c. Local: (i) The Williams County Board of Commissioners; (ii) Williams County Water District; (iii) The Williams County Weed Control Board; (iv) Western Area Water Supply Authority; (v) the cities of Tioga and Springbrook; and (vi) the townships of Buford, Trenton, Tioga and Sauk Valley

## Siting Criteria

14. The Commission has developed criteria pursuant to North Dakota Century Code section 49-22.1-03 to guide the site, corridor, and route suitability evaluation and designation process. The criteria as set forth in North Dakota Administrative Code 69-06-08-02 are classified as Exclusion Areas, Avoidance Areas, Selection Criteria, and Policy Criteria.

15. ONEOK evaluated the Survey Area and route regarding the Exclusion Areas, Avoidance Areas, Selection Criteria, and Policy Criteria.

16. An Exclusion Area is a geographic area that must be excluded in the consideration of a route for a transmission facility. An Exclusion Area may be located within a corridor, but at no given point may such an area or areas encompass more than fifty percent of the corridor unless there is no reasonable alternative. A transmission facility route must not be sited within an Exclusion Area.

17. ONEOK's studies and surveys did not record any known Exclusion Areas within the Survey Area.

18. An Avoidance Area is a geographical area that may not be considered in the routing of a transmission facility unless the applicant demonstrates that under the circumstances, there is no reasonable alternative. In determining whether an Avoidance Area should be designated for a facility, the Commission may consider, among other things, the proposed management of adverse impacts, the orderly siting of facilities, system reliability and integrity, the efficient use of resources, and alternative routes. Economic considerations alone will not justify approval of these areas.

19. Areas that are geologically unstable or potentially unstable are an Avoidance Area. NDGS's October 16, 2019 correspondence identified five areas of potential geologic instability within the proposed corridor. ONEOK has avoided impacts to one area by shifting the Project route and will utilize horizontal directional drilling ("HDD") methods to avoid impacts to three potentially instable areas as set forth and committed to by ONEOK in December 18, 2019 correspondence to the NDGS. (Hearing Exhibit 6). In December 20, 2019 correspondence, the NDGS stated it reviewed ONEOK's proposed avoidance measures and did not note any additional concerns. With respect to the fifth area of potential geologic instability located at approximate milepost 56.4, ONEOK testified this location appears to be located outside of the Project's workspace; however, ONEOK will conduct additional review of this area and submit its findings to the NDGS. ONEOK testified it will submit updated correspondence from the NDGS to the Commission for the fifth location prior to commencing construction in this area.

20. Areas within five hundred feet of a residence, school, or place of business are an Avoidance Area. ONEOK testified that it identified 20 occupied structures, consisting of

19 distinct landowners, within five hundred feet of the Project route. ONEOK has obtained waivers for 14 of these structures and submitted copies as Exhibit 4. ONEOK testified it will obtain the remaining landowner waivers prior to constructing the Project within 500 feet of said areas, or ONEOK will file a route adjustment with the Commission to be outside 500 feet of the occupied areas.

21. Areas containing historical resources not specifically designated as Exclusion or Avoidance Areas are an Avoidance Area. ONEOK's Class III cultural resource survey identified 10 cultural sites that remain unevaluated for inclusion on the National Register of Historic Places within the Project corridor but are not directly crossed by the Project route. ONEOK has applied NDSHPO recommended 100-foot avoidance buffers to these sites. In December 17, 2019 correspondence to the NDSHPO, ONEOK committed to various mitigative measures for nine of the unevaluated sites where full 100-foot buffers could not be maintained. On December 31, 2019, the NDSHPO issued a letter finding ONEOK's Class III Cultural Resource Survey acceptable and concurring with a "No Significant Sites Affected" determination provided the Project remains as proposed.

22. ONEOK's surveys did not identify any other Avoidance Areas within the Survey Area.

23. The Commission's Selection Criteria is set forth in North Dakota Administrative Code section 69-06-08-02(3). A corridor or route shall be approved only if it is determined that any significant adverse effects that will result from the location, construction and operation of the facility as they relate to the selection criteria will be at an acceptable minimum, or will be managed and maintained at an acceptable minimum. ONEOK analyzed the effects that may result from the location, construction, and operation of the Project.

24. ONEOK will minimize and/or avoid impacts to wetlands or waterbodies by employing HDD where appropriate and by following best management practices where the trenching method is utilized. The Project will cross the Little Muddy River and Beaver Creek. ONEOK will avoid impacts to these crossings by utilizing the HDD method.

25. ONEOK identified one wetland within the Survey Area with potentially suitable habitat for piping plover. To avoid potential impacts to the piping plover, ONEOK has committed to undertake certain conservation measures as set forth in its January 24, 2020 correspondence to the USFWS including additional surveys of suitable habitat and presence/absence surveys as necessary and based upon the timing of construction within the identified area. In January 24, 2020 correspondence from the USFWS, the USFWS stated it has no objections to the Project and concurs with ONEOK's proposed conservation measures.

26. During construction, the increase in ambient sound will primarily be from the use of heavy equipment and trucks. Ambient sound will be minimal during pipeline operation.

27. The proposed Project will affect 682 acres of private land in North Dakota, of which approximately 67% consists of privately-owned cropland. Once construction is complete, ONEOK will restore land to its pre-construction contours and land use. ONEOK will also provide settlements to landowners for crop loss caused by construction.

28. The proposed Project will not have significant adverse impacts to extractive and storage resources, ground water flow patterns, or radio, television, and other communication or electronic facilities. If drainage patterns are disturbed during construction, ONEOK will restore those affected areas to their original local topography. Furthermore, the visual effect on adjacent areas will be minimal and mainly consist of the installation of four above-ground mainline block valves along with the pig launcher and receiver facilities.

#### Additional Mitigative Measures

29. ONEOK has agreed to a number of measures to mitigate potential Project impacts, as indicated by the attached Certification Relating to Order Provisions – Transmission Facility Siting along with the attached Tree and Shrub Mitigation Specifications.

30. ONEOK has developed several project control documents that will be utilized during construction activities to minimize and mitigate impacts on environmental resources including a: Construction Mitigation and Restoration Plan; Migratory Bird Plan; Storm Water Pollution Prevention Plan; Spill Prevention, Control and Countermeasure Plan; Unanticipated Discoveries Plan; Revegetation Plan; Weed Management Plan; and Dust Control Plan which are included in Exhibit H to the Application.

31. NDSHPO has approved ONEOK's Unanticipated Discoveries Plan, which provides response measures to be followed in the event of a discovery of cultural or human remains.

32. ONEOK will participate in the North Dakota One-Call Excavation Notice System.

33. Fifty-eight percent of the pipeline will be co-located within the corridor of an existing pipeline.

34. ONEOK testified that they will comply with all applicable safety laws and standards.

35. The Project will be designed, constructed, maintained, and inspected to the USDOT Pipeline and Hazardous Materials Safety Administration regulations utilizing industry standards.

36. A Supervisory Control and Data Acquisition (SCADA) system will allow ONEOK to monitor the pipeline 24 hours a day, 7 days a week, and 365 days a year by trained controls personnel. The system will monitor the flow and pressure of the system, and the

system will allow ONEOK to identify and respond to situations outside normal operating conditions.

37. ONEOK will employ environmental inspectors and third party inspectors to monitor construction activities and ensure activities are in compliance with company processes and practices.

38. ONEOK testified it has annual meetings to educate local emergency response officials and sends mailings to local response officials providing emergency contact information and details regarding leak identification and response procedures. ONEOK further testified its emergency response group is actively coordinating with the Williams County Emergency Officials to discuss emergency preparedness and response with respect to the Project.

From the foregoing Findings of Fact, the Commission now makes its:

### **Conclusions of Law**

1. The Commission has jurisdiction over ONEOK and over the subject matter of the Application under North Dakota Century Code chapter 49-22.1.
2. ONEOK is a utility as defined in North Dakota Century Code section 49-22.1-01(13).
3. The Project is a transmission facility as defined in North Dakota Century Code section 49-22.1-01(7).
4. The construction, operation, and maintenance of the Project will produce minimal adverse effects on the environment and upon the welfare of the citizens of North Dakota.
5. The Project is compatible with the environmental preservation and the efficient use of resources.
6. The construction, operation, and maintenance of the Project minimizes adverse human and environmental impact while ensuring continuing system reliability and integrity and ensuring that energy needs are met and fulfilled in an orderly and timely fashion.

From the foregoing Findings of Fact and Conclusions of Law, the Commission makes the following order:

### **Order**

The Commission orders:

1. ONEOK shall construct, operate, and maintain the Project in accordance with the Commission's Findings of Fact.
2. Certificate of Site Compatibility No. 214 is issued to ONEOK Bakken Pipeline, L.L.C., designating a corridor for the construction, operation, and maintenance of approximately 75 miles of 16-inch diameter natural gas liquids pipeline and associated facilities in Williams County, North Dakota. For purposes of this Certificate, the designated corridor generally consists of a 300-foot wide area centered on the designated route as depicted in Exhibit B.2 of the Application, Hearing Exhibit 1.
3. Route Permit No. 224 is issued to ONEOK Bakken Pipeline, L.L.C., designating a route for the construction, operation, and maintenance of approximately 75 miles of 16-inch diameter natural gas liquids pipeline and associated facilities in Williams County, North Dakota. For purposes of this Permit, the designated route is the route of the Project as depicted in Exhibit B.2 of the Application, Hearing Exhibit 1.
4. The Certification Relating to Order Provisions – Transmission Facility Siting with accompanying Tree and Shrub Mitigation Specifications executed February 25, 2020 is incorporated by reference and attached to this Order.
5. To the extent there are any conflicts or inconsistencies between ONEOK's Application and the Certification, the Certification provisions control.
6. ONEOK shall conduct additional review on the one remaining area of potential geologic instability within the Project corridor and consult with the NDGS regarding its review and proposed avoidance measures. ONEOK shall submit its consultation with the NDGS to the Commission prior to commencing construction in this area.
7. ONEOK shall obtain all remaining 500-foot waiver(s) and provide copies to the Commission prior to constructing the Project on such portion of the Project for which the waiver is applicable.
8. ONEOK shall obtain all other necessary licenses and permits prior to commencing construction on such portion of the Project for which the license and/or permit is required, and shall provide copies to the Commission prior to construction.

9. ONEOK is required to comply with all applicable laws, rules, and regulations in the event it desires to construct another or a different transmission pipeline facility than was specified in the Application within the corridor designated in this proceeding.

**PUBLIC SERVICE COMMISSION**

  
\_\_\_\_\_  
**Julie Fedorchak**  
**Commissioner**

  
\_\_\_\_\_  
**Brian Kroshus**  
**Chairman**

  
\_\_\_\_\_  
**Randy Christmann**  
**Commissioner**



STATE OF NORTH DAKOTA  
PUBLIC SERVICE COMMISSION

ONEOK Bakken Pipeline, L.L.C.  
16-Inch NGL Pipeline – Williams County  
Siting Application

Case No. PU-19-368

CERTIFICATION RELATING TO ORDER PROVISIONS  
TRANSMISSION FACILITY SITING

I am Todd McLinne, a representative of ONEOK Bakken Pipeline, L.L.C. ("Company") with authority to bind the Company to requirements to be set forth by the Commission in its Order and I certify the following:

1. Company understands and agrees that any Certificate of Corridor Compatibility or Route Permit issued by the Commission will be subject to the conditions and criteria set forth in Chapter 49-22.1 of the North Dakota Century Code and Chapter 69-06-08 of the North Dakota Administrative Code, and that Company shall be responsible for compliance with this order and conditions and criteria set forth in the applicable laws and rules.
2. Company agrees to comply with the rules and regulations of all other agencies having jurisdiction over any phase of the transmission facility including all city, township, and county zoning regulations.
3. Company understands and agrees that it shall obtain all other necessary licenses and permits, and shall provide copies of all licenses and permits to the Commission prior to construction activity associated with the transmission facility that requires said license or permit.
4. Company understands and agrees that any Certificate of Corridor Compatibility or Route Permit issued by the Commission is subject to suspension or revocation and may, in an appropriate and proper case, be suspended or revoked for failure to comply with the Commission's order, the conditions and criteria of the certificate or subsequent modification, or failure to comply with the applicable statutes, rules, regulations, standards, and permits of other state or federal agencies.
5. Company agrees to maintain records that will demonstrate that it has complied with the requirements of the Commission's order issuing a Certificate of Corridor Compatibility or Route Permit, and that it will preserve these records for Commission inspection at any reasonable time upon reasonable notice.
6. Company understands and agrees that the authorizations granted by any Certificate of Corridor Compatibility or Route Permit issued by the Commission for the

transmission facility are subject to modification by order of the Commission if deemed necessary to protect further the public or the environment.

**Construction:**

7. Company agrees to hold a preconstruction conference prior to commencement of any construction, which must include a Company representative, its construction supervisor, and a representative of Commission Staff, to ensure that Company fully understands the conditions set forth in the Commission's order.
8. Company understands and agrees that all cultural resource mitigation plans must be submitted to the North Dakota State Historic Preservation Office and approved prior to the start of any fieldwork and construction activity in the affected area.
9. Company understands and agrees that topsoil removal will begin when the Commission's third-party construction inspector is present at the Project site to observe that topsoil is properly removed and kept segregated from subsoil until replacement occurs. Company shall establish the date and time for the Commission's third-party construction inspector's topsoil removal oversight in the preconstruction conference.
10. Company agrees to inform the Commission and the Commission's third-party construction inspector of its intent to start construction on the transmission facility prior to the commencement of construction. Once construction has started, Company shall keep the Commission and the Commission's third-party construction inspector updated on construction activities on a monthly basis.
11. Company understands and agrees that the pipeline will be buried to a minimum depth from the ground surface to the top of the pipe of 48 inches in range land, 48 inches for cultivated land, 48 inches at the bottom of the ditch for road crossings, and 72 inches across undeveloped section lines.
12. Company understands and agrees that all topsoil, up to 12 inches, or topsoil to the depth of cultivation, whichever is greater, over and along trench areas where cuts will be made, must be carefully stripped and segregated from the subsoil. Any area on which excavated subsoil will be placed must also be stripped of topsoil. The stripped topsoil must not be stockpiled in natural drainages, and must be protected from water erosion. Care must be taken to protect topsoil from unnecessary compaction by heavy machinery. Unless otherwise approved by the Commission, topsoil must be removed before topsoil freezes in the late fall/ early winter to the point that frost inhibits proper soil segregation. After backfilling with subsoil is completed, any excess subsoil must be placed over the excavation area, blending the grade into existing topography. Topsoil must be replaced over areas from which it was stripped only after the subsoil is replaced.

13. Company understands and agrees that all buried facility crossings of graded roads must be bored unless the responsible governing agency specifically permits Company to open cut the road.
14. Company understands and agrees that staging areas or equipment shall not be located on land owned by a person other than Company unless otherwise negotiated with landowners.
15. Company understands and agrees that if any cultural resource, paleontological site, archeological site, historical site, or grave site is discovered during construction, it must be marked, preserved and protected from further disturbances until a professional examination can be made and a report of such examination is filed with the Commission and the State Historical Society.
16. Company understands and agrees that construction must be suspended when weather conditions are such that construction activities will cause irreparable damage to roads or land, unless adequate protection measures are taken by Company.
17. Company understands and agrees that the Commission has authority to stop Project construction activities in the event of a probable violation of the siting laws, siting rules, or applicable Commission Orders if, in the opinion of the Commission, construction activities are likely to result in irreparable or significant harm.

**Restoration and Maintenance:**

18. Company understands and agrees that it shall, as soon as practicable upon the completion of the construction of the transmission facility, restore the area affected by the activities to as near as is practicable to the condition as it existed prior to the beginning of construction.
19. Company understands and agrees that all pre-existing township and county roads and lanes used during construction must be repaired or restored to a condition that is equal to or better than the condition prior to the construction of the transmission facility and that will accommodate their previous use, and that areas used as temporary roads or working areas during construction must be restored to their original condition.
20. Company understands and agrees that reclamation, fertilization, and reseeding is to be done according to the Natural Resources Conservation Service recommendations, unless otherwise specified by the landowner and approved by the Commission.

21. Company will fulfill its obligation for reclamation and maintenance of the approved transmission facility right-of-way, transmission facility, and associated facilities continuing throughout the life of the transmission facility.
22. Company will repair all fences and gates removed or damaged during all phases of construction and operation of the transmission facility.
23. Company will repair or replace all drainage tile broken or damaged as a result of construction and operation of the transmission facility.
24. Company agrees to comply with the Tree and Shrub Mitigation Specifications, attached.
25. Company understands and agrees that it shall remove all waste that is a product of construction and operation, restoration, and maintenance of the site, and properly dispose of it on a regular basis.
26. Company understands and agrees that it shall provide any necessary safety measures for traffic control or to restrict public access to the transmission facility.

**Communication with Landowners and PSC:**

27. Company understands and agrees that, prior to beginning construction of the transmission facility at a location, it shall send a letter to each landowner with whom an easement was executed for that location specifying the name and phone number of the company representative who is responsible for receiving and resolving landowner issues for the life of the easement.
28. Company understands and agrees that it will file with the commission the name and phone number of the current company representative who is responsible for receiving and resolving landowner issues for the transmission facility. The company will update this information whenever there is a change to the current company representative for the life of all easements for the transmission facility.
29. Upon request, Company agrees to provide the Commission with engineering design drawings of the transmission facility prior to construction.
30. Company understands and agrees that it shall advise the Commission as soon as reasonably possible of any extraordinary events which take place at the site of the transmission facility, including injuries to any person.
31. Company agrees to report to the Commission, as soon as reasonably possible, the presence in the permit area of any critical habitat or threatened or endangered species of which Company becomes aware and which were not previously reported to the Commission.

32. Company understands and agrees that it shall inform the Commission in writing of any plans to modify the transmission facility or of any plans to modify the site plan for the transmission facility.
33. Company agrees to provide the Commission with both an electronic and a paper copy of the corridor approved by the Commission and the facility design specifications for the construction of the transmission facility showing the location of the transmission facility as built, and will provide this information within 3 months of the completion of the construction. Company also agrees to provide an electronic version of the corridor approved by the Commission and the facility design specifications for the construction of the transmission facility showing the location of the transmission facility as built that can be imported into ESRI GIS mapping software within 3 months of the completion of the construction. This electronic map data must be referenced to the North Dakota coordinate system of 1983, North and/or South zones US Survey feet (NAD 83) UTM Zone 13N or 14N feet (NAD 83), or geographic coordinate system (WGS 84) feet. The vertical data must be in the appropriate vertical datum for the coordinate system used. All submissions must specify the datum in which the data was developed.
34. Company shall notify the Commission as soon as reasonably possible if any damage, as defined by North Dakota Century Code Chapter 49-23, occurs to underground facilities during construction conducted under the certificate or permit issued in this proceeding. In the event of any damage to underground facilities, Company shall suspend construction in the vicinity of the damage until compliance with One-Call Excavation Notice System requirements under North Dakota Century Code Chapter 49-23 has been determined.

**Route Adjustments Before or During Construction:**

35. Company agrees to utilize the following procedures if Company seeks a route adjustment before or during construction of the pipeline, pursuant under N.D.C.C. §49-22.1-15.
36. Company will specifically identify which subsection of NDCC 49-22.1-15 it is requesting the adjustment under. Company will file the name and contact information for a key contact person for the purposes of notice and communication during the adjustment application.
37. **ROUTE ADJUSTMENT WITHIN DESIGNATED CORRIDOR, NO AVOIDANCE AREA AFFECTED:** Before conducting any construction activities for any adjustment to the designated route within the designated corridor under NDCC 49-22.1-15(1), the Company will file:

- a. Certification and supporting documentation affirming that construction activities will be within the designated corridor, will not affect any known exclusion or avoidance areas within the designated corridor;
- b. Certification and supporting documentation, including a map meeting the requirements of N.D. Admin. Code § 69-06-04-01(2)(n) identifying the designated corridor, route and the route adjustment;
- c. Certification that Company will comply with the Commission's order, law and rules designating the corridor and route.

38. **ROUTE ADJUSTMENT WITHIN DESIGNATED CORRIDOR, AVOIDANCE AREA AFFECTED:** Before adjusting the route of a gas or liquid transmission line under NDCC 49-22.1-15(2), within the designated corridor that may affect an avoidance area, and before conducting any construction activities for any adjustment to the designated route within the designated corridor, the Company will file:

- a. A specific description of the avoidance area expected to be impacted, including a map meeting the requirements of N.D. Admin. Code § 69-06-04-01(2)(n) identifying:
  - i. the designated corridor, route and the route adjustment;
  - ii. all exclusion and avoidance areas within the portion of the designated corridor containing the route adjustment
- b. Certification and supporting documentation affirming:
  - i. That construction activities will be within the designated corridor
  - ii. That construction activities will not affect any known exclusion area
- c. All field studies performed on the portion of the designated corridor containing the route adjustment;
- d. Specific information about any mitigation measures Company will take within the adjustment area;
- e. Certification that each owner of real property on which the adjustment is to be located and any applicable governmental entity with an interest in the same adjustment area do not oppose the adjustment;
- f. Certification that unless the Commission previously authorized the impact to the same avoidance area, that the utility has good cause and a specific reason to impact the avoidance area and a reasonable alternative does not exist;
- g. Certification that Company will comply with the Commission's order, law and rules designating the corridor and route.

Company acknowledges and agrees that:

1. Written authorization from the Commission for impacting the avoidance area is necessary prior to commencement of construction activity unless the Commission fails to act within ten working days of receipt of filing a complete adjustment application, in which case the adjustment is deemed approved.
2. The initiation of the ten working days begins upon receipt of a complete filing, to include Company's certifications, supporting documentation and maps. However, Commission may extend the ten working day provision if Company, in the person of the key contact referenced above, is informed of the reason additional time is necessary for extension and has no objection to an extension.

39. **ROUTE ADJUSTMENT OUTSIDE DESIGNATED CORRIDOR, NO AVOIDANCE AREA AFFECTED:** Before adjusting the route of a gas or liquid transmission line under NDCC 49-22.1-15(3), outside the designated corridor and not affecting any exclusion and avoidance area, before conducting any construction activities for any adjustment to the designated route outside the designated corridor, the Company will file:

- a. Certification and supporting documentation affirming that construction activities will not affect any known exclusion or avoidance areas,
- b. Certification and supporting documents stating the length of the proposed route outside of the corridor and a map meeting the requirements of N.D. Admin. Code § 69-06-04-01(2)(n) identifying the designated corridor, corridor adjustment, designated route and the route adjustment;
- c. Certification that each owner of real property on which the adjustment is to be located and any applicable governmental entity with an interest in the same adjustment area do not oppose the adjustment; and
- d. Detailed field studies indicating exclusion and avoidance areas for the proposed adjustment area; and
- e. Certification that Company will comply with the Commission's order, law and rules designating the corridor and route.

40. **ROUTE ADJUSTMENT OUTSIDE DESIGNATED CORRIDOR, AVOIDANCE AREA AFFECTED:** Before adjusting the route of a gas or liquid transmission line under NDCC 49-22.1-15(4), outside the designated corridor that may affect an avoidance area, and before conducting any construction activities for any adjustment to the designated route outside the designated corridor, the Company will file:

- a. A specific description of the avoidance area expected to be impacted, including a map meeting the requirements of N.D. Admin. Code § 69-06-04-01(2)(n) identifying:
  - i. the designated corridor, corridor adjustment, route and the route adjustment;


- ii. all exclusion and avoidance areas within the adjustment area
- b. Certification that construction activities will not affect any known exclusion area;
- c. Certification that the utility has good cause and a specific reason to impact the avoidance area and a reasonable alternative does not exist within the designated corridor and route;
- d. Certification that each owner of real property on which the adjustment is to be located and any applicable governmental entity with an interest in the same adjustment area do not oppose the adjustment;
- e. Provide specific information about any mitigation measures Company will take within the adjustment area;
- f. Detailed field studies indicating exclusion and avoidance areas for the proposed adjustment area; and
- g. Certification that Company will comply with the Commission's order, law and rules designating the corridor and route.

Company acknowledges and agrees that:

- 1. Written authorization from the Commission for impacting the avoidance area is necessary prior to commencement of construction activity unless the Commission fails to act within ten working days of receipt of filing a complete adjustment application, in which case the adjustment is deemed approved.
  - 2. The initiation of the ten working days begins upon receipt of a complete filing, to include Company's certifications, supporting documentation and maps. However, Commission may extend the ten working day provision if Company, in the person of the key contact referenced above, is informed of the reason additional time is necessary for extension and has no objection to an extension.
41. When applicable, Company may submit the field studies from the original application for the corridor and route provided they cover the adjustment area.

Dated this 25th day of February, 2020.

ONEOK BAKKEN PIPELINE, L.L.C.

By   
Todd McKimney

Its VP Construction Projects



**STATE OF NORTH DAKOTA  
PUBLIC SERVICE COMMISSION**

**ONEOK Bakken Pipeline, L.L.C.  
16-Inch NGL Pipeline – Williams County  
Siting Application**

**Case No. PU-19-368**

**Tree and Shrub Mitigation Specifications**

**Inventory**

Prior to cutting or clearing trees or shrubs for construction:

- All trees one-inch or greater in diameter at breast height must be inventoried to record the location, number, and species.
- All shrubs and all coniferous trees of any diameter must be inventoried to record the location, number, and species.

**Clearing**

The maximum width of tree and shrub removal is 50 feet, unless otherwise approved by the Commission.

**Replacement**

1. Landowners must be given the option to have trees and shrubs that are removed from their property replaced on their property. The landowner may waive this option in writing. If the landowner waives this option, the company shall plant replacement trees and shrubs in an alternate location in the same region, if practical.
2. Trees and shrubs must be replaced on a minimum two-to-one basis. The company shall develop a Tree and Shrub Mitigation Plan (Plan) in consultation with landowners who are seeking replacement trees and shrubs and in accordance with USDA-NRCS-North Dakota Field Office Technical Guide: Windbreak and Woodland Tree Care and Management. The guidelines outlined in the Technical Guide shall be followed until filing of the Plan summary outlined in number 5 below.
3. The purpose of the company's Tree and Shrub Mitigation Plan is to create sustainable plantings, appropriate for the local soil and growing conditions that will provide long-term benefit to landowners, farmers and ranchers, the community, wildlife and the environment.
4. The Plan, including the proposed number, variety, type, location, and approximate date for plantings, shall be filed with and approved by the Commission.
5. Two years after completion of the plan, the company must file a summary documenting how the plan achieved the purpose outlined in number 3 above. The summary must also report the number of surviving replacement trees and shrubs.
6. The Commission will consider, on a limited basis as conditions warrant, mitigation plans that provide long-term wildlife habitat and conservation benefits but do not involve the replanting of trees and shrubs.

**PUBLIC SERVICE COMMISSION**  
**STATE OF NORTH DAKOTA**

**Route Permit Number 224**

*This is to certify that the Commission has designated a transmission facility route for ONEOK Bakken Pipeline, L.L.C. for the construction, operation, and maintenance of approximately 75 miles of 16-inch diameter natural gas liquids pipeline and associated facilities in Williams County, North Dakota.*

*This permit is issued in accordance with the Order of this Commission dated April 1, 2020, in Case No. PU-19-368 and is subject to the conditions and limitations noted in the Order.*

*Bismarck, North Dakota, April 1, 2020.*

**ATTEST:**

**PUBLIC SERVICE COMMISSION**

  
\_\_\_\_\_  
**Executive Secretary**

  
\_\_\_\_\_  
**Commissioner**

**PUBLIC SERVICE COMMISSION**  
**STATE OF NORTH DAKOTA**

**Certificate of Corridor Compatibility Number 214**

*This is to certify that the Commission has designated a transmission facility corridor for ONEOK Bakken Pipeline, L.L.C. for the construction, operation, and maintenance of approximately 75 miles of 16-inch diameter natural gas liquids pipeline and associated facilities in Williams County, North Dakota.*

*This certificate is issued in accordance with the Order of the Commission dated April 1, 2020, in Case No. PU-19-368 and is subject to the conditions and limitations noted in the Order.*


*Bismarck, North Dakota, April 1, 2020.*

**ATTEST:**

**PUBLIC SERVICE COMMISSION**



**Executive Secretary**



**Commissioner**