

-Info-Public Service Commission

From: Will Sullivan <wsullivan@outriggerenergy.com>
Sent: Wednesday, July 1, 2020 5:21 PM
To: -Info-Public Service Commission; Renfandt, Adam L.
Cc: Andrew Perdue; Wade Janecek; Russ Kimmitt
Subject: PU-20-082: Bill Sanderson Gas Plant - Permits & Authorizations
Attachments: NDR11-0000 - NDPDES SW Discharge Authorization.pdf; NDPDES Notice of Intent.pdf; NDPDES Notice of Coverage.pdf; PTC20021_0_0 - Air Permit.pdf; LU-0040-20 OE2 North BOCC Decision Letter.pdf; 20-000075 - Permit_Residue Compressor Building.pdf; 20-000076 - Permit_Propane Compressor Building.pdf; 20-000077 - Permit_Control & Maintenance Building.pdf

CAUTION: This email originated from an outside source. Do not click links or open attachments unless you know they are safe.

Adam,

Attached are copies of the following permits & authorizations for PU-20-082 (OE2N Bill Sanderson Gas Plant):

- NDR11-0000: NDPDES Stormwater Discharge Authorization
 - NDPDES Notice of Intent
 - NDPDES Notice of Coverage
- PTC20021_0_0 – Air Permit (Permit-to-Construct)
- LU-0040-20 OE2 North BOCC Decision Letter
- 20-000075 - Permit_Residue Compressor Building
- 20-000076 - Permit_Propane Compressor Building
- 20-000077 - Permit_Control & Maintenance Building

Let me know if submittal of these documents by email is sufficient or if hard copies of the documents need to be formally filed.

Thanks,
Will



[Will Sullivan](#)

1200 Seventeenth Street | Suite 900
Denver, CO 80202
720.361.2571 direct | 720.638.7312 main
406.498.5522 mobile

60 PU-20-82 Filed 07/02/2020 Pages: 47
Permits and Authorizations
Outrigger Energy
Will Sullivan

Permit No: NDR11-0000
Effective Date: April 1, 2020
Expiration Date: March 31, 2025

AUTHORIZATION TO DISCHARGE UNDER THE
NORTH DAKOTA POLLUTANT DISCHARGE ELIMINATION SYSTEM

In compliance with Chapter 33.1-16-01 of the North Dakota Department of Environmental Quality rules as promulgated under Chapter 61-28 (North Dakota Water Pollution Control Act) of the North Dakota Century Code,

Facilities both qualifying for and satisfying the requirements identified in Part I of the permit

are authorized to discharge stormwater associated with construction activity

to waters of the state

provided all the conditions of this permit are met.

This permit and the authorization to discharge shall expire at midnight,
March 31, 2025.

Signed this 30 day of March, 2020.



Karl H. Rockeman, P.E.
Director
Division of Water Quality

This page is intentionally left blank

Table of Contents

- I. PERMIT COVERAGE AND LIMITATIONS 4**
 - A. Discharges Covered 4**
 - B. Discharges Not Covered 5**
 - C. Obtaining Coverage and Authorization Effective Date 5**
 - D. Notice of Intent Process 6**
 - E. Notice of Termination (NOT) 7**
 - F. Transfer of Ownership or Control 7**
- II. STORMWATER DISCHARGE REQUIREMENTS 8**
 - A. Prohibition of Non-Stormwater Discharges 8**
 - B. Releases in Excess of Reportable Quantities 8**
 - C. Stormwater Pollution Prevention Plans 8**
 - D. Local Requirements 14**
 - E. Final Stabilization 14**
- III. SELF MONITORING AND REPORTING 15**
 - A. Inspection and Maintenance Requirements 15**
 - B. Records Location 17**
- IV. STANDARD CONDITIONS 17**
 - A. COMPLIANCE RESPONSIBILITIES BP 2019.05.29 17**
 - B. GENERAL PROVISIONS 20**
- V. DEFINITIONS 22**
- Appendix 1 – Erosion and Sediment Control Requirements 25**

I. PERMIT COVERAGE AND LIMITATIONS

A. Discharges Covered

1. This permit applies to all areas within the state of North Dakota, except for those areas defined as Indian Country. Construction activity located within Indian Country within the state of North Dakota must obtain a permit through the United States Environmental Protection Agency. If the construction activity is located with the jurisdiction of the state of North Dakota, and the United States Environmental Protection Agency, a permit must be obtained from both regulatory entities.
2. This permit applies to stormwater discharges associated with construction activity and small construction activity as defined in Title 40 of the Code of Federal Regulations (CFR), Parts 122.26(b)(14)(x) and (b)(15), respectively. The reference to construction activity in this permit includes both large construction activity and small construction activity as described below.
 - a. Large construction activity includes clearing, grading and excavation, that disturbs land of equal to or greater than five (5) acres and includes the disturbance of less than five (5) acres of total land area that is a part of a larger common plan of development or sale if the larger common plan will ultimately disturb five (5) acres or more.
 - b. Small construction activity includes clearing, grading and excavation, that disturbs land of equal to or greater than one (1) acre, and includes the disturbance of less than one (1) acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater that one (1) and less than five (5) acres.
3. This permit applies to discharges of stormwater from construction activity identified in Part I(A)(1)-(2) associated with oil and gas exploration, production, processing or treatment operations, or transmission facilities resulting in the discharge of a reportable quantity for which notification is required pursuant to 40 CFR 110.6, 40 CFR 117.21, or 40 CFR 302.6 or contributes to a violation of a water quality standard.
4. Stormwater discharges from support activities (e.g., equipment staging yards, material storage areas, excavated material disposal areas, borrow areas) may be covered by this permit as part of a related construction site. The support activities may only be in association with one project. If the support activity is associated with more than one project, a separate stormwater permit (Industrial or mining, extraction or paving material preparation) is required.
5. Certain non-stormwater discharges from facilities covered by this permit and meeting the requirements specified in Part II(A).
6. Stormwater discharges from construction activity covered by the previous permit, issued April 1, 2015, where a notice has been submitted to obtain coverage under this permit.
7. Projects which have obtained coverage under this permit shall amend and implement a Stormwater Pollution Prevention Plan (SWPPP) that meets the requirements of this permit within ninety (90) days of the effective date of this permit.
8. Discharges from dewatering activities related to construction activities (discharges of uncontaminated stormwater, uncontaminated groundwater, and uncontaminated surface water).
9. Local Authority. This permit does not preempt or supersede the authority of local agencies or operators of municipal separate storm sewer systems to prohibit, restrict, or control discharges of stormwater to storm sewer systems or other water courses within their jurisdiction.

B. Discharges Not Covered

1. Stormwater discharges associated with industrial activity from any source other than construction activities described in Part I(A).
2. Post-construction discharges from industrial activity that originate from the site after construction activities have been completed at the site. Industrial and post-construction stormwater discharges may need to be covered by a separate stormwater permit.
3. The placement of fill into waters of the state requiring local, state, or federal authorizations (such as U.S. Army Corps of Engineers Section 404 permits).
4. This permit does not substitute for obligations under the National Environmental Policy Act (NEPA), Endangered Species Act (ESA), Wild and Scenic Rivers Act, or National Historic Preservation Act (NHPA), it is the permittees responsibility to ensure the project and resulting discharges comply with the respective requirements.
5. Discharges to waters for which there is a total maximum daily load (TMDL) allocation are not covered unless you develop a Stormwater Pollution Prevention plan (SWPPP) that is consistent with the assumptions and requirements in the approved TMDL. To be eligible for coverage under this general permit, the SWPPP must incorporate the conditions applicable to the discharge necessary for consistency with the assumptions, allocations and requirements of the TMDL. If a specific numeric wasteload allocation has been established that would apply to discharges from construction activity, the permittee must incorporate that allocation into the SWPPP and implement necessary steps to meet that allocation. Information about TMDL allocations may be found at the following website: deq.nd.gov/WQ.
6. Stormwater discharges that the department determines will cause or have the reasonable potential to cause or contribute to a violation of the standards for quality for waters of the state (North Dakota Administrative Code [NDAC] 33.1-16-02.1).
7. Discharges from hydrostatic testing, well points, water line disinfection, treatment of refined petroleum contaminated groundwater or surface water, treatment of crude oil contaminated groundwater or surface water, and oil and gas production water.
8. Discharges of wash water using detergents, wastewater, and sanitary waste.

C. Obtaining Coverage and Authorization Effective Date

1. To obtain authorization under this general permit for stormwater discharges you must submit a complete notice of intent (NOI) and develop a SWPPP in accordance with Part II(C) of this permit. A SWPPP must be in place as a condition of the permit and a copy of the SWPPP must be retained by the permittee.
2. Permit coverage will become effective seven (7) days after you submit a complete NOI unless otherwise notified by the department (based on the department receipt date).
3. Upon the effective date of permit coverage, permittees are authorized to discharge stormwater from eligible activities under the terms and conditions of this permit.

D. Notice of Intent Process

1. Applicants must use a NOI form or electronic NOI to complete the application. The NOI form or electronic NOI can be found at: deg.nd.gov/WQ. Submission of data contained within the NOI must be in compliance with the electronic reporting requirements found in 40 CFR 127.
2. NOI Content and Conditions.
 - a. The owner, or owner jointly with the operator (usually the general contractor), shall submit a completed NOI for this permit. The owner is responsible for compliance with all terms and conditions of this permit. The operator has day to day supervision of construction activities and is jointly responsible with the owner for compliance with the permit conditions as they pertain to the construction activities delegated to the operator.
 - b. The NOI shall contain, at a minimum, the following information:
 - 1) Owner name, mailing address, and phone number;
 - 2) Project contact name, phone number, and e-mail address;
 - 3) Project/site name;
 - 4) Project/site location (street address; section, township, range) and county;
 - 5) Project/site latitude and longitude;
 - 6) A brief description of the construction activity;
 - 7) The anticipated start date and the anticipated completion date for the project (if known);
 - 8) The estimated total area of the site and the total area of disturbance in acres;
 - 9) The name of receiving water(s), or the name of the municipal storm sewer system and receiving water; and
 - 10) The signature of the applicant(s), owner (and operator if co-applicants) signed in accordance with the Signatory Requirements in Part IV(A)(6) of this permit.
 - c. A SWPPP (Part II(C)) for the project must be prepared and available for review, upon request, by the department at the time of application. Permittees are not required to submit the SWPPP with the NOI unless otherwise notified by the department.
3. For residential construction activity occurring within a common plan of development (such as a subdivision) subject to the permit requirements, coverage may be obtained by the following:
 - a. The owner of the lot(s) shall submit one NOI for all of the owner's construction activity within the common plan of development, or
 - b. The operator, such as a homebuilder who may represent one or more lot owners, shall submit one NOI for all of the operator's construction activity within the common plan of development. Additional phases of the common plan of development may be included under the initial NOI and permit coverage.

In addition, a SWPPP must be developed and implemented for the permittee's activities within the common plan of development. Additional phases of the common plan of development may be included provided the SWPPP is amended to include the additional area or phases.

4. For construction activity associated with oil and gas exploration, production, processing, treatment operations, or transmission facilities, which discharge contaminated stormwater, an NOI may be submitted for individual project sites or for an area of operations such as well field or by county.

E. Notice of Termination (NOT)

1. Permittees wishing to terminate coverage under this permit must submit a Notice of Termination (NOT) signed in accordance with Part IV(A)(6) of this permit. Submission of data contained within the NOT must be in compliance with the electronic reporting requirements found in 40 CFR 127. Compliance with the conditions of this permit is required until a NOT is submitted to the department.
2. Permittees may only submit a NOT after one of the following conditions have been met:
 - a. Final stabilization (Part II(E)) has been achieved on all portions of the site for which the permittee is responsible.
 - b. Another owner/operator/permittee has assumed control in accordance with the transfer provisions (Part I(F)) over all areas of the site that have not achieved final stabilization.
 - c. For residential construction only, a NOT is not required for each lot that is sold, transferred, or has achieved final stabilization. The permittee must modify the SWPPP to indicate that permit coverage is no longer required for that lot. The SWPPP shall indicate the reason why coverage is no longer needed and the date the lot was sold, transferred, or achieved final stabilization. In order to terminate coverage, all lots under the control of the owner or operator must be sold, transferred, or achieved final stabilization (Part II(E)).

F. Transfer of Ownership or Control

1. When the owner or operator of a construction project changes, the new owner or operator must submit a written request for permit transfer/modification within fourteen (14) days of assuming control of the site or commencing work on-site, or of the legal transfer, sale or closing on the property; except as provided in Part I(F)(2). Late submittals will not be rejected; however the department reserves the right to take enforcement for any unpermitted discharges or permit noncompliance. For stormwater discharges from construction activities where the owner or operator changes, the new owner or operator can implement the original SWPPP created for the project or develop and implement their own SWPPP. Permittees shall ensure either directly or through coordination with other operators that their SWPPP meets all terms and conditions of this permit and that their activities do not interfere with another party's SWPPP.
2. A permit transfer/modification request is not required for the legal transfer, sale or closing on a property between permittees covered by this permit. Examples include the sale of a property parcel from a developer to a builder, or the transfer of an easement from a developer to a local government authority. If the new party is not covered by this permit at the time of transfer or sale, then the new owner/operator must submit a completed NOI within fourteen (14) days of assuming control of the site.

II. STORMWATER DISCHARGE REQUIREMENTS

A. Prohibition of Non-Stormwater Discharges

The discharge of wastewater is not authorized by this permit. The following sources of non-stormwater discharges are allowed if they are not a significant source of pollution and are identified in the SWPPP: fire-fighting activity, fire hydrant flushing, potable water line flushing, equipment wash down without detergents or hazardous cleaning products, uncontaminated foundation drains, springs, surface water, lawn watering, chemical treatment of stormwater, and air conditioning condensate. Impervious surface wash water may not be directed into any surface water or storm drain inlet unless appropriate pollution prevention measures have been implemented. Non-stormwater discharges may not come into contact with oil and grease deposits or any other toxic or hazardous materials (unless cleaned up using dry clean-up methods). The SWPPP must include a description of the pollution prevention measures to be implemented while non-stormwater discharges are occurring.

B. Releases in Excess of Reportable Quantities

This permit does not relieve the permittee of the reporting requirements of 40 CFR 110, 40 CFR 117, and 40 CFR 302, nor the reporting requirements found in NDAC 33.1-16-02.1. Any release which meets any reporting requirement shall be reported to the department in accordance with Part IV(A)(7).

C. Stormwater Pollution Prevention Plans

All permittees shall implement a SWPPP for any construction activity requiring this permit until final stabilization is achieved. The SWPPP and revisions are subject to review by the department. The objectives of the SWPPP are to identify potential sources of sediment and other sources of pollution associated with construction activity, and to ensure practices are implemented and maintained to reduce the contribution of pollutants in stormwater discharges from the construction site to waters of the state and storm sewer systems. Stormwater management documents developed under other regulatory programs may be included or incorporated by reference in the SWPPP or used in whole as a SWPPP if it meets the requirements of this part. A partially complete SWPPP is acceptable when it clearly identifies the item(s) to be completed, the person(s) responsible for completing the item(s) and the deadline for completing the item(s). The SWPPP must be completed prior to the start of construction (or the applicable construction phase).

The SWPPP may identify more than one permittee and may specify the responsibilities of each permittee by task, area, and/or timing. Permittees may coordinate and prepare more than one SWPPP to accomplish this. However, in the event there is a requirement under the SWPPP for which responsibility is ambiguous or is not included in the SWPPP, each permittee shall be responsible for implementation of that requirement. Each permittee is responsible for assuring that their activities do not render another permittee's controls ineffective.

The SWPPP must incorporate the requirements provided in Appendix 1 and shall include the following information.

1. **Site Description.** Each SWPPP shall provide a description of the construction activity and potential sources of pollution as indicated below:
 - a. A description of the overall project and the type of construction activity;
 - b. Estimates of the total area of the site and the total area that is expected to be disturbed by excavation, grading, grubbing, or other activities during the life of the project;

- c. A proposed timetable/schedule, or chart, of activities that includes major phases/stages, BMP implementation, BMP removal, disturbances, and stabilization for major portions of the site;
- d. A description of the soil within the disturbed area(s);
- e. The name of the surface water(s) and municipal storm sewer system at or near the disturbed area that will receive stormwater runoff from the project site; and
- f. A site map which indicates the following items as applicable (more than one (1) map may be needed). If an item is not applicable, provide rationale describing why the item is not applicable to the construction activity:
 - 1) Location of project;
 - 2) Project boundaries;
 - 3) Areas of ground disturbance during each phase/stage of the project;
 - 4) Areas where disturbance will not occur, such as avoidance areas (e.g. wetlands, critical habitat, Threatened and Endangered Species, etc);
 - 5) Drainage patterns including flow direction (run-on and runoff);
 - 6) Discharge points and storm sewer system inlets which the site drains to or may be affected by the activity;
 - 7) Location of all temporary and permanent sediment and erosion controls during each particular phase;
 - 8) Location of any stormwater conveyances such as retention ponds, detention ponds, ditches, pipes, swales, stormwater diversions, culverts, and ditch blocks;
 - 9) Location of potential sources of pollution (e.g. portable toilets, trash receptacles, etc.) or areas where potential sources of pollution cannot be located;
 - 10) Location of soil stockpiles;
 - 11) Identify steep slopes;
 - 12) Surface waters, including an aerial extent of wetlands;
 - 13) Location of surface water crossings;
 - 14) Locations where stormwater is discharged to surface waters;
 - 15) Location of dewatering discharge points;
 - 16) Locations where chemical treatment of stormwater will be performed, including discharge points;
 - 17) Fueling locations and storage, vehicle and equipment maintenance areas, designated wash water collection site, lubricant and chemical storage, paint storage, material storage, staging areas, and debris collection area;
 - 18) Location of any impervious surfaces upon completion of construction; and
 - 19) Where included as part of the project, the site maps for off-site concrete/asphalt batch plants, equipment staging areas, borrow sites or excavated fill material disposal sites. Site maps must show items 1 through 18 of this section.
- g. Projects that discharge stormwater which flows to a water body listed as impaired under section 303(d) of the Federal Clean Water Act due to sediment, suspended solids or turbidity must identify the water body and impairment in the SWPPP. The department's 303(d) list may be found at the following website under Integrated Reports: deq.nd.gov/WQ
- h. For water bodies which have a TMDL, the SWPPP must describe and conform to the Waste Load Allocations (WLA) of the water body. Information about TMDL allocations may be found at the following website: deq.nd.gov/WQ

2. **Narrative.** The SWPPP must include a narrative description of the selected operational controls and sediment and erosion controls as outlined in Part II(C)(3), Part II(C)(4), and Appendix 1 of this permit. When applicable, a description of the requirements for any additional environmental regulations and local requirements related to the project, as it relates to waters of the state, must also be included or incorporated by reference (e.g. The Wild and Scenic Rivers Act, The National Historic Preservation Act, The Endangered Species Act, Fish and Wildlife Coordination Act, National Environmental Policy Act, Section 404 of the Clean Water Act, etc.).

The narrative shall describe at a minimum:

- a. The installation, removal (if applicable), and maintenance requirements of selected Best Management Practices (BMPs) for each phase/stage of construction activity;
 - b. The rationale for the selection of all BMPs (the design should be included where appropriate);
 - c. Whether selected BMPs are temporary or permanent;
 - d. Any descriptions of infeasibility or explanations as required in Part II of this permit.
3. **Operational Controls.** The SWPPP shall describe the BMPs used in day to day operations on the project site that reduce the contribution of pollutants in stormwater runoff.
- a. The SWPPP must identify a person knowledgeable and experienced in the application of erosion and sediment control BMPs who will oversee the implementation of the SWPPP, and the installation, inspection, and maintenance of the erosion and sediment control BMPs before and during construction until a NOT is filed or the permit is transferred. A knowledgeable and experienced person is someone who meets the requirements of Part II(C)(3)(e) of this permit.
 - b. The owner shall develop a chain of responsibility with all operators on the site to ensure that the SWPPP will be implemented and stay in effect until the construction project is complete, the entire site has undergone final stabilization, and a NOT has been submitted to the department.
 - c. The SWPPP must include a description of good housekeeping practices used to maintain a clean and orderly site. The SWPPP shall describe how litter, debris, chemicals and parts will be handled to minimize exposure to stormwater. The SWPPP also shall describe what measures will be used to reduce and remove sediment tracked off site by vehicles or equipment. In addition, the SWPPP shall describe methods which will be used to reduce the generation of dust that could be discharged in stormwater from the project.
 - d. The SWPPP shall describe spill prevention and response procedures where potential spills can occur. Specific handling procedures, storage requirements, spill containment, cleanup procedures, and disposal must be identified. Storage structures for petroleum products and other chemicals shall have adequate leak and spill protection to prevent any spilled materials from entering waters of the state or storm sewer systems.

The potential discharge of hazardous substances in stormwater discharges shall be minimized by including measures detailed in the SWPPP to prevent and respond to releases of hazardous substances. If a reportable quantity release occurs, the SWPPP shall be revised to prevent the reoccurrence of such a release.

- e. The SWPPP shall outline how employees and responsible parties shall be trained on the implementation of the SWPPP. Training must be provided at least annually, as new employees or responsible parties are hired, or as necessary to ensure compliance with the SWPPP and the general permit. Employees and responsible parties include individuals who are responsible for design, installation, maintenance, and repair of stormwater controls and conducting inspections.

- 1) On-site personnel must understand the requirements of this permit as it pertains to their role in implementing the SWPPP. On-site personnel must know:
 - a. The purpose of the SWPPP, requirements of the SWPPP, and how the SWPPP will be implemented;
 - b. The location of all BMPs identified in the SWPPP; and
 - c. Correct installation, function, maintenance, and removal (if applicable) of BMPs identified in the SWPPP.
 - 2) Personnel responsible for performing site inspections must understand when inspections must be conducted (Part III(A)), what must be inspected (Part II(C)(7)), how to record findings, and when to initiate and properly document corrective actions.
 - 3) Maintenance personnel must understand when maintenance must be performed on BMPs in order to maintain properly functioning BMPs and what needs to be recorded for corrective actions/maintenance records in accordance with Part III(A)(5) of this permit.
- f. The SWPPP must describe how concrete grindings and slurry will be managed. Wastewater from concrete washout, cleanout or washout from stucco, paint, joint compound, and other building materials shall not be discharged to waters of the state, storm sewer systems, or curb and gutter systems.
- 1) Wash water must be collected in leak-proof containers or leak-proof pits. Containers or pits must be designed and maintained so that overflows cannot occur due to inadequate sizing, precipitation events, or snowmelt.
- g. The SWPPP shall describe any dewatering activities planned at the site. Dewatering or basin draining (e.g., pumped discharges, trench/ditch cuts for drainage) related to the permitted activity must be managed with appropriate BMPs, such that the discharge does not adversely affect the receiving water. The following conditions apply to dewatering activities:
- 1) Dewatering is limited to uncontaminated stormwater, surface water, and groundwater that may collect on-site and those sources identified in Part II(A), if they are not a significant source of pollution. A separate permit must be obtained to discharge water from other sources such as hydrostatic testing of pipes, tanks, or other similar vessels; disinfection of potable water lines; pump testing of water wells; and the treatment of refined petroleum contaminated groundwater or surface water.
 - 2) The permittee(s) must operate the discharge to minimize the release of sediment and provide adequate BMPs where necessary to minimize erosion due to the discharge. Discharges must not lead to the deposition of sediment within stormwater conveyance systems or surface waters. Discharges must not cause or potentially cause a visible plume within a surface water body.
 - 3) When dewatering, utilize structures or BMPs which allow for draw down to occur from the surface of the water, unless infeasible. If infeasible, documentation must be provided in the SWPPP. In addition, you must describe what BMP(s) will be used in its place.

- 4) Chemical treatment of dewatering activities for sediment removal must be conducted in accordance with the chemical manufacturer's specifications. Treatment chemicals must be appropriately selected for the anticipated soil particle size and characteristics of the stormwater (pH, turbidity, flow rate of stormwater flowing into the chemical treatment system, etc.). A description of the chemical treatment process must be included in the SWPPP. Permittees shall ensure the selection and management of chemicals minimize the potential for harmful effects in the discharge. The following information must be included in the SWPPP.
 - a. Material Safety Data Sheet/Safety Data Sheet (MSDS/SDS);
 - b. Proposed water additive discharge concentration;
 - c. Discharge frequency (i.e., number of hours per day and number of days per year);
 - d. Monitoring point for product discharge;
 - e. Type of removal treatment, if any, that the water additive receives prior to discharge;
 - f. Product function (e.g., coagulant, flocculant, etc.);
 - g. A 48-hour LC₅₀ or EC₅₀ for a North American freshwater planktonic crustacean (*Ceriodaphnia* sp., *Daphnia* sp., or *Simocephalus* sp.); and
 - h. Results for a toxicity test for one other North American freshwater aquatic species (other than a planktonic crustacean).
 - 5) Local authorities may require specific BMPs for discharges affecting their storm sewer system.
4. **Erosion and Sediment Controls.** Erosion and sediment controls and stabilization requirements must be implemented for each major phase of site activity (e.g., clearing, grading, building, and landscaping phases). A description of the erosion and sediment controls and site stabilization methods must be provided in accordance with Part II(C)(2) of this permit. Erosion and sediment controls, and site stabilization must conform to the requirements provided in Appendix 1. The description and implementation of controls shall address the following minimum components:
- a. The selection of erosion and sediment controls, and site stabilization shall consider the following:
 - 1) The expected amount, frequency, intensity, and duration of precipitation events. Permittees may state that selected erosion and sediment controls and site stabilization methods are industry standards;
 - 2) The nature of stormwater run-on and runoff from the site as well as changes during, and as a result of, construction activity. This includes changes to impervious surfaces, slopes, seasonal changes, and drainage features on-site;
 - 3) Channelized flow must be handled in order to minimize erosion at outlets and to minimize impacts to downstream receiving waters;
 - 4) Soil types (wind and water erodibility, and settling time); and
 - 5) Seasonal conditions.
 - b. Sediment basins, or an appropriate combination of equivalent sediment controls such as smaller sediment basins and/or sediment traps, silt fences, fiber logs, vegetative buffer strips, berms, etc., are required for all down slope boundaries of the disturbance area and for those side slope boundaries as may be appropriate for site conditions.

- c. Temporary or permanent erosion protection and stabilization (such as cover crop planting or mulching) must be initiated immediately, as described in Appendix 1(A), for all exposed soil areas where activities have been completed or temporarily ceased.
- d. All control measures must be properly selected, installed and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the permittee must replace or modify the control for site situations. Corrective actions must be made prior to the next anticipated rainfall event or within 24 hours of discovery (whichever comes first) or as soon as field conditions allow. Documentation must be provided in the maintenance records if field conditions do not allow access along with a plan of action for performing maintenance activities.

The permittee may deviate from the manufacturer's specifications and erosion and sediment control requirements in Appendix 1 if they provide justification for the deviation and document the rationale for the deviation in the SWPPP. Any deviation must provide equivalent erosion and sediment control.

- e. If sediment escapes from the site, off-site accumulations of sediment must be removed in a manner and frequency sufficient to minimize off-site impacts as outlined in Appendix 1(B). The SWPPP must be modified to prevent further sediment deposition off site.
 - f. Stormwater controls are expected to withstand and function properly during precipitation events of up to the 2-year, 24-hour storm event. Visible erosion and/or off-site sediment deposition from such storm events should be minimal. The 2-year, 24-hour rainfall event in North Dakota ranges from about 1.76 inches in the west to 2.50 inches in the east (NOAA Atlas 14, Volume 8, Version 2, Midwestern States 2013).
 - g. For projects that discharge stormwater which flows to a water body for which there is a TMDL allocation the SWPPP must be consistent with the assumptions, allocations, and requirements in the approved TMDL. If a TMDL specifies certain BMPs or controls to meet a WLA applicable to the project's discharges, the BMPs or controls must be incorporated into the SWPPP. Information about TMDL allocations may be found at the following website: deq.nd.gov/WQ
5. **Stormwater Management.** The SWPPP must identify permanent practices incorporated into the project to control pollutants in stormwater discharges occurring after construction operations have been completed.
- a. Identify stormwater ponds; flow reduction methods; infiltration of runoff on-site; sequential systems which combine several practices or other post-construction stormwater management features.
 - b. Identify velocity / energy dissipation devices placed at discharge locations and appropriate erosion protection for outfall channels and ditches.
 - c. Maintenance for on-site stormwater management features is the responsibility of the permittee until the NOT is submitted or the feature is accepted by the party responsible for long term maintenance.
 - d. The design, installation and use of stormwater management features must comply with applicable local, state or federal requirements.

6. **Maintenance.** The SWPPP shall describe preventative maintenance practices used to ensure the proper operation of erosion and sediment control devices and equipment used or stored on site. All erosion and sediment control measures and other protective measures identified in the SWPPP must be maintained in effective operating condition. The SWPPP must indicate, as appropriate, the maintenance or clean out interval for sediment controls. If site inspections, required in Part III of this permit, identify BMPs that are not operating effectively, maintenance shall be arranged and accomplished in accordance to Appendix 1 or as soon as practicable.
7. **Inspections.** The SWPPP must provide for site inspections as outlined in Part III. The permittee shall ensure that personnel conducting site inspections are familiar with permit conditions and the proper installation and operation of control measures. Inspectors must be knowledgeable in their role of the SWPPP, as outlined in Part II(C)(3)(e) of this permit. The erosion and sediment control measures and stabilized areas identified in the SWPPP shall be observed to ensure they are operating correctly and in serviceable condition. Inspections shall include areas used for storage of materials, permanent stormwater control measures, vehicle maintenance areas, and dewatering activities. These areas shall be inspected for evidence of, or the potential for, pollutants entering a drainage system. If necessary, the plan shall be revised based on the observations and deficiencies noted during the inspection.
8. **SWPPP Review and Revisions.**
 - a. The SWPPP shall be signed in accordance with the Signatory Requirements, Part IV(A)(6), and retained on-site for the duration of activity as outlined in Part III(B). The owner, or owner jointly with the operator (usually the general contractor), shall sign the SWPPP.
 - b. The permittee shall make the SWPPP available upon request to the department, EPA, or, in the case of discharges to a municipal storm sewer system, the operator of the municipal system.
 - c. The permittee shall amend the SWPPP whenever there is a change in design, construction, operation, maintenance, or BMPs. The SWPPP shall be amended if the plan is found to be ineffective in controlling pollutants present in stormwater. The SWPPP shall include a description of the amendment process.

D. Local Requirements

All stormwater discharges must comply with the requirements, policies, or guidelines of municipalities and other local agencies as applicable to the construction site. Any discharges to a storm sewer, ditch or other water course under the jurisdiction of a municipality must comply with any specific conditions or BMPs required by the municipality or agency.

E. Final Stabilization

The permittee(s) must ensure final stabilization of the site. Permittees should submit a NOT within 30 days after final stabilization has been achieved, or another owner/operator (permittee) has assumed control according to Part I(F) for all areas of the site that have not undergone final stabilization. Final stabilization can be achieved in one of the following ways.

1. All soil disturbing activities at the site have been completed and all soils must be stabilized by a uniform perennial vegetative cover with a density of 70 percent of the pre-existing cover over the entire pervious surface area, or other equivalent means necessary to prevent soil failure under erosive conditions and;

- a. All drainage ditches, constructed to drain water from the site after construction is complete, must be stabilized to preclude erosion;
 - b. All temporary erosion prevention and sediment control BMPs (such as silt fence) must be removed as part of the site final stabilization; and
 - c. The permittee(s) must remove all sediment from conveyances and temporary sedimentation basins that will be used as permanent water quality management basins. Sediment must be stabilized to prevent it from being washed into basins, conveyances or drainage ways discharging off-site or to surface waters. The cleanout of permanent basins must be sufficient to return the basin to design capacity.
2. For areas of the state where the average annual rainfall is less than 20 inches, all soil disturbing activities at the site have been completed and erosion control measures (e.g., degradable rolled erosion control product) and stabilization methods are selected, designed, and installed along with an appropriate seed base to provide erosion control for at least three years and achieve 70 percent of the pre-existing vegetative cover within three (3) years without active maintenance. Sites must meet the criteria outlined in items 1(a), (b), and (c) above.
 3. Disturbed areas on land used for agricultural purposes that are restored to their pre-construction agricultural use are not subject to these final stabilization criteria. If the construction activity removed standing crop, the area must be restored in accordance with the landowner.

Areas disturbed that were not previously used for agricultural activities, such as buffer strips immediately adjacent to waters of the state, and areas which are not being returned to their pre-disturbance use must meet the final stabilization criteria in (1) or (2) above.

4. For residential construction only, final stabilization may be achieved when soil is stabilized (see Appendix 1(A)(3)) and down gradient perimeter control for individual lots has been implemented and the residence has been transferred to the homeowner. Additionally, the permittee must distribute a "homeowner fact sheet" to the homeowner to inform the homeowner of the need for, and benefits of, final stabilization. The permittee also must demonstrate that the homeowner received the fact sheet.

III. SELF MONITORING AND REPORTING

A. Inspection and Maintenance Requirements

1. Inspections shall be performed by or under the direction of the permittee at least once every 14 calendar days and within 24 hours after any storm event of greater than 0.25 inches of rain per 24-hour period. Rainfall inspections do not take the place of the scheduled once every 14-calendar day inspection unless the rainfall inspection occurs on the same day as the once every 14-calendar day inspection. Inspections are only required during normal working hours. The permittee shall use a rain gauge on-site or utilize the nearest National Weather Service precipitation gauge station. Rain gauge locations or stations must be representative of the site.
 - a. "Within 24 hours after any storm event greater than 0.25 inches rain per 24-hour period" means that you are required to conduct an inspection within 24 hours once a storm event has produced 0.25 inches, even if the storm event is still continuing. If there is a storm event at your site that continues for multiple days, and each day of the storm produces 0.25 inches or more rain, you are required to conduct an inspection within 24 hours of the first day of the storm and within 24 hours after the end of the storm.

2. There may be times when a site inspection may not be practical at the specified time. Adverse climatic conditions, such as flooding, high winds, tornadoes, electrical storms, site access constraints, etc., may prohibit inspections. The permittee must include a description of why the inspection(s) could not be performed at the designated time in the next inspection record. If an inspection is delayed due to adverse weather conditions or rain events outside normal working hours, an inspection must be conducted during the next working day, or as conditions allow.
3. Some erosion and sediment control measures may require more frequent inspection based on location (e.g., sensitive areas or waters of the state) or as a result of recurring maintenance issues. Erosion or sediment control measures found in need of maintenance between inspections must be repaired or replaced with appropriate measures as soon as practicable. Erosion and sediment control measures which require more frequent inspection based on location or as a result of recurring maintenance issues must be identified in the SWPPP.
4. All inspections conducted during construction must be recorded. These records (or reports) must be retained in accordance with Part III(B). Records (or reports) of each inspection activity shall include:
 - a. Date of inspections;
 - b. Name of person(s) conducting inspections;
 - c. Findings of inspections, including recommendations and schedule for corrective actions;
 - d. Date and amount of all rainfall events greater than 1/4 inch (0.25 inches) in 24 hours;
 - e. Documentation that the SWPPP has been amended when changes are made to BMPs in response to inspections; and
 - f. Signature of person(s) conducting the inspection or other means used to verify an inspector (e.g., work order or preventative maintenance schedule completion).
5. Corrective actions (maintenance activities) performed during construction must be recorded and these records must be retained in accordance with Part III(B). Records for maintenance activity shall include:
 - a. Best Management Practice corrected;
 - b. Date of corrective action;
 - c. Name of person(s) performing corrective actions;
 - d. Corrective actions taken; and
 - e. Corrective actions/maintenance records shall be signed or use another means to verify corrective actions/maintenance were completed (e.g., work order or preventative maintenance schedule completion).
6. Completed areas that have been stabilized but do not meet the 70 percent perennial vegetative cover criteria for final stabilization may be inspected once per month. Inspections may be suspended for parts of the construction site that meet final stabilization requirements of Part II(E) of this permit. The SWPPP must update to identify any areas which meet this condition.

7. Inspections may be suspended where earthwork has been suspended due to frozen ground conditions. The required inspections and maintenance must resume as soon as runoff occurs or the ground begins to thaw at the site. The permittee must record freeze/thaw and runoff dates as part of the inspection records.
8. Dewatering activities shall be inspected daily. The inspection must include the dewatering site, areas where BMPs are being implemented and the discharge location. A record (or report) shall be maintained to document the inspections of the dewatering operation and actions taken to correct any problems that may be identified. Records shall contain at a minimum:
 - a. Date of inspections;
 - b. Name of person(s) conducting inspections;
 - c. Approximate volume of water discharged;
 - d. Findings of the inspection, including recommendations and schedule for corrective actions;
 - e. Corrective actions taken (including dates and party completing maintenance activities);
 - f. Documentation that the SWPPP has been amended when changes are made to the dewatering activity in response to inspections; and
 - g. Signature of person(s) conducting inspections and maintenance or other means used to verify an individual (e.g., work order or preventative maintenance schedule completion).

B. Records Location

A copy of the completed and signed NOI, coverage letter from the department, SWPPP, site inspection records, corrective actions/maintenance records, and this general permit shall be kept at the site of the construction activity in a field office, trailer, shed, vehicle that is on-site during normal working hours, or other reasonable on-site location. If the site does not have a reasonable on-site location, then the documents must be retained at a readily available alternative location; preferably with the individual responsible for overseeing the implementation of the SWPPP. Electronic copies of records are acceptable if the records can be accessed on-site. If the site is inactive, then the documents may be stored at a local office. Permittees should avoid using personal electronic devices for storing electronic records.

IV. STANDARD CONDITIONS

A. COMPLIANCE RESPONSIBILITIES BP 2019.05.29

1. Duty to Comply

The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application.

2. Proper Operation and Maintenance

The permittee shall at all times maintain in good working order and operate as efficiently as possible all treatment or control facilities or systems installed or used by the permittee to achieve compliance with the terms and conditions of this permit. If necessary to achieve compliance with the conditions of this permit, this shall include the operation and maintenance of backup or auxiliary systems.

3. Planned Changes

The department shall be given advance notice of any planned changes at the permitted facility or of an activity which may result in permit noncompliance. Any anticipated facility expansions, production increase, or process modifications which might result in new, different, or increased discharges of pollutants shall be reported to the department as soon as possible. Changes which may result in a facility being designated a "new source" as determined in 40 CFR 122.29(b) shall also be reported.

4. Duty to Provide Information

The permittee shall furnish to the department, within a reasonable time, any information which the department may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit, or to determine compliance with this permit. The permittee shall also furnish to the department, upon request, copies of records required to be kept by this permit. When a permittee becomes aware that it failed to submit any relevant facts or submitted incorrect information in a permit application or any report, it shall promptly submit such facts or information.

5. Records Retention

All records and information (including calibration and maintenance) required by this permit shall be kept by the permittee for at least three years from the date that permit coverage expires or is terminated or longer if requested by the department or EPA.

6. Signatory Requirements

All applications, reports, or information submitted to the department shall be signed and certified.

All permit applications shall be signed by a responsible corporate officer for a corporation; a general partner or the proprietor for a partnership or sole proprietorship; or a principal executive officer or ranking elected official for a municipality, State, Federal, or other public agency.

All reports required by the permit and other information requested by the department shall be signed by a person described above or by a duly authorized representative of that person. A person is a duly authorized representative only if:

- a. The authorization is made in writing by a person described above and included in the SWPPP; and
- b. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility, such as the position of plant manager, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters.

A copy of the written authorization must be submitted to the department upon request. If an authorization under 6. Signatory Requirements is no longer accurate for any reason, a new authorization satisfying the above requirements must be included in the SWPPP.

Any person signing a document under this section shall make the following certification:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

7. Twenty-four Hour Notice of Noncompliance Reporting

- a. The permittee shall report any noncompliance which may endanger health or the environment. Any information shall be provided orally as soon as possible, but no later than twenty-four (24) hours from the time the permittee first became aware of the circumstances. The oral report shall be made the department at 701.328.5210.
- b. A written submission shall also be provided within five days of the time that the permittee became aware of the circumstances. The written submission shall contain:
 - 1) A description of the noncompliance and its cause;
 - 2) The period of noncompliance, including exact dates and times;
 - 3) The estimated time noncompliance is expected to continue if it has not been corrected; and
 - 4) Steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance.

Reports shall be submitted to the department at the following address:

ND Department of Environmental Quality
Division of Water Quality
918 East Divide Ave
Bismarck ND 58501-1947

The department may waive the written report on a case by case basis if the oral report has been received within 24 hours by the department at 701.328.5210 as identified above.

8. Bypass of Treatment Facilities

- a. Prohibition of Bypass. Bypass is prohibited, and the department may take enforcement action against a permittee for bypass, unless:
 - 1) Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;
 - 2) There were no feasible alternatives to the bypass. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of preventive maintenance; and

The department may approve an anticipated bypass, after considering its adverse effects, if the department determines that it will meet the two (2) conditions listed above.

9. Upset Conditions

An upset constitutes an affirmative defense to an action brought for noncompliance with erosion and sediment or site stabilization methods if the requirements of the following paragraph are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review.

A permittee who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:

- a. An upset occurred and the permittee can identify its cause(s);
- b. The permitted facility was, at the time being, properly operated;

- c. The permittee submitted notice of the upset as required under 7. Twenty-four Hour Notice of Noncompliance Reporting and
- d. The permittee complied with any remedial measures required under 10. Duty to Mitigate.

In any enforcement proceeding, the permittee seeking to establish the occurrence of an upset has the burden of proof.

10. Duty to Mitigate

The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment. The permittee, at the department's request, shall provide accelerated or additional monitoring as necessary to determine the nature and impact of any discharge.

11. Removed Materials

Collected screenings, grit, solids, sludges, or other pollutants removed in the course of treatment shall be buried or disposed of in such a manner to prevent any pollutant from entering any waters of the state or creating a health hazard.

12. Duty to Reapply

Any request to have this permit renewed should be made fifteen days prior to its expiration date.

B. GENERAL PROVISIONS

1. Inspection and Entry

The permittee shall allow department and EPA representatives, at reasonable times and upon the presentation of credentials if requested, to enter the permittee's premises to inspect the construction activity and monitoring equipment, to sample any discharges, and to have access to and copy any records required to be kept by this permit.

2. Availability of Reports

Except for data determined to be confidential under 40 CFR Part 2, all reports prepared in accordance with the terms of this permit shall be available for public inspection at the offices of the department and EPA. As required by the Act, permit applications, permits, and effluent data shall not be considered confidential.

3. Transfers

This permit is not transferable except upon the filing of a Transfer/Modification request (Part I(F)) by the new party. The current permit holder should inform the new controller, operator, or owner of the existence of this permit and also notify the department of the possible change.

4. New Limitations or Prohibitions

The permittee shall comply with any effluent standards or prohibitions established under Section 306(a), Section 307(a), or Section 405 of the Act for any pollutant (toxic or conventional) present in the discharge or removed substances within the time identified in the regulations even if the permit has not yet been modified to incorporate the requirements.

5. Permit Actions

This permit may be modified, revoked and reissued, or terminated for cause. This includes the establishment of limitations or prohibitions based on changes to Water Quality Standards, the development and approval of waste load allocation plans, the development or revision to water quality management plans, or the establishment of prohibitions or more stringent limitations for toxic or conventional pollutants and/or sewage sludges. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any permit condition.

6. **Need to Halt or Reduce Activity Not a Defense**

It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.

7. **State Laws**

Nothing in this permit shall be construed to preclude the institution of legal action or relieve the permittee from any responsibilities, liabilities, or penalties established pursuant to any applicable state law or regulation preserved under Section 510 of the Act.

8. **Oil and Hazardous Substance Liability**

Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the permittee from any responsibilities, liabilities, or penalties to which the permittee is or may be subject under Section 311 of the Act.

9. **Property Rights**

The issuance of this permit does not convey any property rights of any sort, nor any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor any infringement of federal, state or local laws or regulations.

10. **Severability**

The provisions of this permit are severable, and if any provision of this permit or the application of any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances and the remainder of this permit shall not be affected thereby.

V. DEFINITIONS

“303(d) list” or **“section 303(d) list”** means a list of North Dakota’s water quality-limited waters needing total maximum daily loads or TMDLs developed to comply with section 303(d) of the Clean Water Act. A copy of the list is available on the state’s web site at: deq.nd.gov/WQ

“Act” means the Clean Water Act.

“Bankfull” means the channel is filled to the top of one or both of its banks.

“BMP” or **“best management practices”** means schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the pollution of waters of the state. BMPs also include treatment requirements, operating procedures and practices to control construction site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage.

“Bypass” means the intentional diversion of waste streams from any portion of a treatment facility.

“Common plan of development or sale” means a contiguous area where multiple separate and distinct land disturbing activities may be taking place at different times, on different schedules, but under one proposed plan. One plan is broadly defined to include design, permit application, advertisement or physical demarcation indicating that land-disturbing activities may occur.

“Construction activity” means construction activity as defined in 40 CFR part 122.26(b)(14)(x) and small construction activity as defined in 40 CFR part 122.26(b)(15). This includes a disturbance to the land that results in a change in topography, existing soil cover (both vegetative and non-vegetative), or the existing soil topography that may result in accelerated stormwater runoff, leading to soil erosion and movement of sediment into surface waters or drainage systems. Examples of construction activity may include clearing, grading, filling and excavating. Construction activity includes the disturbance of less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb one (1) acre or more. Construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the facility.

“Department” means the North Dakota Department of Environmental Quality, Division of Water Quality.

“Energy dissipation” means methods employed at pipe outlets to prevent erosion. Examples include, but are not limited to: concrete aprons, riprap, splash pads, and gabions that are designed to prevent erosion.

“Indian country” means (1) All land within the limits of any Indian reservation under the jurisdiction of the United States Government, notwithstanding the issuance of any patent, and including rights-of-way running through the reservations; (2) All dependent Indian communities within the borders of the United States whether within the originally or subsequently acquired territory thereof, and whether within or without the limits of a state; and (3) All Indian allotments, the Indian titles to which have not been extinguished, including rights-of-way running through the same.

“Infeasible” means not technologically possible or not economically practicable and achievable in light of best industry practices.

“Immediately” means as soon as practicable, but no later than the end of the next work day, following the day when the earth-disturbing activities have temporarily or permanently ceased.

“Large construction activity” means land disturbance of equal to or greater than five (5) acres. Large construction activity also includes the disturbance of less than one acre of total land area that is part of a larger common plan of development or sale, if the larger common plan will ultimately disturb equal to or greater than five acres.

“Normal wetted perimeter” means the area of a conveyance, such as a ditch, channel, or pipe that is in contact with water during flow events that are expected to occur once every year.

“Non-stormwater discharges” means discharges other than stormwater. The term includes both process and non-process sources. Process wastewater sources that require a separate NDPDES permit include, but are not limited to industrial processes, domestic facilities and cooling water. Non-stormwater sources that may be addressed in this permit include, but are not limited to: fire-fighting, fire hydrant flushing, potable water line flushing, equipment wash down without detergents or hazardous cleaning products, uncontaminated foundation drains, springs, surface water, lawn watering, chemical treatment of stormwater and air conditioning condensate.

“Operator” means the person (usually the general contractor) designated by the owner who has day to day operational control and/or the ability to modify project plans and specifications related to the SWPPP. The person must be knowledgeable in those areas of the permit for which the operator is responsible and must perform those responsibilities in a workmanlike manner.

“Owner” means the person or party possessing the title of the land on which the construction activities will occur; or if the construction activity is for a lease holder, the party or individual identified as the lease holder; or the contracting government agency responsible for the construction activity.

“Permanently ceased” means clearing and excavation within any area of your construction site that will not include permanent structures has been completed.

“Permanent Cover” means final stabilization. Examples include grass, gravel, asphalt, and concrete.

“Severe property damage” means substantial physical damage to property, damage to best management practices which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in construction.

“Significant materials” includes, but is not limited to: raw materials; fuels; materials such as solvents, detergents, and plastic pellets; finished materials such as metallic products; hazardous substances designated under Section 101(14) of CERCLA; any chemical the facility is required to report pursuant to Section 313 of Title III of SARA; fertilizers; pesticides; and waste products such as ashes, slag and sludge that have the potential to be released with stormwater discharges.

“Significant spills” includes, but is not limited to: releases of oil or hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (see 40 CFR 110.10 and CFR 117.21) or Section 102 of CERCLA (see 40 CFR 302.4).

“Small construction activity” means land disturbance of equal to or greater than one acre and less than five acres. Small construction activity also includes the disturbance of less than one acre of total land area that is part of a larger common plan of development or sale, if the larger common plan will ultimately disturb equal to or greater than one and less than five acres.

“Stabilized” means the exposed ground surface has been covered by appropriate materials such as mulch, staked sod, riprap, erosion control blanket, or other material that prevents erosion from occurring. Grass seeding alone is not stabilization. Snow cover and frozen ground conditions are not considered stabilized.

“Steep Slopes” means slopes which are 3:1 (Horizontal:Vertical) or greater in grade.

“Stormwater” means stormwater runoff, snow melt runoff, and surface runoff and drainage.

“Stormwater associated with industrial activity” means stormwater runoff, snow melt runoff, or surface runoff and drainage from industrial activities as defined in 40 CFR 122.26(b)(14).

“Stormwater associated with small construction activity” means the discharge of stormwater from:

(i) Construction activities including clearing, grading, and excavating that result in land disturbance of equal to or greater than one acre and less than five acres. Small construction activity also includes the disturbance of less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater than one and less than five acres. Small construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the facility.

(ii) Any other construction activity designated by EPA or the Department, based on the potential for contribution to a violation of a water quality standard or for significant contribution of pollutants to waters of the state.

“Temporarily ceased” means clearing, grading, and excavation within any area of the site that will not include permanent structures, will not resume (i.e., the land will be idle) for a period of 14 or more calendar days, but such activities will resume in the future.

“Temporary erosion protection” means methods employed to prevent erosion. Examples of temporary cover include; mulch, straw, erosion control blanket, wood chips, tackifiers, and erosion netting.

“Upset” means an exceptional incident in which there is unintentional and temporary noncompliance with permit requirements because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed erosion and sediment controls or site stabilization methods, inadequate erosion and sediment controls or site stabilization methods, lack of preventive maintenance, or careless or improper operation.

“Waters of the state” means any and all surface waters that are contained in or flow in or through the state of North Dakota as defined in NDCC 61-28-02. This definition includes all water courses, even if they are usually dry.

Appendix 1 – Erosion and Sediment Control Requirements

Requirements for designing, implementing and maintaining erosion and sediment controls.

A. Erosion and Sediment Control Practices

1. Sites using temporary (or permanent) sediment basins must meet the following requirements:
 - a. Sediment basins shall be designed for a calculated volume of runoff from a 2-year, 24-hour storm per acre drained to the basin and provides not less than 1,800 cubic feet of sediment storage below the invert of the outlet pipe from each acre drained to the basin; or
 - b. Basins shall be sized to provide 3,600 cubic feet of sediment storage below the invert of the outlet pipe per acre drained to the basin if calculations are not performed.
 - c. Basin outlets must be designed to avoid short-circuiting and the discharge of floating debris. Basins must be designed with the ability to allow complete basin drawdown for maintenance activities. Basins must release the storage volume in at least 24 hours. Outlet structures must be designed to withdraw water from the surface, unless not practicable. If not practicable, rationale must be provided in the SWPPP. The basin must have a stabilized emergency overflow to prevent failure of pond integrity. Energy dissipation must be provided for the basin outlet.
2. Erosion, sediment, and stabilization practices shall be provided. Erosion, sediment, and stabilization practices include such things as: silt fences, fiber logs, stabilized earth berms, vegetative buffer strips, erosion control blankets, mulch, hydro-seeding combined with mulch or tackifiers, etc.
3. All exposed soil areas must be stabilized (see definitions). Stabilization must be initiated immediately where activities have been permanently or temporarily ceased on any portion of the site and will not resume for a period exceeding fourteen (14) calendar days. Stabilization must be completed as soon as practicable, but no later than fourteen (14) calendar days after the initiation of soil stabilization. Temporary stockpiles without significant silt, clay or organic components (e.g., clean aggregate stockpiles, demolition concrete stockpiles, sand stockpiles) are exempt from this requirement.
 - a. For slopes with a grade of 3:1 or greater, stabilization must be initiated immediately once activities have been completed or temporarily ceased. Stabilization must be completed as soon as practicable, but no later than seven (7) calendar days after the initiation of soil stabilization.
4. Temporary soil stockpiles must have effective sediment controls, and cannot be placed in surface waters, including stormwater conveyances such as curb and gutter systems, or conduits and ditches.
5. The normal wetted perimeter of any temporary or permanent drainage ditch that drains water from a construction site, or diverts water around a site, must be stabilized at least 200 linear feet from the property edge, or from the point of discharge to any surface water. Stabilization shall be completed prior to connection with a surface water. Any remaining portion of the temporary or permanent drainage ditch must be stabilized within fourteen (14) calendar days for portions which construction activities have temporarily or permanently ceased.
6. If stabilization requirements cannot be met due to circumstances beyond the control of the permittee, the permittee may comply with following:
 - a. If vegetative stabilization is to be used, immediately initiate, and within 14 calendars days complete, the installation of temporary non-vegetated stabilization; or
 - b. Complete all methods of initiating stabilization as soon as conditions or circumstances allow.

If any conditions in parts (a) or (b) above are encountered, the permittee must document in the SWPPP the circumstances which prevented the stabilization requirements from being met and provide a schedule in the SWPPP which will be followed in order to meet the stabilization requirements.

Permittees are responsible for implementing winter stabilization methods during frozen ground conditions if the site was not stabilized prior to the ground freezing.

7. Stream diversions, or any temporary or permanent drainage ditch or trench which will have continuous flow, shall be stabilized with appropriate controls prior to connection with any surface water. The entire area (channel and bank) of the stream diversion or temporary or permanent drainage ditch, or trench, must be appropriately stabilized to bankfull height.
8. While working in or around surface waters, sediment and erosion controls must be used above the anticipated level of the surface water. Floating silt curtain does not satisfy the down slope and side slope boundary requirements in Part II(C)(4)(b) of this permit, unless the construction activity is on or below the elevation of the surface water. Floating silt curtain must be placed as close to shore as possible. Sediment controls must be installed where exposed soils drain to the surface water immediately after construction activity along the waterline has been completed.
9. Pipe and culvert outlets must be provided with energy dissipation prior to connection with a surface water.
10. Splash pads and/or downspout extensions must be provided for roof drains to prevent erosion from roof runoff.
11. All storm drain inlets in the immediate vicinity of the construction site must be protected by appropriate BMPs during construction until all disturbed areas and stockpiles with the potential to discharge to the inlet have been stabilized. This includes storm drain inlets which may be affected by sediment tracked onto paved surfaces by vehicles or equipment.
12. Inlet protection devices are a last line of control – erosion and sediment control practices must be used on site. Inlet protection devices must conform to local ordinances or regulations. In general, inlet protection devices need to provide for adequate drainage to prevent excessive roadway flooding. Inlet protection may be removed for a particular inlet if a specific concern (i.e., street flooding/freezing, snow removal) has been identified and documented in the SWPPP. In this situation, additional erosion and sediment control practices, or stabilization methods must be used to supplement the loss of the inlet protection device to prevent sediment from entering the storm sewer system.
13. Vegetated buffers must have a minimum width of 1 foot for every 5 feet of disturbed area that drains to the buffer. The width of the buffer shall have a slope of 5 percent or less and the area draining to the buffer shall have a slope of 6 percent or less. Concentrated flows should be minimized throughout the buffer.

Buffers shall consist of dense grassy vegetation, 3 to 12 inches tall with uniform coverage over 90 percent of the buffer. Woody vegetation shall not be counted for the 90 percent coverage. No more than 10 percent of the overall buffer may be comprised of woody vegetation.
14. A 50-foot natural buffer or equivalent erosion and sediment controls must be provided when a project is within 50 feet of a surface water and stormwater flows to the surface water. If equivalent erosion and sediment controls are used, rationale for using equivalent controls must be provided in the SWPPP.

If working within 100 feet of a surface water listed as impaired for sediment, suspended solids or turbidity, a 100-foot natural buffer or equivalent sediment and erosion controls must be provided. If equivalent erosion and sediment controls are to be used, rationale for using equivalent controls must be provided in the SWPPP.

15. Discharges from the chemical treatment of stormwater must not cause a violation of the standards of quality for waters of the state (NDAC 33.1-16-02.1). The discharge must meet the dewatering or basin draining requirements provided in Part II(C)(3)(g) of this permit.
16. Minimize the duration of exposed soils on steep slopes.

B. Maintenance Requirements for Erosion and Sediment Controls

1. All erosion prevention and sediment control BMPs must be inspected to ensure integrity and effectiveness. All nonfunctional BMPs must be repaired, maintained, or replaced with functional BMPs. Corrective actions must be made prior to the next anticipated rainfall event or within 24 hours of discovery (whichever comes first), or as soon as field conditions allow access. Documentation must be provided in the maintenance records if field conditions do not allow access along with a plan of action for performing maintenance activities.

Permittees must investigate and comply with the following inspection and maintenance requirements:

- a. All control devices similar to, and including, silt fence or fiber rolls must be repaired, replaced, maintained or supplemented when they become nonfunctional (torn from posts, visible tears, etc.). Collected sediment must be removed as it approaches 1/2 of the above ground capacity of the control device.
 - b. Fiber rolls must be replaced when 1/2 of the original above ground height of the device when it was installed has been lost as a result of flattening or other damage.
 - c. Sedimentation basins must be drained and the sediment removed when the depth of sediment collected in the basin reaches 1/2 the storage volume. Drainage and removal must be completed within 72 hours of discovery, or as soon as field conditions allow access. Documentation must be provided in the maintenance records if field conditions do not allow access along with a plan of action for performing maintenance activities.
 - d. Maintenance and cleaning of inlet protection devices must be performed when sediment accumulates, the filter becomes clogged, and/or performance is compromised.
2. Surface waters, including drainage ditches and conveyance systems, must be inspected for evidence of sediment deposited by erosion. Permittees must remove all deltas and sediment deposits in surface waters, drainage ways, catch basins, and other drainage systems. Areas where sediment removal results in exposed soil must be stabilized. Removal and stabilization must take place immediately, but no more than, seven (7) calendar days after the discovery unless precluded by legal, regulatory or physical access constraints. Permittees shall use all reasonable efforts to obtain access. If precluded, removal and stabilization shall take place immediately, but no more than, seven (7) calendar days after obtaining access. Permittees are responsible for contacting all local, regional, state, and federal authorities, and receiving any applicable permits prior to conducting any work.
 3. Vehicle tracking of sediment from the site must be minimized by BMPs. This may include having a designated egress with aggregate surfacing from the site or by designating off-site parking. Permittees are responsible for (or making the arrangements for) street sweeping and/or scraping if BMPs are not adequate to prevent sediment from being tracked onto the street from the site.

Construction site egress locations must be inspected for evidence of sediment being tracked offsite by vehicles or equipment onto paved surfaces. Accumulations of tracked and deposited sediment must be removed from all off-site paved surfaces by the end of the work day, shift or if applicable, within a shorter time specified by local authorities or the department.

4. If sediment escapes the construction site, off-site accumulations of sediment must be removed in a manner and at a frequency sufficient to minimize off-site impacts (e.g., fugitive sediment in streets could be washed into storm sewers by the next rain event and/or pose a safety hazard to users of public streets). BMPs shall be used to minimize further impacts of off-site accumulations of sediment until the off-site accumulations are removed. Impervious surface wash water may not be directed into any surface water or storm drain inlet unless appropriate pollution prevention measures have been implemented.
5. Vegetative buffers must be inspected for proper distribution of flows, sediment accumulation and signs of rill formation. If a buffer becomes silt covered, contains rills, or is otherwise rendered ineffective, other control measures shall be implemented. Eroded areas shall be repaired and stabilized within 24 hours of discovery, or as soon as conditions allow access. Documentation must be provided in the maintenance records if field conditions do not allow access along with a plan of action for performing maintenance activities.

C. Operational Controls

1. Properly handle construction debris and waste materials.
 - a. Debris and waste must be handled appropriately until disposal. Litter and debris shall be collected and stored to reduce the potential for wind and water to carry the materials off-site or leachate discharging from a site. Collected material shall be taken to the appropriate facility for disposal or recycling.
 - b. Liquid or soluble materials including oil, fuel, paint, and any other hazardous substances must be properly stored, to prevent spills, leaks or other discharges. Restricted access to storage areas must be provided to prevent vandalism. Storage and disposal of liquid or soluble material must be in compliance with applicable regulations.
2. Wash water containments must be cleaned out (solids and liquid) before 80 percent of storage capacity is attained.
3. BMPs used in surface waters must be cleaned immediately upon removal from surface waters to prevent the transfer of aquatic nuisance species.
4. Fueling operations must be managed to minimize spills or leaks. Collected spill or leak material must be disposed in compliance with applicable regulations.



**APPLICATION (NOTICE OF INTENT) TO OBTAIN
 COVERAGE UNDER NDPDES GENERAL PERMIT
 FOR STORMWATER DISCHARGES ASSOCIATED
 WITH CONSTRUCTION ACTIVITY (NDR10-0000)**
 NORTH DAKOTA DEPARTMENT OF ENVIRONMENTAL QUALITY
 DIVISION OF WATER QUALITY
 SFN 19145 (06/2019)

FOR DEPT. USE ONLY

Date Received
Application Number
NOI ID: SW_NOI_20200326171518087

New Project

GENERAL INFORMATION

1. Name of Owner of Construction Project OE2 North LLC	2. Contact First Name Grant	3. Contact Last Name Burchell	4. Contact Telephone Number 720.638.7312
5. Contact E-mail Address gburchell@outriggerenergy.com	6. Mailing Address 1200 Seventeenth Street, Suite 900		
7. City Denver	8. State/Province CO	9. Zip Code 80202	
10. Name of Operator Working at Site OE2 North LLC	11. Contact First Name Grant	12. Contact Last Name Burchell	13. Contact Telephone Number 720.638.7312
14. Contact E-mail Address gburchell@outriggerenergy.com	15. Mailing Address 1200 Seventeenth Street, Suite 900		
16. City Denver	17. State/Province CO	18. Zip Code 80202	

PROJECT INFORMATION

19. Name of Construction Project Bill Sanderson Gas Plant			
20. Brief Description of Construction Activity Construction of a 250 MMscfd natural gas processing facility			
21. Project Start Date 04/07/2020	22. Estimated Completion Date 12/31/2020	23. Estimated Total Acres of Site 39	24. Estimated Acres of Disturbance 37
Project Location	25. Physical Address 49th Street NW		26. City Williston, ND 58801
	27. Township 154	28. Range 104	29. Section 27
	30. Quarter Section (ABCD Format) SWSE		31. County Williams
	32. Latitude (Decimal Degrees) 48.12789		33. Longitude (Decimal Degrees) -104.04156
Receiving Waters	34. Name of Municipal Storm Sewer System or Description of Receiving Water Unnamed intermittent tributary to Little Muddy Creek		

35. A SWPPP must be prepared and available for review at the time of application. You are not required to submit the SWPPP with the application unless otherwise notified by the department. The SWPPP must be completed prior to the start of construction (or the applicable construction phase). Please refer to Part I(D)(2)(c) of the permit.

<p>Submit by E-mail</p> <p>AFTER SUBMITTING BY E-MAIL PRINT AND SEND COMPLETED APPLICATION WITH "WET" INK SIGNATURE TO:</p> <p>North Dakota Dept. of Env. Quality Division of Water Quality, 4th Floor 918 East Divide Avenue Bismarck, ND 58501-1947</p> <p>Telephone: (701) 328-5210</p> <p>Print Form</p>	I certify under penalty of law that I have personally examined and am familiar with the information submitted herein. Based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.	
	36. Printed Name of Owner(s) Grant Burchell	37. Title Senior VP, Engineering & Operations
	38. Signature of Owner(s) 	39. Date 3/27/20
	40. Printed Name of Operator(s) Grant Burchell	41. Title Senior VP, Engineering & Operations
	42. Signature of Operator(s) 	43. Date 3/27/20

May 14, 2020

North Dakota Pollutant Discharge Elimination System (NDPDES)
General Permit for Stormwater Discharges from Construction Activity
NOTICE OF COVERAGE

Permittee(s)

Owner/Operator Grant Burchell
Contact: OE2 North LLC
1200 Seventeenth Street, Suite 900
Denver, CO 80202

Coverage under the 2020 reissued construction general permit (NDR11-0000) is identified as follows:

Permit ID: **NDR110679** Site Name: **Bill Sanderson Gas Plant**

Please remember to update the Stormwater Pollution Prevention (SWPP) plan as appropriate for site conditions. The best management practices (BMPs) and temporary structures must be inspected, maintained and adjusted until the site is stabilized following construction activities. Once the site is stabilized as outlined in the general permit, you may end permit coverage by filing a termination notice. Cities or counties may impose additional requirements and/or specific BMPs for construction affecting their storm drainage system. Please check with the local officials to be sure all local stormwater management considerations are addressed.

Additional Information

The permit will expire on March 31, 2025. The permit conditions, forms and related information may be found on our web site at:

https://deq.nd.gov/WQ/2_NDPDES_Permits/7_Stormwater/StW.aspx

Should you have any questions on the permit, please contact a stormwater staff person listed below.

Dallas Grossman 701.328.5242 dgrossma@nd.gov	Sam DeVries 701.328.5215 sgDeVries@nd.gov	Allison Lightfoot 701.328.5285 alightfoot@nd.gov	Emily Joynt 701.328.5239 ejoynt@nd.gov
-----------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------

**AIR POLLUTION CONTROL
 PERMIT TO CONSTRUCT**

Pursuant to Chapter 23.1-06 of the North Dakota Century Code, and the Air Pollution Control Rules of the State of North Dakota (Article 33.1-15 of the North Dakota Administrative Code), and in reliance on statements and representations heretofore made by the owner designated below, a Permit to Construct is hereby issued authorizing such owner to construct and initially operate the source unit(s) at the location designated below. This Permit to Construct is subject to all applicable rules and orders now or hereafter in effect of the North Dakota Department of Environmental Quality (Department) and to any conditions specified below:

I. General Information:

- A. **Permit to Construct Number:** PTC20021

- B. **Source:**
 - 1. **Name:** OE2 North LLC
 - 2. **Location:** Sanderson Gas Plant
 Lat. 48.127456, Long. -104.041311
 SW ¼ Sec., 27, T154N, R104W
 Williams County, North Dakota
 - 3. **Source Type:** Natural Gas Processing
 - 4. **Equipment at the Facility:**

Emission Unit Description	Emission Unit (EU)	Emission Point (EP)	Air Pollution Control Equipment
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engine rated at 2,675 bhp (2020)(JJJ)	ENG-1	ENG-1	Catalytic Oxidizer
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engine rated at 2,675 bhp (2020)(JJJ)	ENG-2	ENG-2	Catalytic Oxidizer
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engine rated at 2,675 bhp (2020)(JJJ)	ENG-3	ENG-3	Catalytic Oxidizer
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engine rated at 2,675 bhp (2020)(JJJ)	ENG-4	ENG-4	Catalytic Oxidizer

Emission Unit Description	Emission Unit (EU)	Emission Point (EP)	Air Pollution Control Equipment
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engine rated at 2,675 bhp (2020)(JJJJ)	ENG-5	ENG-5	Catalytic Oxidizer
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engine rated at 2,675 bhp (2020)(JJJJ)	ENG-6	ENG6	Catalytic Oxidizer
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engine rated at 2,675 bhp (2020)(JJJJ)	ENG-7	ENG-7	Catalytic Oxidizer
Heatec natural gas-fired heat medium oil (HMO) heater rated at 34 x 10 ⁶ Btu/hr (2020) (Dc)	HTR-1	HTR-1	None
Heatec natural gas-fired regenerator heater rated at 29 x 10 ⁶ Btu/hr	HTR-2	HTR-2	None
Heatec natural gas-fired heat medium oil (HMO) heater rated at 21 x 10 ⁶ Btu/hr (2020) (Dc)	HTR-3	HTR-3	None
Two 400-barrel slop tanks	TNK-1 and TNK-2	TNK-1 and TNK-2	COMB and Submerged Fill Pipe (SFP)
Tank Combustor	COMB	COMB	None
Slop tank loadout	LOAD	LOAD	None
Emergency Flare	FLR	FLR	None
Fugitive Emissions ^A	FUG	FUG	Leak Detection and Repair (LDAR)

^A Minor emission source (no specific emission limit).

C. Owner/Operator (Permit Applicant):

1. Name: OE2 North LLC
2. Address: 1200 - 17th Street, Ste 900
Denver, CO 80202
3. Application Date: February 7, 2020

II. **Conditions:** This Permit to Construct allows the construction and initial operation of the above-mentioned new or modified equipment at the source. The source may be operated under this Permit to Construct until a Permit to Operate is issued unless this permit is suspended or revoked. The source is subject to all applicable rules, regulations, and orders

now or hereafter in effect of the North Dakota Department of Environmental Quality and to the conditions specified below.

- A. **Emission Limits:** Emission limits from the operation of the source unit(s) identified in Item I.B of this Permit to Construct (hereafter referred to as "permit") are as follows. Source units not listed are subject to the applicable emission limits specified in the North Dakota Air Pollution Control Rules.

Emission Unit Description	EU	EP	Pollutant / Parameter	Emission Limit
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engines	ENG-1 through ENG-7	ENG-1 through ENG-7	NO _x	1.77 lb/hr and 1.0 g/hp-hr or 82 ppmvd ^{A, D}
			CO	1.47 lb/hr and 2.0 g/hp-hr or 270 ppmvd ^{A, D}
			VOC	0.83 lb/hr and 0.7 g/hp-hr or 60 ppmvd ^{A, D}
			Opacity	20% ^{B, D}
Natural gas-fired HMO heater rated at 34 x 10 ⁶ Btu/hr	HTR-1	HTR-1	Opacity	20% ^B
Natural gas-fired regenerator heater rated at 29 x 10 ⁶ Btu/hr	HTR-2	HTR-2	Opacity	20% ^B
Natural gas-fired HMO heater rated at 21 x 10 ⁶ Btu/hr	HTR-3	HTR-3	Opacity	20% ^B
Tank Combustor	COMB	COMB	Opacity	20% ^B
Emergency Flare	FLR	FLR	Opacity	20% ^C

^A The emission limits in g/hp-hr and ppmvd (at 15% O₂) are from 40 CFR 60, Subpart JJJJ.

^B 40% permissible for not more than six minutes per hour.

^C 60% permissible for not more than six minutes per hour.

^D Applies to each unit.

- B. **Fuel Restriction:**

The compressor engines, heaters, combustor, and flare (EUs ENG-1 through ENG-7, HTR-1 through HTR-3, COMB, and FLR) are restricted to combusting only natural gas containing no more than 2 grains of sulfur per 100 standard cubic feet.

C. **Emissions Testing:**

1. Initial Testing: Within 180 days after initial startup, the permittee shall conduct emissions tests at the emission units listed below using an independent testing firm, to determine the compliance status of the facility with respect to the emission limits specified in Condition II.A. Emissions testing shall be conducted for the pollutant(s) listed below in accordance with EPA Reference Methods listed in 40 CFR 60, Appendix A. Test methods other than those listed below may be used upon approval by the Department.

Emission Unit Description	EP	Pollutant/ Parameter
Caterpillar G3608 A4 (4SLB) natural gas-fired compressor engines	ENG-1 through ENG-7	NO _x CO VOC

A signed copy of the test results shall be furnished to the Department within 60 days of the test date. The basis for this condition is NDAC 33.1-15-01-12 which is hereby incorporated into this permit by reference. To facilitate preparing for and conducting such tests, and to facilitate reporting the test results to the Department, the owner/operator shall follow the procedures and formats in the Department's Emission Testing Guideline.

2. Notification: The permittee shall notify the Department using the form in the Emission Testing Guideline, or its equivalent, at least 30 calendar days in advance of any tests of emissions of air contaminants required by the Department. If the permittee is unable to conduct the performance test on the scheduled date, the permittee shall notify the Department at least five days prior to the scheduled test date and coordinate a new test date with the Department.
3. Sampling Ports/Access: Sampling ports shall be provided downstream of all emission control devices and in a flue, conduit, duct, stack or chimney arranged to conduct emissions to the ambient air.

The ports shall be located to allow for reliable sampling and shall be adequate for test methods applicable to the facility. Safe sampling platforms and safe access to the platforms shall be provided. Plans and specifications showing the size and location of the ports, platform and utilities shall be submitted to the Department for review and approval.

4. Other Testing:

- a) The Department may require the permittee to have tests conducted to determine the emission of air contaminants from any source,

whenever the Department has reason to believe that an emission of a contaminant not addressed by the permit applicant is occurring, or the emission of a contaminant in excess of that allowed by this permit is occurring. The Department may specify testing methods to be used in accordance with good professional practice. The Department may observe the testing. All tests shall be conducted by reputable, qualified personnel. A signed copy of the test results shall be furnished to the Department within 60 days of the test date.

All tests shall be conducted, and the results calculated in accordance with test procedures approved by the Department. All tests shall be conducted under the direction of persons qualified by training or experience in the field of air pollution control as approved by the Department.

- b) The Department may conduct tests of emissions of air contaminants from any source. Upon request of the Department, the permittee shall provide necessary holes in stacks or ducts and such other safe and proper sampling and testing facilities, exclusive of instruments and sensing devices, as may be necessary for proper determination of the emission of air contaminants.

D. **New Source Performance Standards (NSPS):** The owner/operator shall comply with all applicable requirements of the following NSPS subparts as referenced in Chapter 33.1-15-12 of the North Dakota Air Pollution Control Rules and 40 CFR 60:

1. **40 CFR 60, Subpart JJJJ:** The owner/operator shall comply with all applicable requirements of 40 CFR 60, Subpart JJJJ – Standards of Performance for Stationary Spark Ignition Internal Combustion Engines (EUs ENG-1 through ENG-7).
2. **40 CFR 60, Subpart Dc:** The owner/operator shall comply with all applicable requirements of 40 CFR 60, Subpart Dc – Standards of Performance for Small Industrial-Commercial-Institutional Steam Generating Units (EUs HTR-1 and HTR-3).
3. **40 CFR 60, Subpart OOOOa:** The owner/operator may be subject to the requirements of Subpart OOOOa –Standards of Performance for Crude Oil and Natural Gas Facilities for which Construction, Modification or Reconstruction Commenced After September 18, 2015. The Department has not adopted this subpart. All required documentation must be submitted to EPA Region 8 at the following address:

U.S. EPA Region 8
1595 Wynkoop Street
Mail Code 8ENF – AT
Denver, CO 80202-1129

- E. **Maximum Achievable Control Technology Standards (MACT):** The permittee shall comply with all applicable requirements of the following MACT subparts as referenced in Chapter 33.1-15-22 of the North Dakota Air Pollution Control Rules and 40 CFR 63.
1. 40 CFR 63, Subpart ZZZZ - National Emissions Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines (EU 1). The North Dakota Department of Environmental Quality has not adopted the area source provisions of this subpart. Please send all documentation to EPA at the address above.
- F. **Requirements for Control of VOC Emissions:**
1. When it is necessary to operate the flares during emergency, malfunction or maintenance, all precautions shall be taken to minimize emissions and maintain compliance with the applicable ambient air quality standards as outlined in NDAC 33.1-15-02 and the opacity standard of 20% not to exceed 60% for more than one six-minute period per hour.
 2. The flares/combustors (EUs FLR and COMB) must be equipped and operated with an automatic ignitor or a continuous burning pilot which must be maintained in good working order as outlined in NDAC 33.1-15-07-02.
 3. The presence of a flame for the flare and combustor shall be monitored using a thermocouple or any other equivalent device approved by the Department.
- G. **Stack Heights:** The stack height of each engine shall be at least 1.5 times the nearby building height. A nearby building is any building located a distance of less than five times the building height from the stack.
- H. **Like-Kind Engine Replacement:** This permit allows the permittee to replace an existing compressor engine with a like-kind engine. Replacement is subject to the following conditions:
1. The Department must be notified within 10 days after change-out of the engine.
 2. The replacement engine shall operate in the same manner, provide no increase in throughput and have equal or less emissions than the engine it is replacing.
 3. The date of manufacture of the replacement engine must be included in the notification. The facility must comply with any applicable federal

standards (e.g. NSPS, MACT) triggered by the replacement.

4. The replacement engine is subject to the same state emission limits as the existing engine in addition to any NSPS or MACT emission limit that is applicable. Testing shall be conducted to confirm compliance with the emission limits within 180 days after start-up of the engine.
- I. **Construction:** Construction of the above described facility shall be in accordance with information provided in the permit application as well as any plans, specifications and supporting data submitted to the Department. The Department shall be notified ten days in advance of any significant deviations from the specifications furnished. The issuance of this Permit to Construct may be suspended or revoked if the Department determines that a significant deviation from the plans and specifications furnished has been or is to be made.

Any violation of a condition issued as part of this permit to construct as well as any construction which proceeds in variance with any information submitted in the application, is regarded as a violation of construction authority and is subject to enforcement action.
- J. **Startup Notice:** A notification of the actual date of initial startup shall be submitted to the Department within 15 days after the date of initial startup.
- K. **Storage Tanks:** All stationary volatile organic compounds storage tanks shall be equipped with a submerged fill pipe in accordance with NDAC 33.1-15-07-01.3.
- L. **Organic Compounds Emissions:** The permittee shall comply with all applicable requirements of NDAC 33.1-15-07 – Control of Organic Compounds Emissions.
- M. **Permit Invalidation:** This permit shall become invalid if construction is not commenced within eighteen months after issuance of such permit, if construction is discontinued for a period of eighteen months or more; or if construction is not completed within a reasonable time.
- N. **Fugitive Emissions:** The release of fugitive emissions shall comply with the applicable requirements in NDAC 33.1-15-17.
- O. **Annual Emission Inventory/Annual Production Reports:** The owner/operator shall submit an annual emission inventory report and/or an annual production report upon Department request, on forms supplied or approved by the Department.
- P. **Source Operations:** Operations at the installation shall be in accordance with statements, representations, procedures and supporting data contained in the initial application, and any supplemental information or application(s) submitted thereafter. Any operations not listed in this permit are subject to all applicable North Dakota Air Pollution Control Rules.

- Q. **Alterations, Modifications or Changes:** Any alteration, repairing, expansion, or change in the method of operation of the source which results in the emission of an additional type or greater amount of air contaminants or which results in an increase in the ambient concentration of any air contaminant, must be reviewed and approved by the Department prior to the start of such alteration, repairing, expansion or change in the method of operation.
- R. **Air Pollution from Internal Combustion Engines:** The permittee shall comply with all applicable requirements of NDAC 33.1-15-08-01 – Internal Combustion Engine Emissions Restricted.
- S. **Recordkeeping:** The owner/operator shall maintain any compliance monitoring records required by this permit or applicable requirements. The owner/operator shall retain records of all required monitoring data and support information for a period of at least five years from the date of the monitoring sample, measurement, report or application. Support information may include all calibration and maintenance records and all original strip-chart recordings/computer printouts for continuous monitoring instrumentation, and copies of all reports required by the permit.
- T. **Nuisance or Danger:** This permit shall in no way authorize the maintenance of a nuisance or a danger to public health or safety.
- U. **Malfunction Notification:** The owner/operator shall notify the Department of any malfunction which can be expected to last longer than twenty-four hours and can cause the emission of air contaminants in violation of applicable rules and regulations.
- V. **Operation of Air Pollution Control Equipment:** The owner/operator shall maintain and operate all air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions.
- W. **Transfer of Permit to Construct:** The holder of a permit to construct may not transfer such permit without prior approval from the Department.
- X. **Right of Entry:** Any duly authorized officer, employee or agent of the North Dakota Department of Environmental Quality may enter and inspect any property, premise or place at which the source listed in Item I.B of this permit is located at any time for the purpose of ascertaining the state of compliance with the North Dakota Air Pollution Control Rules. The Department may conduct tests and take samples of air contaminants, fuel, processing material, and other materials which affect or may affect emissions of air contaminants from any source. The Department shall have the right to access and copy any records required by the Department's rules and to inspect monitoring equipment located on the premises.


- Y. **Other Regulations:** The owner/operator of the source unit(s) described in Item I.B of this permit shall comply with all State and Federal environmental laws and rules. In addition, the owner/operator shall comply with all local burning, fire, zoning, and other applicable ordinances, codes, rules and regulations.
- Z. **Permit Issuance:** This permit is issued in reliance upon the accuracy and completeness of the information set forth in the application. Notwithstanding the tentative nature of this information, the conditions of this permit herein become, upon the effective date of this permit, enforceable by the Department pursuant to any remedies it now has, or may in the future have, under the North Dakota Air Pollution Control Law, NDCC Chapter 23.1-06.
- AA. **Odor Restrictions:** The owner/operator shall not discharge into the ambient air any objectionable odorous air contaminant which is in excess of the limits established in NDAC 33.1-15-16.

The owner/operator shall not discharge into the ambient air hydrogen sulfide (H₂S) in concentrations that would be objectionable on land owned or leased by the complainant or in areas normally accessed by the general public. For the purpose of complaint resolution, two samples with concentrations greater than 0.05 parts per million (50 parts per billion) sampled at least 15 minutes apart within a two-hour period and measured in accordance with Section 33.1-15-16-04 constitute a violation.

- BB. **Sampling and Testing:** The Department may require the owner/operator to conduct tests to determine the emission rate of air contaminants from the source. The Department may observe the testing and may specify testing methods to be used. A signed copy of the test results shall be furnished to the Department within 60 days of the test date. The basis for this condition is NDAC 33.1-15-01-12 which is hereby incorporated into this permit by reference. To facilitate preparing for and conducting such tests, and to facilitate reporting the test results to the Department, the owner/operator shall follow the procedures and formats in the Department's Emission Testing Guideline.

FOR THE NORTH DAKOTA DEPARTMENT
OF ENVIRONMENTAL QUALITY

Date 4/24/20

By 
James L. Semerad
Director
Division of Air Quality



April 7, 2020

OE2 North LLC
Attn: Trent Taylor
1200 17th St., Suite 900
Denver, CO 80202

LU-0040-20 Trent Taylor, on behalf of OE2 North, LLC, is requesting a Zone Change to Heavy Industrial and a Conditional Use Permit for a gas processing facility. The property is approximately 140-acres located in Lots 3 and 4 E/2SE/4 of Section 27, T154N R104W. The property is currently zoned Agricultural. Round Prairie Township.

Dear Applicant:

On April 7, 2020, the Williams County Board of County Commissioners granted this request provided you comply with the following special conditions and restrictions:

1. 49th Street must be constructed to 2015 Williams County Design Standards for Township Roads "Off-System" from County Road 5 to the project location. The construction plans must be approved by Williams County Highway Department. Additional Roadway Easements may be needed. A turn-around of at least 80' diameter will be needed at the end of 49th Street. Storm water management plan (SWMP) approved by Williams County Water Resource District Board will be required. Williams County will not be responsible for construction, repair or maintenance, including snow removal for 49th Street.
2. A Storm Water Management Plan (SWMP), approved by Williams County Water Resource District Board, will be required.
3. Adhere to NDCC and Williams County Ordinance.
4. Adhere to State requirements and regulations, when applicable.
5. Adequate utilities, access roads, drainage and other necessary site improvements will be provided prior to the conditional use being initiated.
6. Adequate measures will be taken to provide ingress and egress so designed as to minimize traffic.
7. The applicant shall develop a road agreement in regard to road maintenance of 49th St NW.

Please contact the Planning and Zoning Division should you have any questions or concerns.

Thank you,

Kameron Hymer
Development Services Director

Development Services

P.O. Box 2047 | 206 E Broadway, Williston, ND 58802 | (701) 577-4565 | planning@co.williams.nd.us

County of Williams,
ND

206 E Broadway
Williston, ND 58801

Ph: (701) 577-4565

New Building Permit (C)

#20-000075

Project Description: New Residue Compressor Building 58(W)
X 362(L) X 31(T)

Issued on: 06/19/2020 at 11:41 AM by: Melissa Christensen



ADDRESS

15535 49th Street NW,
Williston, ND 58801

LEGAL

Sec 27 E2se L3(31.72)
L4(31.56) T154 R104
#831623

PERMIT HOLDER

Will Sullivan
OEll North LLC
(720) 638-7312

OWNERS

- Anderson Beau D &
Anderson, Amber D

INSPECTIONS

11

- | | |
|-------------------------------------|----------------------------|
| 1. Building Footing (C) | 7. Fire Inspection (C) |
| 2. Building Footing (C) - 1 | 8. Building Insulation (C) |
| 3. Building Foundation Wall (C) | 9. Building Final (C) |
| 4. Building Foundation Wall (C) - 1 | 10. Fire Final (C) |
| 5. Building Framing (C) | 11. Public Works Final (C) |
| 6. Building Framing (C) - 1 | |

INFORMATION FIELDS

Parcel ID #	59154040027010
Project Valuation	2089382.00
Contractor Name	ZAP Engineering & Construction Services
ND License #	55074
Mailing Address	333 S. Allison Parkway, Ste. 100, Lakewood CO 80226
Phone Number	(720) 644-3417
Email	fischers@zapecs.com
Copies of Plans	1 - Residue Compressor Scope.pdf
Site Plan	1 - Application.pdf
Applicant Certification	Yes

FEE	TOTAL	PAID	DUE
Building Permit Fee	\$ 8,357.53	\$ 8,357.53	\$ 8,357.53
(C) Project Plan Review Fee (25% of BPF)	\$ 2,089.38	\$ 2,089.38	\$ 2,089.38
TOTALS	\$ 10,446.91	\$ 10,446.91	\$ 0.00



The granting of this permit does not presume to give authority to violate or cancel the provisions of City, State, or other local laws regulating construction or the performance of construction. All provisions, laws, and ordinances governing this type of work shall be complied with, whether specified or not and shall be enforced at any and all times.

County of Williams,
ND

206 E Broadway
Williston, ND 58801

Ph: (701) 577-4565

New Building Permit (C)

#20-000076

Project Description: New Propane Compressor Building 52(W)
X 80(L) X 30(T)

Issued on: 06/19/2020 at 12:30 PM by: Melissa Christensen



ADDRESS

15535 49th Street NW,
Williston, ND 58801

LEGAL

Sec 27 E2se L3(31.72)
L4(31.56) T154 R104
#831623

PERMIT HOLDER

Will Sullivan
OEll North LLC
(720) 638-7312

OWNERS

- Anderson Beau D &
Anderson, Amber D

INSPECTIONS

11

- | | |
|-------------------------------------|----------------------------|
| 1. Building Footing (C) | 7. Fire Inspection (C) |
| 2. Building Footing (C) - 1 | 8. Building Insulation (C) |
| 3. Building Foundation Wall (C) | 9. Building Final (C) |
| 4. Building Foundation Wall (C) - 1 | 10. Fire Final (C) |
| 5. Building Framing (C) | 11. Public Works Final (C) |
| 6. Building Framing (C) - 1 | |

INFORMATION FIELDS

Parcel ID #	59154040027010
Project Valuation	685739.00
Contractor Name	ZAP Engineering & Construction Services
ND License #	55074
Mailing Address	333 S. Allison Parkway, Ste. 100, Lakewood CO 80226
Phone Number	(720) 644-3417
Email	fischers@zapecs.com
Copies of Plans	1 - Propane Compressor Scope.pdf
Site Plan	1 - Application.pdf
Applicant Certification	Yes

FEE	TOTAL	PAID	DUE
Building Permit Fee	\$ 2,742.96	\$ 2,742.96	\$ 2,742.96
(C) Project Plan Review Fee (25% of BPF)	\$ 685.74	\$ 685.74	\$ 685.74
TOTALS	\$ 3,428.70	\$ 3,428.70	\$ 0.00



The granting of this permit does not presume to give authority to violate or cancel the provisions of City, State, or other local laws regulating construction or the performance of construction. All provisions, laws, and ordinances governing this type of work shall be complied with, whether specified or not and shall be enforced at any and all times.

**County of Williams,
ND**

206 E Broadway
Williston, ND 58801

Ph: (701) 577-4565

New Building Permit (C)

#20-000077

Project Description: New Controls & Maintenance Building
2,600 sq ft

Issued on: 06/19/2020 at 11:38 AM by: Melissa Christensen



ADDRESS

15535 49th Street NW,
Williston, ND 58801

LEGAL

Sec 27 E2se L3(31.72)
L4(31.56) T154 R104
#831623

PERMIT HOLDER

Will Sullivan
OEll North LLC
(720) 638-7312

OWNERS

- Anderson Beau D &
Anderson, Amber D

INSPECTIONS

11

- | | |
|-------------------------------------|----------------------------|
| 1. Building Footing (C) | 7. Fire Inspection (C) |
| 2. Building Footing (C) - 1 | 8. Building Insulation (C) |
| 3. Building Foundation Wall (C) | 9. Building Final (C) |
| 4. Building Foundation Wall (C) - 1 | 10. Fire Final (C) |
| 5. Building Framing (C) | 11. Public Works Final (C) |
| 6. Building Framing (C) - 1 | |

INFORMATION FIELDS

Parcel ID #	59154040027010
Project Valuation	920988
Contractor Name	ZAP Engineering & Construction Services
ND License #	55074
Mailing Address	333 S. Allison Parkway, Ste. 100, Lakewood CO 80226
Phone Number	(720) 644-3417
Email	fischers@zapecs.com
Copies of Plans	1 - Controls Building Scope.pdf
Site Plan	1 - Application.pdf
Applicant Certification	Yes

FEE	TOTAL	PAID	DUE
Building Permit Fee	\$ 3,683.95	\$ 3,683.95	\$ 3,683.95
(C) Project Plan Review Fee (25% of BPF)	\$ 920.99	\$ 920.99	\$ 920.99
TOTALS	\$ 4,604.94	\$ 4,604.94	\$ 0.00



The granting of this permit does not presume to give authority to violate or cancel the provisions of City, State, or other local laws regulating construction or the performance of construction. All provisions, laws, and ordinances governing this type of work shall be complied with, whether specified or not and shall be enforced at any and all times.