

Observations

Portions of the Project occurring in range or pasture land had approximately 80-100% ground cover.

Recommendations

1. Continual maintenance should be done to encourage the revegetation of desirable species.

Conclusion

Overall, the Project appeared to be constructed as designed with minimal impacts to the surrounding environment. The Project site is in good condition and is well maintained. The Project is as near as practical to preconstruction conditions.


Conclusions

Overall, the Project appeared to be constructed as designed with minimal impacts to the surrounding environment. The Project site was in good condition, well maintained, and appeared to be constructed in compliance with the siting laws, siting rules, and applicable Commission Orders. The Project is as near as practical to preconstruction conditions with the exceptions of some BMPs still in place.

Management Review

The services performed by Keitu and its staff for this project have been conducted in a manner consistent with the degree of care and technical skill appropriately exercised by professionals currently practicing in this area under similar time and budget constraints.

Recommendations and findings contained in this report represent our professional judgment and are based upon available information and technically accepted practices at the present time and location. Other than this, no warranty is implied or expressed.


Jaimee Antognazzi, Operations Manager

10/18/23