

August 17, 2023

RECEIVED

AUG 21 2023

Amy Haugen
Administrative Services
North Dakota Public Service Commission
600 East Boulevard Ave., Dept. 408
Bismarck, ND 58505-0480

NORTH DAKOTA
PUBLIC SERVICE COMMISSION

Re: Project Code: PU-23-252, Otter Tail Power Company, Ashtabula 1 Wind Upgrade Siting
App in Barnes County

Dear Ms. Haugen:

The North Dakota Department of Environmental Quality has reviewed the information concerning the above-referenced project received at the department on August 7, 2023, with respect to possible environmental impacts.

1. Care is to be taken during construction activity near any water of the state to minimize adverse effects on a water body. This includes minimal disturbance of stream beds and banks to prevent excess siltation, and the replacement and revegetation of any disturbed area as soon as possible after work has been completed. Caution must also be taken to prevent spills of oil and grease that may reach the receiving water from equipment maintenance and/or the handling of fuels on the site. Guidelines for minimizing degradation to waterways during construction are attached.

2. Projects disturbing one or more acres are required to have a permit to discharge stormwater runoff until the site is stabilized by the re-establishment of vegetation or other permanent cover. Further information on the stormwater permit may be obtained from the department's website or by calling the Division of Water Quality at 701-328-5210. Also, cities may impose additional requirements and/or specific best management practices for construction affecting their storm drainage system. Check with the local officials to be sure any local stormwater management considerations are addressed.

3. All solid waste materials must be managed and transported in accordance with the state's solid and hazardous waste rules. Appropriate efforts to reduce, reuse and/or recycle waste materials are strongly encouraged. As appropriate, segregation of inert waste from non-inert waste can generally reduce the cost of waste management. Wind turbine blades are prohibited from landfill disposal in North Dakota unless approved by the department in accordance with Subsection 23.1-08-08(2) of the Solid Waste Management and Land Protection Law. Further information on waste management and recycling is available from the department's Division of Waste Management at 701-328-5166.

16 PU-23-252 Filed: 8/21/2023 Pages: 3
 Agency Correspondence
 North Dakota Department of Environmental Quality (DEQ)
 L. David Glatt, P.E., Director

4. Polychlorinated Biphenyls, commonly referred to as PCBs, can be found in electrical equipment older than 1980. Projects that involve the removal of fluid-filled electrical equipment, heat transfer equipment, older fluorescent lights, caulks and paints must ensure that all materials are PCB free. Any PCB-containing waste must be handled, stored, and disposed of appropriately. Questions on proper PCB management may be directed to the Hazardous Waste Program at 701-328-5166.

The department owns no land in or adjacent to the proposed improvements, nor does it have any projects scheduled in the area. In addition, we believe the proposed activities are consistent with the State Implementation Plan for the Control of Air Pollution for the State of North Dakota.

If you have any questions regarding our comments, please feel free to contact this office.

Sincerely,



L. David Glatt, P.E., Director
North Dakota Department of Environmental Quality

LDG:ll
Attach.

Construction and Environmental Disturbance Requirements

The following are the minimum requirements of the North Dakota Department of Environmental Quality for projects that involve construction and environmental disturbance in or near waters of the State of North Dakota. They ensure that minimal environmental degradation occurs as a result of construction or related work which has the potential to affect waters of the state. All projects must be constructed to minimize the loss of soil, vegetative cover, and pollutants (chemical or biological) from a site.

Soils

Prevent the erosion and sediment loss using erosion and sediment controls. Fragile and sensitive areas such as wetlands, riparian zones, delicate flora, and land resources must be prohibited against compaction, vegetation loss and unnecessary damage.

Surface Waters

All construction must be managed to minimize impacts to aquatic systems. Follow safe storage and handling procedures to prevent the contamination of water from fuel spills, lubricants, and chemicals. Stream bank and stream bed disturbances must be contained to minimize silt movement, nutrient upsurges, plant dislocations, and any physical chemicals, or biological disruption. The use of pesticides or herbicides in or near surface waters is allowed under the department's pesticide application permit with notification to the department.

Fill Material

Any fill material placed below the ordinary high-water mark must be free of topsoil, decomposable materials, and persistent synthetic organic compounds; including, but not limited to, asphalt, tires, treated lumber, and construction debris. The department may require testing of fill material. All temporary fills must be removed. Debris and solid waste must be properly disposed or recycled. Impacted areas must be restored to near original condition.