

April 1, 2026

Geri Schmaltz
 Administrative Officer
 North Dakota Public Service Commission
 600 East Boulevard Ave., Dept. 408
 Bismarck, ND 58505-0480

Re: Longspur Wind Project – 230kV Transmission Line in Mercer and Morton Counties

Dear Ms. Schmaltz:

The North Dakota Department of Environmental Quality (Department) has reviewed the information concerning the above-referenced project received at the Department on March 9, 2026, with respect to possible environmental impacts.

1. Necessary measures should be taken to minimize fugitive dust emissions created during construction activities. Any complaints that may arise should be dealt with in an efficient and effective manner.
2. Care is to be taken during construction activity near any water of the state to minimize adverse effects on a water body. This includes minimal disturbance of stream beds and banks to prevent excess siltation, and the replacement and revegetation of any disturbed area as soon as possible after work has been completed. Caution must also be taken to prevent spills of oil and grease that may reach the receiving water from equipment maintenance and/or the handling of fuels on the site. Guidelines for minimizing degradation to waterways during construction are attached.
3. Projects disturbing one or more acres are required to have a permit to discharge stormwater runoff until the site is stabilized by the re-establishment of vegetation or other permanent cover. Further information on the stormwater permit may be obtained from the Department’s website or by calling the Division of Water Quality at 701-328-5210. Check with the local officials to be sure any local stormwater management considerations are addressed. Stormwater runoff from the project area discharges to a water body listed as impaired under Section 303(d) of the Federal Clean Water Act (Wilson Creek watershed [Assessment Unit ND-10130203-046-S_00]) and a water body with an alternative restoration plan (Hailstone Creek [Assessment Unit ND-10130203-041-S_00]). Extra care should be taken to ensure construction activity does not affect the water bodies.
4. All solid waste materials must be managed and transported in accordance with the state’s solid and hazardous waste rules. Appropriate efforts to reduce, reuse and/or recycle waste materials are strongly encouraged. As appropriate, segregation of inert waste from non-inert

25 PU-25-305 Filed 04/07/2026 Pages: 3
 Agency Correspondence
 North Dakota Department of Environmental Quality (DEQ)
 Karl Rockeman, P.E., Deputy Director
 25 PU-25-304 Filed 04/07/2026 Pages: 3
 Agency Correspondence
 North Dakota Department of Environmental Quality (DEQ)
 Karl Rockeman, P.E., Deputy Director

waste can generally reduce the cost of waste management. Further information on waste management and recycling is available from the Department's Division of Waste Management at 701-328-5166.

The Department owns no land in or adjacent to the proposed improvements, nor does it have any projects scheduled in the area. In addition, we believe the proposed activities are consistent with the State Implementation Plan for the Control of Air Pollution for the State of North Dakota.

If you have any questions regarding our comments, please feel free to contact this office.

Sincerely,

A handwritten signature in blue ink, appearing to read 'Karl Rockeman', with a stylized flourish at the end.

Karl Rockeman, P.E., Deputy Director
North Dakota Department of Environmental Quality

KR:ll
Attach.

Construction and Environmental Disturbance Requirements

The following are the minimum requirements of the North Dakota Department of Environmental Quality (Department) for projects that involve construction and environmental disturbance in or near waters of the State of North Dakota. They ensure that minimal environmental degradation occurs as a result of construction or related work which has the potential to affect waters of the state. All projects must be constructed to minimize the loss of soil, vegetative cover, and pollutants (chemical or biological) from a site.

Soils

Prevent the erosion and sediment loss using erosion and sediment controls. Fragile and sensitive areas such as wetlands, riparian zones, delicate flora, and land resources must be prohibited against compaction, vegetation loss and unnecessary damage.

Surface Waters

All construction must be managed to minimize impacts to aquatic systems. Follow safe storage and handling procedures to prevent the contamination of water from fuel spills, lubricants, and chemicals. Stream bank and stream bed disturbances must be contained to minimize silt movement, nutrient upsurges, plant dislocations, and any physical chemicals, or biological disruption. The use of pesticides or herbicides in or near surface waters is allowed under the Department's pesticide application permit with notification to the Department.

Fill Material

Any fill material placed below the ordinary high-water mark must be free of topsoil, decomposable materials, and persistent synthetic organic compounds, including, but not limited to, asphalt, tires, treated lumber, and construction debris. The Department may require testing of fill material. All temporary fills must be removed. Debris and solid waste must be properly disposed or recycled. Impacted areas must be restored to near original condition.